


The Hindu-Arabic Numerals


David Eugene Smith and Louis Charles

The background of the lower half of the image is a solid magenta color. Overlaid on this background is a complex, abstract pattern of white geometric shapes. These shapes include straight lines of varying lengths and orientations, right-angled corners, semi-circular arcs, and triangles of different sizes and orientations. Some of these shapes are solid white, while others are outlines. The pattern is dense and non-repeating, creating a modern, geometric aesthetic.

Project Gutenberg

The Hindu-Arabic Numerals

David Eugene Smith and Louis Charles



Project Gutenberg

The Project Gutenberg eBook of The Hindu-Arabic Numerals

This eBook is for the use of anyone anywhere in the United States and most other parts of the world at no cost and with almost no restrictions whatsoever. You may copy it, give it away or re-use it under the terms of the Project Gutenberg License included with this eBook or online at www.gutenberg.org. If you are not located in the United States, you will have to check the laws of the country where you are located before using this eBook.

Title: The Hindu-Arabic Numerals

Author: David Eugene Smith
Louis Charles Karpinski

Release date: September 14, 2007 [eBook #22599]
Most recently updated: January 2, 2021

Language: English

Other information and formats: www.gutenberg.org/ebooks/22599

Credits: Produced by David Newman, Chuck Greif, Keith Edkins and the Online Distributed Proofreading Team at <https://www.pgdp.net> (This file was produced from images from the Cornell University Library: Historical Mathematics Monographs collection.)

*** START OF THE PROJECT GUTENBERG EBOOK THE HINDU-ARABIC
NUMERALS ***

Transcriber's note: Sections in Greek or Hebrew will yield a transliteration when the pointer is moved over them, and words using diacritic characters in the Latin Extended Additional block, which may not display in some fonts or browsers, will display an unaccented version.

THE

HINDU-ARABIC NUMERALS

BY
DAVID EUGENE SMITH
AND
LOUIS CHARLES KARPINSKI

BOSTON AND LONDON
GINN AND COMPANY, PUBLISHERS
1911

COPYRIGHT, 1911, BY DAVID EUGENE SMITH
AND LOUIS CHARLES KARPINSKI
ALL RIGHTS RESERVED
811.7

The Athenæum Press
GINN AND COMPANY · PROPRIETORS
BOSTON · U.S.A.

PREFACE

So familiar are we with the numerals that bear the misleading name of Arabic, and so extensive is their use in Europe and the Americas, that it is difficult for us to realize that their general acceptance in the transactions of commerce is a matter of only the last four centuries, and that they are unknown to a very large part of the human race to-day. It seems strange that such a labor-saving device should have struggled for nearly a thousand years after its system of place value was perfected before it replaced such crude notations as the one that the Roman conqueror made substantially universal in Europe. Such, however, is the case, and there is probably no one who has not at least some slight passing interest in the story of this struggle. To the mathematician and the student of civilization the interest is generally a deep one; to the teacher of the elements of knowledge the interest may be less marked, but nevertheless it is real; and even the business man who makes daily use of the curious symbols by which we express the numbers of commerce, cannot fail to have some appreciation for the story of the rise and progress of these tools of his trade.

This story has often been told in part, but it is a long time since any effort has been made to bring together the fragmentary narrations and to set forth the general problem of the origin and development of these numerals. In this little work we have attempted to state the history of these forms in small compass, to place before the student materials for the

investigation of the problems involved, and to express as clearly as possible the results of the labors of scholars who have studied the subject in different parts of the world. We have had no theory to exploit, for the history of mathematics has seen too much of this tendency already, but as far as possible we have weighed the testimony and have set forth what seem to be the reasonable conclusions from the evidence at hand.

To facilitate the work of students an index has been prepared which we hope may be serviceable. In this the names of authors appear only when some use has been made of their opinions or when their works are first mentioned in full in a footnote.

If this work shall show more clearly the value of our number system, and shall make the study of mathematics seem more real to the teacher and student, and shall offer material for interesting some pupil more fully in his work with numbers, the authors will feel that the considerable labor involved in its preparation has not been in vain.

We desire to acknowledge our especial indebtedness to Professor Alexander Ziwet for reading all the proof, as well as for the digest of a Russian work, to Professor Clarence L. Meader for Sanskrit transliterations, and to Mr. Steven T. Byington for Arabic transliterations and the scheme of pronunciation of Oriental names, and also our indebtedness to other scholars in Oriental learning for information.

DAVID EUGENE SMITH
LOUIS CHARLES KARPINSKI

CONTENTS

CHAPTER

PRONUNCIATION OF ORIENTAL NAMES [vi](#)

I. EARLY IDEAS OF THEIR ORIGIN [1](#)

II. EARLY HINDU FORMS WITH NO PLACE VALUE [12](#)

III. LATER HINDU FORMS, WITH A PLACE VALUE [38](#)

IV. THE SYMBOL ZERO [51](#)

V. THE QUESTION OF THE INTRODUCTION OF THE NUMERALS INTO EUROPE BY BOETHIUS [63](#)

VI. THE DEVELOPMENT OF THE NUMERALS AMONG THE ARABS [91](#)

VII. THE DEFINITE INTRODUCTION OF THE NUMERALS INTO EUROPE [99](#)

PRONUNCIATION OF ORIENTAL NAMES

(S) = in Sanskrit names and words; (A) = in Arabic names and words.

b, d, f, g, h, j, l, m, n, p, sh (A), **t, th** (A), **v, w, x, z**, as in English.

a, (S) like *u* in *but*: thus *pandit*, pronounced *pundit*. (A) like *a* in *ask* or in *man*. **ā**, as in *father*.

c, (S) like *ch* in *church* (Italian *c* in *cento*).

ḍ, ṇ, ṣ, ṭ, (S) *d, n, sh, t*, made with the tip of the tongue turned up and back into the dome of the palate. **ḍ, ṣ, ṭ, ṣ**, (A) *d, s, t, z*, made with the tongue spread so that the sounds are produced largely against the side teeth. Europeans commonly pronounce **ḍ, ṇ, ṣ, ṭ, ṣ**, both (S) and (A), as simple *d, n, sh* (S) or *s* (A), *t, z*. **ḍ** (A), like *th* in *this*.

e, (S) as in *they*. (A) as in *bed*.

ġ, (A) a voiced consonant formed below the vocal cords; its sound is compared by some to a *g*, by others to a guttural *r*; in Arabic words adopted into English it is represented by *gh* (e.g. *ghoul*), less often *r* (e.g. *razzia*).

h preceded by *b, c, t, ṭ*, etc. does not form a single sound with these letters, but is a more or less distinct *h* sound following them; cf. the sounds in *abhor, boathook*, etc., or, more accurately for (S), the "bhoy's" etc. of Irish brogue. **h** (A) retains its consonant sound at the end of a word. **ḥ**, (A) an unvoiced consonant formed below the vocal cords; its sound is sometimes compared to German hard *ch*, and may be represented by an *h* as strong as possible. In Arabic words adopted into English it is represented by *h*, e.g. in *sahib, hakeem*. **ḥ** (S) is final consonant *h*, like final *h* (A).

i, as in *pin*. **ī**, as in *pique*.

k, as in *kick*.

kh, (A) the hard *ch* of Scotch *loch*, German *ach*, especially of German as pronounced by the Swiss.

m̄, n̄, (S) like French final *m* or *n*, nasalizing the preceding vowel.

ṇ, see **ḍ**. **ñ**, like *ng* in *singing*.

o, (S) as in *so*. (A) as in *obey*.

q, (A) like *k* (or *c*) in *cook*; further back in the mouth than in *kick*.

r, (S) English *r*, smooth and untrilled. (A) stronger. **ṛ**, (S) *r* used as vowel, as in *apron* when pronounced *aprn* and not *apern*; modern Hindus say *ri*, hence our *amrita*, *Krishna*, for *a-mṛta*, *Kṛṣṇa*.

s, as in *same*. **ṣ**, see **ḍ**. **ś**, (S) English *sh* (German *sch*).

ṭ, see **ḍ**.

u, as in *put*. **ū**, as in *rule*.

y, as in *you*.

z, see **ḍ**.

‘, (A) a sound kindred to the spiritus lenis (that is, to our ears, the mere distinct separation of a vowel from the preceding sound, as at the beginning of a word in German) and to *h*. The **‘** is a very distinct sound in Arabic, but is more nearly represented by the spiritus lenis than by any sound that we can produce without much special training. That is, it should be treated as silent, but the sounds that precede and follow it should not run together. In Arabic words adopted into English it is treated as silent, e.g. in *Arab*, *amber*, *Caaba* (*‘Arab*, *‘anbar*, *ka‘abah*).

(A) A final long vowel is shortened before *al* (*‘l*) or *ibn* (whose *i* is then silent).

Accent: (S) as if Latin; in determining the place of the accent *ṁ* and *ṅ* count as consonants, but *h* after another consonant does not. (A), on the last syllable that contains a long vowel or a vowel followed by two consonants, except that a final long vowel is not ordinarily accented; if there is no long vowel nor two consecutive consonants, the accent falls on the first syllable. The words *al* and *ibn* are never accented.

THE HINDU-ARABIC NUMERALS

CHAPTER I

EARLY IDEAS OF THEIR ORIGIN

It has long been recognized that the common numerals used in daily life are of comparatively recent origin. The number of systems of notation employed before the Christian era was about the same as the number of written languages, and in some cases a single language had several systems. The Egyptians, for example, had three systems of writing, with a numerical notation for each; the Greeks had two well-defined sets of numerals, and the Roman symbols for number changed more or less from century to century. Even to-day the number of methods of expressing numerical concepts is much greater than one would believe before making a study of the subject, for the idea that our common numerals are universal is far from being correct. It will be well, then, to think of the numerals that we still commonly call Arabic, as only one of many systems in use just before the Christian era. As it then existed the system was no better than many others, it was of late origin, it contained no zero, it was cumbersome and little used, and it had no particular promise. Not until centuries later did the system have any standing in the world of business and science; and had the place value which now characterizes it, and which requires a zero, been worked out in Greece, we might have been using Greek numerals to-day instead of the ones with which we are familiar.

Of the first number forms that the world used this is not the place to speak. Many of them are interesting, but none had much scientific value. In Europe the invention of notation was generally assigned to the eastern shores of the Mediterranean until the critical period of about a century ago,—sometimes to the Hebrews, sometimes to the Egyptians, but more often to the early trading Phœnicians.^[1]

The idea that our common numerals are Arabic in origin is not an old one. The mediæval and Renaissance writers generally recognized them as Indian, and many of them expressly stated that they were of Hindu origin.^[2] Others argued that they were probably invented by the Chaldeans or the Jews because they increased in value from right to left, an argument that would apply quite as well to the Roman and Greek systems, or to any other. It was, indeed, to the general idea of notation that many of these writers referred, as is evident from the words of England's earliest arithmetical textbook-maker, Robert Recorde (c. 1542): "In that thinge all men do agree, that the Chaldays, whiche fyrste inuented thys arte, did set these figures as thei set all their letters. for they wryte backwarde as you tearme it, and so doo they reade. And that may appeare in all Hebrewes, Chaldaye and Arabike bookes ... where as the Greekes, Latines, and all nations of Europe, do wryte and reade from the lefte hand towarde the ryghte."^[3] Others, and among them such influential writers as Tartaglia^[4] in Italy and Köbel^[5] in Germany, asserted the Arabic origin of the

numerals, while still others left the matter undecided^[6] or simply dismissed them as "barbaric."^[7] Of course the Arabs themselves never laid claim to the invention, always recognizing their indebtedness to the Hindus both for the numeral forms and for the distinguishing feature of place value. Foremost among these writers was the great master of the golden age of Bagdad, one of the first of the Arab writers to collect the mathematical classics of both the East and the West, preserving them and finally passing them on to awakening Europe. This man was Moḥammed the Son of Moses, from Khowārezm, or, more after the manner of the Arab, Moḥammed ibn Mūsā al-Khowārazmī,^[8] a man of great learning and one to whom the world is much indebted for its present knowledge of algebra^[9] and of arithmetic. Of him there will often be occasion to speak; and in the arithmetic which he wrote, and of which Adelhard of Bath^[10] (c. 1130) may have made the translation or paraphrase,^[11] he stated distinctly that the numerals were due to the Hindus.^[12] This is as plainly asserted by later Arab writers, even to the present day.^[13] Indeed the phrase *'ilm hindī*, "Indian science," is used by them for arithmetic, as also the adjective *hindī* alone.^[14]

Probably the most striking testimony from Arabic sources is that given by the Arabic traveler and scholar Mohammed ibn Aḥmed, Abū 'l-Rīḥān al-Bīrūnī (973-1048), who spent many years in Hindustan. He wrote a large work on India,^[15] one on ancient chronology,^[16] the "Book of the Ciphers," unfortunately lost, which treated doubtless of the Hindu art of calculating, and was the author of numerous other works. Al-Bīrūnī was a man of unusual attainments, being versed in Arabic, Persian, Sanskrit, Hebrew, and Syriac, as well as in astronomy, chronology, and mathematics. In his work on India he gives detailed information concerning the language and customs of the people of that country, and states explicitly^[17] that the Hindus of his time did not use the letters of their alphabet for numerical notation, as the Arabs did. He also states that the numeral signs called *anka*^[18] had different shapes in various parts of India, as was the case with the letters. In his *Chronology of Ancient Nations* he gives the sum of a geometric progression and shows how, in order to avoid any possibility of error, the number may be expressed in three different systems: with Indian symbols, in sexagesimal notation, and by an alphabet system which will be touched upon later. He also speaks^[19] of "179, 876, 755, expressed in Indian ciphers," thus again attributing these forms to Hindu sources.

Preceding Al-Bīrūnī there was another Arabic writer of the tenth century, Moṭahhar ibn Ṭāhir,^[20] author of the *Book of the Creation and of History*, who gave as a curiosity, in Indian (Nāgarī) symbols, a large number asserted by the people of India to represent the duration of the world. Huart feels positive that in Moṭahhar's time the present Arabic symbols had not yet come into use, and that the Indian symbols, although known to scholars, were not current. Unless this were the case, neither the author nor his readers would have found anything extraordinary in the appearance of the number which he cites.

Mention should also be made of a widely-traveled student, Al-Mas'ūdī (885?-956), whose journeys carried him from Bagdad to Persia, India, Ceylon, and even across the China sea,

and at other times to Madagascar, Syria, and Palestine.^[21] He seems to have neglected no accessible sources of information, examining also the history of the Persians, the Hindus, and the Romans. Touching the period of the Caliphs his work entitled *Meadows of Gold* furnishes a most entertaining fund of information. He states^[22] that the wise men of India, assembled by the king, composed the *Sindhind*. Further on^[23] he states, upon the authority of the historian Moḥammed ibn 'Alī 'Abdī, that by order of Al-Manṣūr many works of science and astrology were translated into Arabic, notably the *Sindhind* (*Siddhānta*). Concerning the meaning and spelling of this name there is considerable diversity of opinion. Colebrooke^[24] first pointed out the connection between *Siddhānta* and *Sindhind*. He ascribes to the word the meaning "the revolving ages."^[25] Similar designations are collected by Sédillot,^[26] who inclined to the Greek origin of the sciences commonly attributed to the Hindus.^[27] Casiri,^[28] citing the *Tārīkh al-ḥokamā* or *Chronicles of the Learned*,^[29] refers to the work as the *Sindum-Indum* with the meaning "perpetuum æternumque." The reference^[30] in this ancient Arabic work to Al-Khowārazmī is worthy of note.

This *Sindhind* is the book, says Mas'ūdī,^[31] which gives all that the Hindus know of the spheres, the stars, arithmetic,^[32] and the other branches of science. He mentions also Al-Khowārazmī and Ḥabash^[33] as translators of the tables of the *Sindhind*. Al-Bīrūnī^[34] refers to two other translations from a work furnished by a Hindu who came to Bagdad as a member of the political mission which Sindh sent to the caliph Al-Manṣūr, in the year of the Hejira 154 (A.D. 771).

The oldest work, in any sense complete, on the history of Arabic literature and history is the *Kitāb al-Fihrist*, written in the year 987 A.D., by Ibn Abī Ya'qūb al-Nadīm. It is of fundamental importance for the history of Arabic culture. Of the ten chief divisions of the work, the seventh demands attention in this discussion for the reason that its second subdivision treats of mathematicians and astronomers.^[35]

The first of the Arabic writers mentioned is Al-Kindī (800-870 A.D.), who wrote five books on arithmetic and four books on the use of the Indian method of reckoning. Sened ibn 'Alī, the Jew, who was converted to Islam under the caliph Al-Māmūn, is also given as the author of a work on the Hindu method of reckoning. Nevertheless, there is a possibility^[36] that some of the works ascribed to Sened ibn 'Alī are really works of Al-Khowārazmī, whose name immediately precedes his. However, it is to be noted in this connection that Casiri^[37] also mentions the same writer as the author of a most celebrated work on arithmetic.

To Al-Šūfī, who died in 986 A.D., is also credited a large work on the same subject, and similar treatises by other writers are mentioned. We are therefore forced to the conclusion that the Arabs from the early ninth century on fully recognized the Hindu origin of the new numerals.

Leonard of Pisa, of whom we shall speak at length in the chapter on the Introduction of the Numerals into Europe, wrote his *Liber Abbaci*^[38] in 1202. In this work he refers frequently to the nine Indian figures,^[39] thus showing again the general consensus of opinion in the Middle Ages that the numerals were of Hindu origin.

Some interest also attaches to the oldest documents on arithmetic in our own language. One of the earliest treatises on algorism is a commentary^[40] on a set of verses called the *Carmen de Algorismo*, written by Alexander de Villa Dei (Alexandra de Ville-Dieu), a Minorite monk of about 1240 A.D. The text of the first few lines is as follows:

"Hec algorism' ars p'sens dicit' in qua
Talib; indorꝝ fruim bis quinq; figuris."^[41]

"This boke is called the boke of algorim or augrym after lewder use. And this boke tretys of the Craft of Nombryng, the quych crafte is called also Algorym. Ther was a kyng of Inde the quich heyth Algor & he made this craft.... Algorisms, in the quych we use teen figurys of Inde."

CHAPTER II

EARLY HINDU FORMS WITH NO PLACE VALUE

While it is generally conceded that the scientific development of astronomy among the Hindus towards the beginning of the Christian era rested upon Greek^[42] or Chinese^[43] sources, yet their ancient literature testifies to a high state of civilization, and to a considerable advance in sciences, in philosophy, and along literary lines, long before the golden age of Greece. From the earliest times even up to the present day the Hindu has been wont to put his thought into rhythmic form. The first of this poetry—it well deserves this name, being also worthy from a metaphysical point of view^[44]—consists of the Vedas, hymns of praise and poems of worship, collected during the Vedic period which dates from approximately 2000 B.C. to 1400 B.C.^[45] Following this work, or possibly contemporary with it, is the Brahmanic literature, which is partly ritualistic (the Brāhmaṇas), and partly philosophical (the Upanishads). Our especial interest is in the Sūtras, versified abridgments of the ritual and of ceremonial rules, which contain considerable geometric material used in connection with altar construction, and also numerous examples of rational numbers the sum of whose squares is also a square, i.e. "Pythagorean numbers," although this was long before Pythagoras lived. Whitney^[46] places the whole of the Veda literature, including the Vedas, the Brāhmaṇas, and the Sūtras, between 1500 B.C. and 800 B.C., thus agreeing with Bürk^[47] who holds that the knowledge of the Pythagorean theorem revealed in the Sūtras goes back to the eighth century B.C.

The importance of the Sūtras as showing an independent origin of Hindu geometry, contrary to the opinion long held by Cantor^[48] of a Greek origin, has been repeatedly emphasized in recent literature,^[49] especially since the appearance of the important work of Von Schroeder.^[50] Further fundamental mathematical notions such as the conception of irrationals and the use of gnomons, as well as the philosophical doctrine of the transmigration of souls,—all of these having long been attributed to the Greeks,—are shown in these works to be native to India. Although this discussion does not bear directly upon the origin of our numerals, yet it is highly pertinent as showing the aptitude of the Hindu for mathematical and mental work, a fact further attested by the independent development of the drama and of epic and lyric poetry.

It should be stated definitely at the outset, however, that we are not at all sure that the most ancient forms of the numerals commonly known as Arabic had their origin in India. As will presently be seen, their forms may have been suggested by those used in Egypt, or in Eastern Persia, or in China, or on the plains of Mesopotamia. We are quite in the dark as to these early steps; but as to their development in India, the approximate period of the rise of their essential feature of place value, their introduction into the Arab civilization, and their spread to the West, we have more or less definite information. When, therefore, we consider the rise of the numerals in the land of the Sindhu,^[51] it must be understood that it is only the large movement that is meant, and that there must further be considered the numerous possible sources outside of India itself and long anterior to the first prominent appearance of the number symbols.

No one attempts to examine any detail in the history of ancient India without being struck with the great dearth of reliable material.^[52] So little sympathy have the people with any save those of their own caste that a general literature is wholly lacking, and it is only in the observations of strangers that any all-round view of scientific progress is to be found. There is evidence that primary schools existed in earliest times, and of the seventy-two recognized sciences writing and arithmetic were the most prized.^[53] In the Vedic period, say from 2000 to 1400 B.C., there was the same attention to astronomy that was found in the earlier civilizations of Babylon, China, and Egypt, a fact attested by the Vedas themselves.^[54] Such advance in science presupposes a fair knowledge of calculation, but of the manner of calculating we are quite ignorant and probably always shall be. One of the Buddhist sacred books, the *Lalitavistara*, relates that when the Bōdhisattva^[55] was of age to marry, the father of Gopa, his intended bride, demanded an examination of the five hundred suitors, the subjects including arithmetic, writing, the lute, and archery. Having vanquished his rivals in all else, he is matched against Arjuna the great arithmetician and is asked to express numbers greater than 100 kotis.^[56] In reply he gave a scheme of number names as high as 10^{53} , adding that he could proceed as far as 10^{421} ,^[57] all of which suggests the system of Archimedes and the unsettled question of the indebtedness of the West to the East in the realm of ancient mathematics.^[58] Sir Edwin Arnold, in *The Light of Asia*, does not mention this part of the contest, but he speaks of Buddha's training at the hands of the learned Viṣvamitra:

"And Viswamitra said, 'It is enough,
 Let us to numbers. After me repeat
 Your numeration till we reach the lakh,^[59]
 One, two, three, four, to ten, and then by tens
 To hundreds, thousands.' After him the child
 Named digits, decads, centuries, nor paused,
 The round lakh reached, but softly murmured on,
 Then comes the kōti, nahut, ninnahut,
 Khamba, viskhamba, abab, attata,
 To kumuds, gundhikas, and utpalas,
 By pundarīkas into padumas,
 Which last is how you count the utmost grains
 Of Hastagiri ground to finest dust;^[60]
 But beyond that a numeration is,
 The Kātha, used to count the stars of night,
 The Kōti-Kātha, for the ocean drops;
 Ingga, the calculus of circulars;
 Sarvanikchepa, by the which you deal
 With all the sands of Gunga, till we come
 To Antah-Kalpas, where the unit is
 The sands of the ten crore Gungas. If one seeks
 More comprehensive scale, th' arithmic mounts
 By the Asankya, which is the tale
 Of all the drops that in ten thousand years
 Would fall on all the worlds by daily rain;
 Thence unto Maha Kalpas, by the which
 The gods compute their future and their past."

Thereupon Viṣvamitra Ācārya^[61] expresses his approval of the task, and asks to hear the
 "measure of the line" as far as yōjana, the longest measure bearing name. This given,
 Buddha adds:

... "And master! if it please,
 I shall recite how many sun-motes lie
 From end to end within a yōjana.'
 Thereat, with instant skill, the little prince
 Pronounced the total of the atoms true.
 But Viswamitra heard it on his face
 Prostrate before the boy; 'For thou,' he cried,
 'Art Teacher of thy teachers—thou, not I,
 Art Gūrū.'"

It is needless to say that this is far from being history. And yet it puts in charming rhythm
 only what the ancient *Lalitavistara* relates of the number-series of the Buddha's time.

While it extends beyond all reason, nevertheless it reveals a condition that would have been impossible unless arithmetic had attained a considerable degree of advancement.

To this pre-Christian period belong also the *Vedāṅgas*, or "limbs for supporting the Veda," part of that great branch of Hindu literature known as *Smṛiti* (recollection), that which was to be handed down by tradition. Of these the sixth is known as *Jyotiṣa* (astronomy), a short treatise of only thirty-six verses, written not earlier than 300 B.C., and affording us some knowledge of the extent of number work in that period.^[62] The Hindus also speak of eighteen ancient *Siddhāntas* or astronomical works, which, though mostly lost, confirm this evidence.^[63]

As to authentic histories, however, there exist in India none relating to the period before the Mohammedan era (622 A.D.). About all that we know of the earlier civilization is what we glean from the two great epics, the *Mahābhārata*^[64] and the *Rāmāyana*, from coins, and from a few inscriptions.^[65]

It is with this unsatisfactory material, then, that we have to deal in searching for the early history of the Hindu-Arabic numerals, and the fact that many unsolved problems exist and will continue to exist is no longer strange when we consider the conditions. It is rather surprising that so much has been discovered within a century, than that we are so uncertain as to origins and dates and the early spread of the system. The probability being that writing was not introduced into India before the close of the fourth century B.C., and literature existing only in spoken form prior to that period,^[66] the number work was doubtless that of all primitive peoples, palpable, merely a matter of placing sticks or cowries or pebbles on the ground, of marking a sand-covered board, or of cutting notches or tying cords as is still done in parts of Southern India to-day.^[67]

The early Hindu numerals^[68] may be classified into three great groups, (1) the Kharoṣṭhī, (2) the Brāhmī, and (3) the word and letter forms; and these will be considered in order.

The Kharoṣṭhī numerals are found in inscriptions formerly known as Bactrian, Indo-Bactrian, and Aryan, and appearing in ancient Gandhāra, now eastern Afghanistan and northern Punjab. The alphabet of the language is found in inscriptions dating from the fourth century B.C. to the third century A.D., and from the fact that the words are written from right to left it is assumed to be of Semitic origin. No numerals, however, have been found in the earliest of these inscriptions, number-names probably having been written out in words as was the custom with many ancient peoples. Not until the time of the powerful King Aśoka, in the third century B.C., do numerals appear in any inscriptions thus far discovered; and then only in the primitive form of marks, quite as they would be found in Egypt, Greece, Rome, or in various other parts of the world. These Aśoka^[69] inscriptions, some thirty in all, are found in widely separated parts of India, often on columns, and are in the various vernaculars that were familiar to the people. Two are in the Kharoṣṭhī characters, and the rest in some form of Brāhmī. In the Kharoṣṭhī inscriptions only four numerals have been found, and these are merely vertical marks for one, two, four, and five, thus:

I II III IIII

In the so-called Śaka inscriptions, possibly of the first century B.C., more numerals are found, and in more highly developed form, the right-to-left system appearing, together with evidences of three different scales of counting,—four, ten, and twenty. The numerals of this period are as follows:


1	2	3	4	5	6	8	10
I	II	III	X	IX	II X	XX	?
3	233	333	2333	2333	11	211	
20	50	60	70	100	200		

There are several noteworthy points to be observed in studying this system. In the first place, it is probably not as early as that shown in the Nānā Ghāt forms hereafter given, although the inscriptions themselves at Nānā Ghāt are later than those of the Aśoka period. The four is to this system what the X was to the Roman, probably a canceling of three marks as a workman does to-day for five, or a laying of one stick across three others. The ten has never been satisfactorily explained. It is similar to the A of the Kharoṣṭhī alphabet, but we have no knowledge as to why it was chosen. The twenty is evidently a ligature of two tens, and this in turn suggested a kind of radix, so that ninety was probably written in a way reminding one of the quatre-vingt-dix of the French. The hundred is unexplained, although it resembles the letter *ta* or *tra* of the Brāhmī alphabet with 1 before (to the right of) it. The two hundred is only a variant of the symbol for hundred, with two vertical marks.^[70]

This system has many points of similarity with the Nabatean numerals^[71] in use in the first centuries of the Christian era. The cross is here used for four, and the Kharoṣṭhī form is employed for twenty. In addition to this there is a trace of an analogous use of a scale of twenty. While the symbol for 100 is quite different, the method of forming the other hundreds is the same. The correspondence seems to be too marked to be wholly accidental.

It is not in the Kharoṣṭhī numerals, therefore, that we can hope to find the origin of those used by us, and we turn to the second of the Indian types, the Brāhmī characters. The alphabet attributed to Brahṃā is the oldest of the several known in India, and was used from the earliest historic times. There are various theories of its origin, none of which has as yet any wide acceptance,^[72] although the problem offers hope of solution in due time. The numerals are not as old as the alphabet, or at least they have not as yet been found in inscriptions earlier than those in which the edicts of Aśoka appear, some of these having been incised in Brāhmī as well as Kharoṣṭhī. As already stated, the older writers probably wrote the numbers in words, as seems to have been the case in the earliest Pali writings of Ceylon.^[73]


The following numerals are, as far as known, the only ones to appear in the Aśoka edicts:
[74]



These fragments from the third century B.C., crude and unsatisfactory as they are, are the undoubted early forms from which our present system developed. They next appear in the second century B.C. in some inscriptions in the cave on the top of the Nānā Ghāt hill, about seventy-five miles from Poona in central India. These inscriptions may be memorials of the early Andhra dynasty of southern India, but their chief interest lies in the numerals which they contain.

The cave was made as a resting-place for travelers ascending the hill, which lies on the road from Kalyāna to Junar. It seems to have been cut out by a descendant of King Śātavāhana,^[75] for inside the wall opposite the entrance are representations of the members of his family, much defaced, but with the names still legible. It would seem that the excavation was made by order of a king named Vedisiri, and "the inscription contains a list of gifts made on the occasion of the performance of several *yagnas* or religious sacrifices," and numerals are to be seen in no less than thirty places.^[76]

There is considerable dispute as to what numerals are really found in these inscriptions, owing to the difficulty of deciphering them; but the following, which have been copied from a rubbing, are probably number forms:^[77]



The inscription itself, so important as containing the earliest considerable Hindu numeral system connected with our own, is of sufficient interest to warrant reproducing part of it in facsimile, as is done on page 24.

The image shows a stone inscription with a rectangular frame. The text is written in an ancient script, likely Pahlavi, and is arranged in several horizontal lines. The stone is weathered and the text is somewhat faded.

1	2	3	4	5	6	7	8	9
10	10	20	40	70	100	200	500	
1000	2000	3000	4000	8000	70,000			

TABLE SHOWING THE PROGRESS OF NUMBER FORMS IN INDIA

NUMERALS	1	2	3	4	5	6	7	8	9	10	20	30	40	50	60	70	80	90	100	200	1
Aśoka ^[80]	I	II	III	IIII																	
Śaka ^[81]	I	II	III	X	IX	IIIX	XX	7	3					733333						Δ	711
Aśoka ^[82]	I	II		+	6									6							4
Nāgarī ^[83]	-	=	≡	7	6	7		2	α	o					1		o			7	7
Nasik ^[84]	-	=	≡	7	6	7		2	α	o				X						7	7

Kṣatrapa ^[85]	—=≡𑀓𑀔𑀕𑀖𑀗𑀘𑀙𑀚𑀛𑀜𑀝𑀞𑀟𑀠𑀡𑀢𑀣𑀤𑀥𑀦𑀧𑀨𑀩𑀪𑀫𑀬𑀭𑀮𑀯𑀰𑀱𑀲𑀳𑀴𑀵𑀶𑀷𑀸𑀹𑀺𑀻𑀼𑀽𑀾𑀿𑁀𑁁𑁂𑁃𑁄𑁅𑁆𑁇𑁈𑁉𑁊𑁋𑁌𑁍𑁎𑁏𑁐𑁑𑁒𑁓𑁔𑁕𑁖𑁗𑁘𑁙𑁚𑁛𑁜𑁝𑁞𑁟𑁠𑁡𑁢𑁣𑁤𑁥𑁦𑁧𑁨𑁩𑁪𑁫𑁬𑁭𑁮𑁯𑁰𑁱𑁲𑁳𑁴𑁵𑁶𑁷𑁸𑁹𑁺𑁻𑁼𑁽𑁾𑁿𑂀𑂁𑂂𑂃𑂄𑂅𑂆𑂇𑂈𑂉𑂊𑂋𑂌𑂍𑂎𑂏𑂐𑂑𑂒𑂓𑂔𑂕𑂖𑂗𑂘𑂙𑂚𑂛𑂜𑂝𑂞𑂟𑂠𑂡𑂢𑂣𑂤𑂥𑂦𑂧𑂨𑂩𑂪𑂫𑂬𑂭𑂮𑂯𑂰𑂱𑂲𑂳𑂴𑂵𑂶𑂷𑂸𑂺𑂹𑂻𑂼𑂽𑂾𑂿𑃀𑃁𑃂𑃃𑃄𑃅𑃆𑃇𑃈𑃉𑃊𑃋𑃌𑃍𑃎𑃏𑃐𑃑𑃒𑃓𑃔𑃕𑃖𑃗𑃘𑃙𑃚𑃛𑃜𑃝𑃞𑃟𑃠𑃡𑃢𑃣𑃤𑃥𑃦𑃧𑃨𑃩𑃪𑃫𑃬𑃭𑃮𑃯𑃰𑃱𑃲𑃳𑃴𑃵𑃶𑃷𑃸𑃹𑃺𑃻𑃼𑃽𑃾𑃿𑄀𑄁𑄂𑄃𑄄𑄅𑄆𑄇𑄈𑄉𑄊𑄋𑄌𑄍𑄎𑄏𑄐𑄑𑄒𑄓𑄔𑄕𑄖𑄗𑄘𑄙𑄚𑄛𑄜𑄝𑄞𑄟𑄠𑄡𑄢𑄣𑄤𑄥𑄦𑄧𑄨𑄩𑄪𑄫𑄬𑄭𑄮𑄯𑄰𑄱𑄲𑄳𑄴𑄵𑄶𑄷𑄸𑄹𑄺𑄻𑄼𑄽𑄾𑄿𑅀𑅁𑅂𑅃𑅄𑅅𑅆𑅇𑅈𑅉𑅊𑅋𑅌𑅍𑅎𑅏𑅐𑅑𑅒𑅓𑅔𑅕𑅖𑅗𑅘𑅙𑅚𑅛𑅜𑅝𑅞𑅟𑅠𑅡𑅢𑅣𑅤𑅥𑅦𑅧𑅨𑅩𑅪𑅫𑅬𑅭𑅮𑅯𑅰𑅱𑅲𑅳𑅴𑅵𑅶𑅷𑅸𑅹𑅺𑅻𑅼𑅽𑅾𑅿𑆀𑆁𑆂𑆃𑆄𑆅𑆆𑆇𑆈𑆉𑆊𑆋𑆌𑆍𑆎𑆏𑆐𑆑𑆒𑆓𑆔𑆕𑆖𑆗𑆘𑆙𑆚𑆛𑆜𑆝𑆞𑆟𑆠𑆡𑆢𑆣𑆤𑆥𑆦𑆧𑆨𑆩𑆪𑆫𑆬𑆭𑆮𑆯𑆰𑆱𑆲𑆳𑆴𑆵𑆶𑆷𑆸𑆹𑆺𑆻𑆼𑆽𑆾𑆿𑇀𑇁𑇂𑇃𑇄𑇅𑇆𑇇𑇈𑇉𑇊𑇋𑇌𑇍𑇎𑇏𑇐𑇑𑇒𑇓𑇔𑇕𑇖𑇗𑇘𑇙𑇚𑇛𑇜𑇝𑇞𑇟𑇠𑇡𑇢𑇣𑇤𑇥𑇦𑇧𑇨𑇩𑇪𑇫𑇬𑇭𑇮𑇯𑇰𑇱𑇲𑇳𑇴𑇵𑇶𑇷𑇸𑇹𑇺𑇻𑇼𑇽𑇾𑇿𑈀𑈁𑈂𑈃𑈄𑈅𑈆𑈇𑈈𑈉𑈊𑈋𑈌𑈍𑈎𑈏𑈐𑈑𑈒𑈓𑈔𑈕𑈖𑈗𑈘𑈙𑈚𑈛𑈜𑈝𑈞𑈟𑈠𑈡𑈢𑈣𑈤𑈥𑈦𑈧𑈨𑈩𑈪𑈫𑈬𑈭𑈮𑈯𑈰𑈱𑈲𑈳𑈴𑈶𑈵𑈷𑈸𑈹𑈺𑈻𑈼𑈽𑈾𑈿𑉀𑉁𑉂𑉃𑉄𑉅𑉆𑉇𑉈𑉉𑉊𑉋𑉌𑉍𑉎𑉏𑉐𑉑𑉒𑉓𑉔𑉕𑉖𑉗𑉘𑉙𑉚𑉛𑉜𑉝𑉞𑉟𑉠𑉡𑉢𑉣𑉤𑉥𑉦𑉧𑉨𑉩𑉪𑉫𑉬𑉭𑉮𑉯𑉰𑉱𑉲𑉳𑉴𑉵𑉶𑉷𑉸𑉹𑉺𑉻𑉼𑉽𑉾𑉿𑊀𑊁𑊂𑊃𑊄𑊅𑊆𑊇𑊈𑊉𑊊𑊋𑊌𑊍𑊎𑊏𑊐𑊑𑊒𑊓𑊔𑊕𑊖𑊗𑊘𑊙𑊚𑊛𑊜𑊝𑊞𑊟𑊠𑊡𑊢𑊣𑊤𑊥𑊦𑊧𑊨𑊩𑊪𑊫𑊬𑊭𑊮𑊯𑊰𑊱𑊲𑊳𑊴𑊵𑊶𑊷𑊸𑊹𑊺𑊻𑊼𑊽𑊾𑊿𑋀𑋁𑋂𑋃𑋄𑋅𑋆𑋇𑋈𑋉𑋊𑋋𑋌𑋍𑋎𑋏𑋐𑋑𑋒𑋓𑋔𑋕𑋖𑋗𑋘𑋙𑋚𑋛𑋜𑋝𑋞𑋟𑋠𑋡𑋢𑋣𑋤𑋥𑋦𑋧𑋨𑋩𑋪𑋫𑋬𑋭𑋮𑋯𑋰𑋱𑋲𑋳𑋴𑋵𑋶𑋷𑋸𑋹𑋺𑋻𑋼𑋽𑋾𑋿𑌀𑌁𑌂𑌃𑌄𑌅𑌆𑌇𑌈𑌉𑌊𑌋𑌌𑌍𑌎𑌏𑌐𑌑𑌒𑌓𑌔𑌕𑌖𑌗𑌘𑌙𑌚𑌛𑌜𑌝𑌞𑌟𑌠𑌡𑌢𑌣𑌤𑌥𑌦𑌧𑌨𑌩𑌪𑌫𑌬𑌭𑌮𑌯𑌰𑌱𑌲𑌳𑌴𑌵𑌶𑌷𑌸𑌹𑌺𑌻𑌼𑌽𑌾𑌿𑍀𑍁𑍂𑍃𑍄𑍅𑍆𑍇𑍈𑍉𑍊𑍋𑍌𑍍𑍎𑍏𑍐𑍑𑍒𑍓𑍔𑍕𑍖𑍗𑍘𑍙𑍚𑍛𑍜𑍝𑍞𑍟𑍠𑍡𑍢𑍣𑍤𑍥𑍦𑍧𑍨𑍩𑍪𑍫𑍬𑍭𑍮𑍯𑍰𑍱𑍲𑍳𑍴𑍵𑍶𑍷𑍸𑍹𑍺𑍻𑍼𑍽𑍾𑍿𑎀𑎁𑎂𑎃𑎄𑎅𑎆𑎇𑎈𑎉𑎊𑎋𑎌𑎍𑎎𑎏𑎐𑎑𑎒𑎓𑎔𑎕𑎖𑎗𑎘𑎙𑎚𑎛𑎜𑎝𑎞𑎟𑎠𑎡𑎢𑎣𑎤𑎥𑎦𑎧𑎨𑎩𑎪𑎫𑎬𑎭𑎮𑎯𑎰𑎱𑎲𑎳𑎴𑎵𑎶𑎷𑎸𑎹𑎺𑎻𑎼𑎽𑎾𑎿𑏀𑏁𑏂𑏃𑏄𑏅𑏆𑏇𑏈𑏉𑏊𑏋𑏌𑏍𑏎𑏏𑏐𑏑𑏒𑏓𑏔𑏕𑏖𑏗𑏘𑏙𑏚𑏛𑏜𑏝𑏞𑏟𑏠𑏡𑏢𑏣𑏤𑏥𑏦𑏧𑏨𑏩𑏪𑏫𑏬𑏭𑏮𑏯𑏰𑏱𑏲𑏳𑏴𑏵𑏶𑏷𑏸𑏹𑏺𑏻𑏼𑏽𑏾𑏿𑐀𑐁𑐂𑐃𑐄𑐅𑐆𑐇𑐈𑐉𑐊𑐋𑐌𑐍𑐎𑐏𑐐𑐑𑐒𑐓𑐔𑐕𑐖𑐗𑐘𑐙𑐚𑐛𑐜𑐝𑐞𑐟𑐠𑐡𑐢𑐣𑐤𑐥𑐦𑐧𑐨𑐩𑐪𑐫𑐬𑐭𑐮𑐯𑐰𑐱𑐲𑐳𑐴𑐵𑐶𑐷𑐸𑐹𑐺𑐻𑐼𑐽𑐾𑐿𑑀𑑁𑑂𑑃𑑄𑑅𑑆𑑇𑑈𑑉𑑊𑑋𑑌𑑍𑑎𑑏𑑐𑑑𑑒𑑓𑑔𑑕𑑖𑑗𑑘𑑙𑑚𑑛𑑜𑑝𑑞𑑟𑑠𑑡𑑢𑑣𑑤𑑥𑑦𑑧𑑨𑑩𑑪𑑫𑑬𑑭𑑮𑑯𑑰𑑱𑑲𑑳𑑴𑑵𑑶𑑷𑑸𑑹𑑺𑑻𑑼𑑽𑑾𑑿𑒀𑒁𑒂𑒃𑒄𑒅𑒆𑒇𑒈𑒉𑒊𑒋𑒌𑒍𑒎𑒏𑒐𑒑𑒒𑒓𑒔𑒕𑒖𑒗𑒘𑒙𑒚𑒛𑒜𑒝𑒞𑒟𑒠𑒡𑒢𑒣𑒤𑒥𑒦𑒧𑒨𑒩𑒪𑒫𑒬𑒭𑒮𑒯𑒰𑒱𑒲𑒳𑒴𑒵𑒶𑒷𑒸𑒻𑒻𑒼𑒽𑒾𑒿𑓀𑓁𑓃𑓂𑓄𑓅𑓆𑓇𑓈𑓉𑓊𑓋𑓌𑓍𑓎𑓏𑓐𑓑𑓒𑓓𑓔𑓕𑓖𑓗𑓘𑓙𑓚𑓛𑓜𑓝𑓞𑓟𑓠𑓡𑓢𑓣𑓤𑓥𑓦𑓧𑓨𑓩𑓪𑓫𑓬𑓭𑓮𑓯𑓰𑓱𑓲𑓳𑓴𑓵𑓶𑓷𑓸𑓹𑓺𑓻𑓼𑓽𑓾𑓿𑔀𑔁𑔂𑔃𑔄𑔅𑔆𑔇𑔈𑔉𑔊𑔋𑔌𑔍𑔎𑔏𑔐𑔑𑔒𑔓𑔔𑔕𑔖𑔗𑔘𑔙𑔚𑔛𑔜𑔝𑔞𑔟𑔠𑔡𑔢𑔣𑔤𑔥𑔦𑔧𑔨𑔩𑔪𑔫𑔬𑔭𑔮𑔯𑔰𑔱𑔲𑔳𑔴𑔵𑔶𑔷𑔸𑔹𑔺𑔻𑔼𑔽𑔾𑔿𑕀𑕁𑕂𑕃𑕄𑕅𑕆𑕇𑕈𑕉𑕊𑕋𑕌𑕍𑕎𑕏𑕐𑕑𑕒𑕓𑕔𑕕𑕖𑕗𑕘𑕙𑕚𑕛𑕜𑕝𑕞𑕟𑕠𑕡𑕢𑕣𑕤𑕥𑕦𑕧𑕨𑕩𑕪𑕫𑕬𑕭𑕮𑕯𑕰𑕱𑕲𑕳𑕴𑕵𑕶𑕷𑕸𑕹𑕺𑕻𑕼𑕽𑕾𑕿𑖀𑖁𑖂𑖃𑖄𑖅𑖆𑖇𑖈𑖉𑖊𑖋𑖌𑖍𑖎𑖏𑖐𑖑𑖒𑖓𑖔𑖕𑖖𑖗𑖘𑖙𑖚𑖛𑖜𑖝𑖞𑖟𑖠𑖡𑖢𑖣𑖤𑖥𑖦𑖧𑖨𑖩𑖪𑖫𑖬𑖭𑖮𑖯𑖰𑖱𑖲𑖳𑖴𑖵𑖶𑖷𑖸𑖹𑖺𑖻𑖼𑖽𑖾𑗀𑖿𑗁𑗂𑗃𑗄𑗅𑗆𑗇𑗈𑗉𑗊𑗋𑗌𑗍𑗎𑗏𑗐𑗑𑗒𑗓𑗔𑗕𑗖𑗗𑗘𑗙𑗚𑗛𑗜𑗝𑗞𑗟𑗠𑗡𑗢𑗣𑗤𑗥𑗦𑗧𑗨𑗩𑗪𑗫𑗬𑗭𑗮𑗯𑗰𑗱𑗲𑗳𑗴𑗵𑗶𑗷𑗸𑗹𑗺𑗻𑗼𑗽𑗾𑗿𑘀𑘁𑘂𑘃𑘄𑘅𑘆𑘇𑘈𑘉𑘊𑘋𑘌𑘍𑘎𑘏𑘐𑘑𑘒𑘓𑘔𑘕𑘖𑘗𑘘𑘙𑘚𑘛𑘜𑘝𑘞𑘟𑘠𑘡𑘢𑘣𑘤𑘥𑘦𑘧𑘨𑘩𑘪𑘫𑘬𑘭𑘮𑘯𑘰𑘱𑘲𑘳𑘴𑘵𑘶𑘷𑘸𑘹𑘺𑘻𑘼𑘽𑘾𑘿𑙀𑙁𑙂𑙃𑙄𑙅𑙆𑙇𑙈𑙉𑙊𑙋𑙌𑙍𑙎𑙏𑙐𑙑𑙒𑙓𑙔𑙕𑙖𑙗𑙘𑙙𑙚𑙛𑙜𑙝𑙞𑙟𑙠𑙡𑙢𑙣𑙤𑙥𑙦𑙧𑙨𑙩𑙪𑙫𑙬𑙭𑙮𑙯𑙰𑙱𑙲𑙳𑙴𑙵𑙶𑙷𑙸𑙹𑙺𑙻𑙼𑙽𑙾𑙿𑚀𑚁𑚂𑚃𑚄𑚅𑚆𑚇𑚈𑚉𑚊𑚋𑚌𑚍𑚎𑚏𑚐𑚑𑚒𑚓𑚔𑚕𑚖𑚗𑚘𑚙𑚚𑚛𑚜𑚝𑚞𑚟𑚠𑚡𑚢𑚣𑚤𑚥𑚦𑚧𑚨𑚩𑚪𑚫𑚬𑚭𑚮𑚯𑚰𑚱𑚲𑚳𑚴𑚵𑚷𑚶𑚸𑚹𑚺𑚻𑚼𑚽𑚾𑚿𑛀𑛁𑛂𑛃𑛄𑛅𑛆𑛇𑛈𑛉𑛊𑛋𑛌𑛍𑛎𑛏𑛐𑛑𑛒𑛓𑛔𑛕𑛖𑛗𑛘𑛙𑛚𑛛𑛜𑛝𑛞𑛟𑛠𑛡𑛢𑛣𑛤𑛥𑛦𑛧𑛨𑛩𑛪𑛫𑛬𑛭𑛮𑛯𑛰𑛱𑛲𑛳𑛴𑛵𑛶𑛷𑛸𑛹𑛺𑛻𑛼𑛽𑛾𑛿𑜀𑜁𑜂𑜃𑜄𑜅𑜆𑜇𑜈𑜉𑜊𑜋𑜌𑜍𑜎𑜏𑜐𑜑𑜒𑜓𑜔𑜕𑜖𑜗𑜘𑜙𑜚𑜛𑜜𑜝𑜞𑜟𑜠𑜡𑜢𑜣𑜤𑜥𑜦𑜧𑜨𑜩𑜪𑜫𑜬𑜭𑜮𑜯𑜰𑜱𑜲𑜳𑜴𑜵𑜶𑜷𑜸𑜹𑜺𑜻𑜼𑜽𑜾𑜿𑝀𑝁𑝂𑝃𑝄𑝅𑝆𑝇𑝈𑝉𑝊𑝋𑝌𑝍𑝎𑝏𑝐𑝑𑝒𑝓𑝔𑝕𑝖𑝗𑝘𑝙𑝚𑝛𑝜𑝝𑝞𑝟𑝠𑝡𑝢𑝣𑝤𑝥𑝦𑝧𑝨𑝩𑝪𑝫𑝬𑝭𑝮𑝯𑝰𑝱𑝲𑝳𑝴𑝵𑝶𑝷𑝸𑝹𑝺𑝻𑝼𑝽𑝾𑝿𑞀𑞁𑞂𑞃𑞄𑞅𑞆𑞇𑞈𑞉𑞊𑞋𑞌𑞍𑞎𑞏𑞐𑞑𑞒𑞓𑞔𑞕𑞖𑞗𑞘𑞙𑞚𑞛𑞜𑞝𑞞𑞟𑞠𑞡𑞢𑞣𑞤𑞥𑞦𑞧𑞨𑞩𑞪𑞫𑞬𑞭𑞮𑞯𑞰𑞱𑞲𑞳𑞴𑞵𑞶𑞷𑞸𑞹𑞺𑞻𑞼𑞽𑞾𑞿𑟀𑟁𑟂𑟃𑟄𑟅𑟆𑟇𑟈𑟉𑟊𑟋𑟌𑟍𑟎𑟏𑟐𑟑𑟒𑟓𑟔𑟕𑟖𑟗𑟘𑟙𑟚𑟛𑟜𑟝𑟞𑟟𑟠𑟡𑟢𑟣𑟤𑟥𑟦𑟧𑟨𑟩𑟪𑟫𑟬𑟭𑟮𑟯𑟰𑟱𑟲𑟳𑟴𑟵𑟶𑟷𑟸𑟹𑟺𑟻𑟼𑟽𑟾𑟿𑠀𑠁𑠂𑠃𑠄𑠅𑠆𑠇𑠈𑠉𑠊𑠋𑠌𑠍𑠎𑠏𑠐𑠑𑠒𑠓𑠔𑠕𑠖𑠗𑠘𑠙𑠚𑠛𑠜𑠝𑠞𑠟𑠠𑠡𑠢𑠣𑠤𑠥𑠦𑠧𑠨𑠩𑠪𑠫𑠬𑠭𑠮𑠯𑠰𑠱𑠲𑠳𑠴𑠵𑠶𑠷𑠸𑠺𑠹𑠻𑠼𑠽𑠾𑠿𑡀𑡁𑡂𑡃𑡄𑡅𑡆𑡇𑡈𑡉𑡊𑡋𑡌𑡍𑡎𑡏𑡐𑡑𑡒𑡓𑡔𑡕𑡖𑡗𑡘𑡙𑡚𑡛𑡜𑡝𑡞𑡟𑡠𑡡𑡢𑡣𑡤𑡥𑡦𑡧𑡨𑡩𑡪𑡫𑡬𑡭𑡮𑡯𑡰𑡱𑡲𑡳𑡴𑡵𑡶𑡷𑡸𑡹𑡺𑡻𑡼𑡽𑡾𑡿𑢀𑢁𑢂𑢃𑢄𑢅𑢆𑢇𑢈𑢉𑢊𑢋𑢌𑢍𑢎𑢏𑢐𑢑𑢒𑢓𑢔𑢕𑢖𑢗𑢘𑢙𑢚𑢛𑢜𑢝𑢞𑢟𑢠𑢡𑢢𑢣𑢤𑢥𑢦𑢧𑢨𑢩𑢪𑢫𑢬𑢭𑢮𑢯𑢰𑢱𑢲𑢳𑢴𑢵𑢶𑢷𑢸𑢹𑢺𑢻𑢼𑢽𑢾𑢿𑣀𑣁𑣂𑣃𑣄𑣅𑣆𑣇𑣈𑣉𑣊𑣋𑣌𑣍𑣎𑣏𑣐𑣑𑣒𑣓𑣔𑣕𑣖𑣗𑣘𑣙𑣚𑣛𑣜𑣝𑣞𑣟𑣠𑣡𑣢𑣣𑣤𑣥𑣦𑣧𑣨𑣩𑣪𑣫𑣬𑣭𑣮𑣯𑣰𑣱𑣲𑣳𑣴𑣵𑣶𑣷𑣸𑣹𑣺𑣻𑣼𑣽𑣾𑣿𑤀𑤁𑤂𑤃𑤄𑤅𑤆𑤇𑤈𑤉𑤊𑤋𑤌𑤍𑤎𑤏𑤐𑤑𑤒𑤓𑤔𑤕𑤖𑤗𑤘𑤙𑤚𑤛𑤜𑤝𑤞𑤟𑤠𑤡𑤢𑤣𑤤𑤥𑤦𑤧𑤨𑤩𑤪𑤫𑤬𑤭𑤮𑤯𑤰𑤱𑤲𑤳𑤴𑤵𑤶𑤷𑤸𑤹𑤺𑤻𑤼𑤽𑤾𑤿𑥀𑥁𑥂𑥃𑥄𑥅𑥆𑥇𑥈𑥉𑥊𑥋𑥌𑥍𑥎𑥏𑥐𑥑𑥒𑥓𑥔𑥕𑥖𑥗𑥘𑥙𑥚𑥛𑥜𑥝𑥞𑥟𑥠𑥡𑥢𑥣𑥤𑥥𑥦𑥧𑥨𑥩𑥪𑥫𑥬𑥭𑥮𑥯𑥰𑥱𑥲𑥳𑥴𑥵𑥶𑥷𑥸𑥹𑥺𑥻𑥼𑥽𑥾𑥿𑦀𑦁𑦂𑦃𑦄𑦅𑦆𑦇𑦈𑦉𑦊𑦋𑦌𑦍𑦎𑦏𑦐𑦑𑦒𑦓𑦔𑦕𑦖𑦗𑦘𑦙𑦚𑦛𑦜𑦝𑦞𑦟𑦠𑦡𑦢𑦣𑦤𑦥𑦦𑦧𑦨𑦩𑦪𑦫𑦬𑦭𑦮𑦯𑦰𑦱𑦲𑦳𑦴𑦵𑦶𑦷𑦸𑦹𑦺𑦻𑦼𑦽𑦾𑦿𑧀𑧁𑧂𑧃𑧄𑧅𑧆𑧇𑧈𑧉𑧊𑧋𑧌𑧍𑧎𑧏𑧐𑧑𑧒𑧓𑧔𑧕𑧖𑧗𑧘𑧙𑧚𑧛𑧜𑧝𑧞𑧟𑧠𑧡𑧢𑧣𑧤𑧥𑧦𑧧𑧨𑧩𑧪𑧫𑧬𑧭𑧮𑧯𑧰𑧱𑧲𑧳𑧴𑧵𑧶𑧷𑧸𑧹𑧺𑧻𑧼𑧽𑧾𑧿𑨀𑨁𑨂𑨃𑨄𑨅𑨆𑨇𑨈𑨉𑨊𑨋𑨌𑨍𑨎𑨏𑨐𑨑𑨒𑨓𑨔𑨕𑨖𑨗𑨘𑨙𑨚𑨛𑨜𑨝𑨞𑨟𑨠𑨡𑨢𑨣𑨤𑨥𑨦𑨧𑨨𑨩𑨪𑨫𑨬𑨭𑨮𑨯𑨰𑨱𑨲𑨳𑨴𑨵𑨶𑨷𑨸𑨹𑨺𑨻𑨼𑨽𑨾𑨿𑩀𑩁𑩂𑩃𑩄𑩅𑩆𑩇𑩈𑩉𑩊𑩋𑩌𑩍𑩎𑩏𑩐𑩑𑩒𑩓𑩔𑩕𑩖𑩗𑩘𑩙𑩚𑩛𑩜𑩝𑩞𑩟𑩠𑩡𑩢𑩣𑩤𑩥𑩦𑩧𑩨𑩩𑩪𑩫𑩬𑩭𑩮𑩯𑩰𑩱𑩲𑩳𑩴𑩵𑩶𑩷𑩸𑩹𑩺𑩻𑩼𑩽𑩾𑩿𑪀𑪁𑪂𑪃𑪄𑪅𑪆𑪇𑪈𑪉𑪊𑪋𑪌𑪍𑪎𑪏𑪐𑪑𑪒𑪓𑪔𑪕𑪖𑪗𑪘𑪙𑪚𑪛𑪜𑪝𑪞𑪟𑪠𑪡𑪢𑪣𑪤𑪥𑪦𑪧𑪨𑪩𑪪𑪫𑪬𑪭𑪮𑪯𑪰𑪱𑪲𑪳𑪴𑪵𑪶𑪷𑪸𑪹𑪺𑪻𑪼𑪽𑪾𑪿𑫀𑫁𑫂𑫃𑫄𑫅𑫆𑫇𑫈𑫉𑫊𑫋𑫌𑫍𑫎𑫏𑫐𑫑𑫒𑫓𑫔𑫕𑫖𑫗𑫘𑫙𑫚𑫛𑫜𑫝𑫞𑫟𑫠𑫡𑫢𑫣𑫤𑫥𑫦𑫧𑫨𑫩𑫪𑫫𑫬𑫭𑫮𑫯𑫰𑫱𑫲𑫳𑫴𑫵𑫶𑫷𑫸𑫹𑫺𑫻𑫼𑫽𑫾𑫿𑬀𑬁𑬂𑬃𑬄𑬅𑬆𑬇𑬈𑬉𑬊𑬋𑬌𑬍𑬎𑬏𑬐𑬑𑬒𑬓𑬔𑬕𑬖𑬗𑬘𑬙𑬚𑬛𑬜𑬝𑬞𑬟𑬠𑬡𑬢𑬣𑬤𑬥𑬦𑬧𑬨𑬩𑬪𑬫𑬬𑬭𑬮𑬯𑬰𑬱𑬲𑬳𑬴𑬵𑬶𑬷𑬸𑬹𑬺𑬻𑬼𑬽𑬾𑬿𑭀𑭁𑭂𑭃𑭄𑭅𑭆𑭇𑭈𑭉𑭊𑭋𑭌𑭍𑭎𑭏𑭐𑭑𑭒𑭓𑭔𑭕𑭖𑭗𑭘𑭙𑭚𑭛𑭜𑭝𑭞𑭟𑭠𑭡𑭢𑭣𑭤𑭥𑭦𑭧𑭨𑭩𑭪𑭫𑭬𑭭𑭮𑭯𑭰𑭱𑭲𑭳𑭴𑭵𑭶𑭷𑭸𑭹𑭺𑭻𑭼𑭽𑭾𑭿𑮀𑮁𑮂𑮃𑮄𑮅𑮆𑮇𑮈𑮉𑮊𑮋𑮌𑮍𑮎𑮏𑮐𑮑𑮒𑮓𑮔𑮕𑮖𑮗𑮘𑮙𑮚𑮛𑮜𑮝𑮞𑮟𑮠𑮡𑮢𑮣𑮤𑮥𑮦𑮧𑮨𑮩𑮪𑮫𑮬𑮭𑮮𑮯𑮰𑮱𑮲𑮳𑮴𑮵𑮶𑮷𑮸𑮹𑮺𑮻𑮼𑮽𑮾𑮿𑯀𑯁𑯂𑯃𑯄𑯅𑯆𑯇𑯈𑯉𑯊𑯋𑯌𑯍𑯎𑯏𑯐𑯑𑯒𑯓𑯔𑯕𑯖𑯗𑯘𑯙𑯚𑯛𑯜𑯝𑯞𑯟𑯠𑯡𑯢𑯣𑯤𑯥𑯦𑯧𑯨𑯩𑯪𑯫𑯬𑯭𑯮𑯯𑯰𑯱𑯲𑯳𑯴𑯵𑯶𑯷𑯸𑯹𑯺𑯻𑯼𑯽𑯾𑯿𑰀𑰁𑰂𑰃𑰄𑰅𑰆𑰇𑰈𑰉𑰊𑰋𑰌𑰍𑰎𑰏𑰐𑰑𑰒𑰓𑰔𑰕𑰖𑰗𑰘𑰙𑰚𑰛𑰜
--------------------------	---

Having now examined types of the early forms it is appropriate to turn our attention to the question of their origin. As to the first three there is no question. The 1 or _ is simply one stroke, or one stick laid down by the computer. The 11 or = represents two strokes or two sticks, and so for the 111 and ≡. From some primitive 11 came the two of Egypt, of Rome, of early Greece, and of various other civilizations. It appears in the three Egyptian numeral systems in the following forms:

Hieroglyphic 11

Hieratic 11

Demotic 11 11

The last of these is merely a cursive form as in the Arabic 2, which becomes our 2 if tipped through a right angle. From some primitive = came the Chinese symbol, which is practically identical with the symbols found commonly in India from 150 B.C. to 700 A.D. In the cursive form it becomes 2, and this was frequently used for two in Germany until the 18th century. It finally went into the modern form 2, and the ≡ in the same way became our 3.

There is, however, considerable ground for interesting speculation with respect to these first three numerals. The earliest Hindu forms were perpendicular. In the Nānā Ghāt inscriptions they are vertical. But long before either the Aśoka or the Nānā Ghāt inscriptions the Chinese were using the horizontal forms for the first three numerals, but a vertical arrangement for four.^[101] Now where did China get these forms? Surely not from India, for she had them, as her monuments and literature^[102] show, long before the Hindus knew them. The tradition is that China brought her civilization around the north of Tibet, from Mongolia, the primitive habitat being Mesopotamia, or possibly the oases of Turkestan. Now what numerals did Mesopotamia use? The Babylonian system, simple in its general principles but very complicated in many of its details, is now well known.^[103] In particular, one, two, and three were represented by vertical arrow-heads. Why, then, did the Chinese write theirs horizontally? The problem now takes a new interest when we find that these Babylonian forms were not the primitive ones of this region, but that the early Sumerian forms were horizontal.^[104]

What interpretation shall be given to these facts? Shall we say that it was mere accident that one people wrote "one" vertically and that another wrote it horizontally? This may be the case; but it may also be the case that the tribal migrations that ended in the Mongol invasion of China started from the Euphrates while yet the Sumerian civilization was prominent, or from some common source in Turkestan, and that they carried to the East the primitive numerals of their ancient home, the first three, these being all that the people as a whole knew or needed. It is equally possible that these three horizontal forms represent primitive stick-laying, the most natural position of a stick placed in front of a calculator being the horizontal one. When, however, the cuneiform writing developed more fully, the vertical form may have been proved the easier to make, so that by the time the migrations to the West began these were in use, and from them came the upright forms of Egypt, Greece, Rome, and other Mediterranean lands, and those of Aśoka's time in

India. After Aśoka, and perhaps among the merchants of earlier centuries, the horizontal forms may have come down into India from China, thus giving those of the Nānā Ghāt cave and of later inscriptions. This is in the realm of speculation, but it is not improbable that further epigraphical studies may confirm the hypothesis.

As to the numerals above three there have been very many conjectures. The figure one of the Demotic looks like the one of the Sanskrit, the two (reversed) like that of the Arabic, the four has some resemblance to that in the Nasik caves, the five (reversed) to that on the Kṣatrapa coins, the nine to that of the Kuṣana inscriptions, and other points of similarity have been imagined. Some have traced resemblance between the Hieratic five and seven and those of the Indian inscriptions. There have not, therefore, been wanting those who asserted an Egyptian origin for these numerals.^[105] There has already been mentioned the fact that the Kharoṣṭhī numerals were formerly known as Bactrian, Indo-Bactrian, and Aryan. Cunningham^[106] was the first to suggest that these numerals were derived from the alphabet of the Bactrian civilization of Eastern Persia, perhaps a thousand years before our era, and in this he was supported by the scholarly work of Sir E. Clive Bayley,^[107] who in turn was followed by Canon Taylor.^[108] The resemblance has not proved convincing, however, and Bayley's drawings have been criticized as being affected by his theory. The following is part of the hypothesis:^[109]

<i>Numeral</i>	<i>Hindu</i>	<i>Bactrian</i>	<i>Sanskrit</i>
4	𑂔	𑂔 = ch	chatur, Lat. quattuor
5	𑂕	𑂕 = p	pancha, Gk. πέντε
6	𑂖	𑂖 = s	ṣaṣ
7	𑂗	𑂗 = ṣ	sapta

(the s and ṣ are interchanged as occasionally in N. W. India)

Bühler^[110] rejects this hypothesis, stating that in four cases (four, six, seven, and ten) the facts are absolutely against it.

While the relation to ancient Bactrian forms has been generally doubted, it is agreed that most of the numerals resemble Brāhmī letters, and we would naturally expect them to be initials.^[111] But, knowing the ancient pronunciation of most of the number names,^[112] we find this not to be the case. We next fall back upon the hypothesis that they represent the order of letters^[113] in the ancient alphabet. From what we know of this order, however, there seems also no basis for this assumption. We have, therefore, to confess that we are not certain that the numerals were alphabetic at all, and if they were alphabetic we have no evidence at present as to the basis of selection. The later forms may possibly have been alphabetical expressions of certain syllables called *akṣaras*, which possessed in Sanskrit fixed numerical values,^[114] but this is equally uncertain with the rest. Bayley also thought^[115] that some of the forms were Phœnician, as notably the use of a circle for twenty, but the resemblance is in general too remote to be convincing.

There is also some slight possibility that Chinese influence is to be seen in certain of the early forms of Hindu numerals.^[116]

More absurd is the hypothesis of a Greek origin, supposedly supported by derivation of the current symbols from the first nine letters of the Greek alphabet.^[117] This difficult feat is accomplished by twisting some of the letters, cutting off, adding on, and effecting other changes to make the letters fit the theory. This peculiar theory was first set up by Dasypodius^[118] (Conrad Rauhfuss), and was later elaborated by Huet.^[119]

A bizarre derivation based upon early Arabic (c. 1040 A.D.) sources is given by Kircher in his work^[120] on number mysticism. He quotes from Abenragel,^[121] giving the Arabic and a Latin translation^[122] and stating that the ordinary Arabic forms are derived from sectors of a circle, $\oplus$.

Out of all these conflicting theories, and from all the resemblances seen or imagined between the numerals of the West and those of the East, what conclusions are we prepared to draw as the evidence now stands? Probably none that is satisfactory. Indeed, upon the evidence at hand we might properly feel that everything points to the numerals as being substantially indigenous to India. And why should this not be the case? If the king Srong-tsan-Gampo (639 A.D.), the founder of Lhāsa,^[123] could have set about to devise a new alphabet for Tibet, and if the Siamese, and the Singhalese, and the Burmese, and other peoples in the East, could have created alphabets of their own, why should not the numerals also have been fashioned by some temple school, or some king, or some merchant guild? By way of illustration, there are shown in the table on page 36 certain systems of the East, and while a few resemblances are evident, it is also evident that the creators of each system endeavored to find original forms that should not be found in other systems. This, then, would seem to be a fair interpretation of the evidence. A human mind cannot readily create simple forms that are absolutely new; what it fashions will naturally resemble what other minds have fashioned, or what it has known through hearsay or through sight. A circle is one of the world's common stock of figures, and that it should mean twenty in Phœnicia and in India is hardly more surprising than that it signified ten at one time in Babylon.^[124] It is therefore quite probable that an extraneous origin cannot be found for the very sufficient reason that none exists.

Of absolute nonsense about the origin of the symbols which we use much has been written. Conjectures, however, without any historical evidence for support, have no place in a serious discussion of the gradual evolution of the present numeral forms.^[125]

TABLE OF CERTAIN EASTERN SYSTEMS

	0	1	2	3	4	5	6	7	8	9	10
Siam	๐	๑	๒	๓	๔	๕	๖	๗	๘	๙	๑๐

Burma ^[126]	○ ୨ ୨ ୨ ୨ ୨ ୨ ୨ ୨ ୨ ୨
Malabar ^[127]	୪ ୪ ୪ ୪ ୪ ୪ ୪ ୪ ୪ ୪
Tibet ^[128]	୦ ୧ ୨ ୩ ୪ ୫ ୬ ୭ ୮ ୯
Ceylon ^[129]	୦ ୧ ୨ ୩ ୪ ୫ ୬ ୭ ୮ ୯
Malayalam ^[129]	୦ ୧ ୨ ୩ ୪ ୫ ୬ ୭ ୮ ୯

We may summarize this chapter by saying that no one knows what suggested certain of the early numeral forms used in India. The origin of some is evident, but the origin of others will probably never be known. There is no reason why they should not have been invented by some priest or teacher or guild, by the order of some king, or as part of the mysticism of some temple. Whatever the origin, they were no better than scores of other ancient systems and no better than the present Chinese system when written without the zero, and there would never have been any chance of their triumphal progress westward had it not been for this relatively late symbol. There could hardly be demanded a stronger proof of the Hindu origin of the character for zero than this, and to it further reference will be made in Chapter IV.

CHAPTER III

LATER HINDU FORMS, WITH A PLACE VALUE

Before speaking of the perfected Hindu numerals with the zero and the place value, it is necessary to consider the third system mentioned on page 19,—the word and letter forms. The use of words with place value began at least as early as the 6th century of the Christian era. In many of the manuals of astronomy and mathematics, and often in other works in mentioning dates, numbers are represented by the names of certain objects or ideas. For example, zero is represented by "the void" (*śūnya*), or "heaven-space" (*ambara ākāśa*); one by "stick" (*rupa*), "moon" (*indu śāśin*), "earth" (*bhū*), "beginning" (*ādi*), "Brahma," or, in general, by anything markedly unique; two by "the twins" (*yama*), "hands" (*kara*), "eyes" (*naṇana*), etc.; four by "oceans," five by "senses" (*viśaya*) or "arrows" (the five arrows of Kāmadēva); six by "seasons" or "flavors"; seven by "mountain" (*aga*), and so on.^[130] These names, accommodating themselves to the verse in which scientific works were written, had the additional advantage of not admitting, as did the figures, easy alteration, since any change would tend to disturb the meter.

As an example of this system, the date "Śaka Saṃvat, 867" (A.D. 945 or 946), is given by "*giri-raṣa-vasu*," meaning "the mountains" (seven), "the flavors" (six), and the gods "*Vasu*" of which there were eight. In reading the date these are read from right to left.^[131]

The period of invention of this system is uncertain. The first trace seems to be in the *Śrautasūtra* of Kātyāyana and Lāṭyāyana.^[132] It was certainly known to Varāha-Mihira (d. 587),^[133] for he used it in the *Bṛhat-Saṃhitā*.^[134] It has also been asserted^[135] that Āryabhaṭa (c. 500 A.D.) was familiar with this system, but there is nothing to prove the statement.^[136] The earliest epigraphical examples of the system are found in the Bayang (Cambodia) inscriptions of 604 and 624 A.D.^[137]

Mention should also be made, in this connection, of a curious system of alphabetic numerals that sprang up in southern India. In this we have the numerals represented by the letters as given in the following table:

1	2	3	4	5	6	7	8	9	0
k	kh	g	gh	ṇ	c	ch	j	jh	ñ
ṭ	ṭh	ḍ	ḍh	ṇ	t	th	d	dh	n
p	ph	b	bh	m					
y	r	l	v	ś	ṣ	s	h	l	

By this plan a numeral might be represented by any one of several letters, as shown in the preceding table, and thus it could the more easily be formed into a word for mnemonic purposes. For example, the word

2 3 1 5 6 5 1
kha gont yan me ṣa mā pa

has the value 1,565,132, reading from right to left.^[138] This, the oldest specimen (1184 A.D.) known of this notation, is given in a commentary on the Rīgveda, representing the number of days that had elapsed from the beginning of the Kaliyuga. Burnell^[139] states that this system is even yet in use for remembering rules to calculate horoscopes, and for astronomical tables.

A second system of this kind is still used in the pagination of manuscripts in Ceylon, Siam, and Burma, having also had its rise in southern India. In this the thirty-four consonants when followed by *a* (as *ka ... la*) designate the numbers 1-34; by *ā* (as *kā ... lā*), those from 35 to 68; by *i* (*ki ... li*), those from 69 to 102, inclusive; and so on.^[140]

As already stated, however, the Hindu system as thus far described was no improvement upon many others of the ancients, such as those used by the Greeks and the Hebrews. Having no zero, it was impracticable to designate the tens, hundreds, and other units of higher order by the same symbols used for the units from one to nine. In other words, there was no possibility of place value without some further improvement. So the Nānā Ghāt symbols required the writing of "thousand seven twenty-four" about like T 7, tw, 4 in modern symbols, instead of 7024, in which the seven of the thousands, the two of the tens (concealed in the word twenty, being originally "twain of tens," the -ty signifying ten), and the four of the units are given as spoken and the order of the unit (tens, hundreds, etc.) is

given by the place. To complete the system only the zero was needed; but it was probably eight centuries after the Nānā Ghāt inscriptions were cut, before this important symbol appeared; and not until a considerably later period did it become well known. Who it was to whom the invention is due, or where he lived, or even in what century, will probably always remain a mystery.^[141] It is possible that one of the forms of ancient abacus suggested to some Hindu astronomer or mathematician the use of a symbol to stand for the vacant line when the counters were removed. It is well established that in different parts of India the names of the higher powers took different forms, even the order being interchanged.^[142] Nevertheless, as the significance of the name of the unit was given by the order in reading, these variations did not lead to error. Indeed the variation itself may have necessitated the introduction of a word to signify a vacant place or lacking unit, with the ultimate introduction of a zero symbol for this word.

To enable us to appreciate the force of this argument a large number, 8,443,682,155, may be considered as the Hindus wrote and read it, and then, by way of contrast, as the Greeks and Arabs would have read it.

Modern American reading, 8 billion, 443 million, 682 thousand, 155.

Hindu, 8 padmas, 4 vyarbudas, 4 kōṭis, 3 prayutas, 6 lakṣas, 8 ayutas, 2 sahasra, 1 śata, 5 daśan, 5.

Arabic and early German, eight thousand thousand thousand and four hundred thousand thousand and forty-three thousand thousand, and six hundred thousand and eighty-two thousand and one hundred fifty-five (or five and fifty).

Greek, eighty-four myriads of myriads and four thousand three hundred sixty-eight myriads and two thousand and one hundred fifty-five.

As Woepcke^[143] pointed out, the reading of numbers of this kind shows that the notation adopted by the Hindus tended to bring out the place idea. No other language than the Sanskrit has made such consistent application, in numeration, of the decimal system of numbers. The introduction of myriads as in the Greek, and thousands as in Arabic and in modern numeration, is really a step away from a decimal scheme. So in the numbers below one hundred, in English, eleven and twelve are out of harmony with the rest of the -teens, while the naming of all the numbers between ten and twenty is not analogous to the naming of the numbers above twenty. To conform to our written system we should have ten-one, ten-two, ten-three, and so on, as we have twenty-one, twenty-two, and the like. The Sanskrit is consistent, the units, however, preceding the tens and hundreds. Nor did any other ancient people carry the numeration as far as did the Hindus.^[144]

When the *aṅkapalli*,^[145] the decimal-place system of writing numbers, was perfected, the tenth symbol was called the *śūnyabindu*, generally shortened to *śūnya* (the void). Brockhaus^[146] has well said that if there was any invention for which the Hindus, by all their philosophy and religion, were well fitted, it was the invention of a symbol for zero.

This making of nothingness the crux of a tremendous achievement was a step in complete harmony with the genius of the Hindu.

It is generally thought that this *śūnya* as a symbol was not used before about 500 A.D., although some writers have placed it earlier.^[147] Since Āryabhaṭa gives our common method of extracting roots, it would seem that he may have known a decimal notation,^[148] although he did not use the characters from which our numerals are derived.^[149] Moreover, he frequently speaks of the void.^[150] If he refers to a symbol this would put the zero as far back as 500 A.D., but of course he may have referred merely to the concept of nothingness.

A little later, but also in the sixth century, Varāha-Mihira^[151] wrote a work entitled *Brhat Saṃhitā*^[152] in which he frequently uses *śūnya* in speaking of numerals, so that it has been thought that he was referring to a definite symbol. This, of course, would add to the probability that Āryabhaṭa was doing the same.

It should also be mentioned as a matter of interest, and somewhat related to the question at issue, that Varāha-Mihira used the word-system with place value^[153] as explained above.

The first kind of alphabetic numerals and also the word-system (in both of which the place value is used) are plays upon, or variations of, position arithmetic, which would be most likely to occur in the country of its origin.^[154]

At the opening of the next century (c. 620 A.D.) Bāṇa^[155] wrote of Subandhus's *Vāsavadattā* as a celebrated work, and mentioned that the stars dotting the sky are here compared with zeros, these being points as in the modern Arabic system. On the other hand, a strong argument against any Hindu knowledge of the symbol zero at this time is the fact that about 700 A.D. the Arabs overran the province of Sind and thus had an opportunity of knowing the common methods used there for writing numbers. And yet, when they received the complete system in 776 they looked upon it as something new.^[156] Such evidence is not conclusive, but it tends to show that the complete system was probably not in common use in India at the beginning of the eighth century. On the other hand, we must bear in mind the fact that a traveler in Germany in the year 1700 would probably have heard or seen nothing of decimal fractions, although these were perfected a century before that date. The élite of the mathematicians may have known the zero even in Āryabhaṭa's time, while the merchants and the common people may not have grasped the significance of the novelty until a long time after. On the whole, the evidence seems to point to the west coast of India as the region where the complete system was first seen.^[157] As mentioned above, traces of the numeral words with place value, which do not, however, absolutely require a decimal place-system of symbols, are found very early in Cambodia, as well as in India.

Concerning the earliest epigraphical instances of the use of the nine symbols, plus the zero, with place value, there is some question. Colebrooke^[158] in 1807 warned against the possibility of forgery in many of the ancient copper-plate land grants. On this account

Fleet, in the *Indian Antiquary*,^[159] discusses at length this phase of the work of the epigraphists in India, holding that many of these forgeries were made about the end of the eleventh century. Colebrooke^[160] takes a more rational view of these forgeries than does Kaye, who seems to hold that they tend to invalidate the whole Indian hypothesis. "But even where that may be suspected, the historical uses of a monument fabricated so much nearer to the times to which it assumes to belong, will not be entirely superseded. The necessity of rendering the forged grant credible would compel a fabricator to adhere to history, and conform to established notions: and the tradition, which prevailed in his time, and by which he must be guided, would probably be so much nearer to the truth, as it was less remote from the period which it concerned."^[161] Bühler^[162] gives the copper-plate Gurjara inscription of Cedi-saṃvat 346 (595 A.D.) as the oldest epigraphical use of the numerals^[163] "in which the symbols correspond to the alphabet numerals of the period and the place." Vincent A. Smith^[164] quotes a stone inscription of 815 A.D., dated Saṃvat 872. So F. Kielhorn in the *Epigraphia Indica*^[165] gives a Pathari pillar inscription of Parabala, dated Vikrama-saṃvat 917, which corresponds to 861 A.D., and refers also to another copper-plate inscription dated Vikrama-saṃvat 813 (756 A.D.). The inscription quoted by V. A. Smith above is that given by D. R. Bhandarkar,^[166] and another is given by the same writer as of date Saka-saṃvat 715 (798 A.D.), being incised on a pilaster. Kielhorn^[167] also gives two copper-plate inscriptions of the time of Mahendrapala of Kanauj, Valhabī-saṃvat 574 (893 A.D.) and Vikrama-saṃvat 956 (899 A.D.). That there should be any inscriptions of date as early even as 750 A.D., would tend to show that the system was at least a century older. As will be shown in the further development, it was more than two centuries after the introduction of the numerals into Europe that they appeared there upon coins and inscriptions. While Thibaut^[168] does not consider it necessary to quote any specific instances of the use of the numerals, he states that traces are found from 590 A.D. on. "That the system now in use by all civilized nations is of Hindu origin cannot be doubted; no other nation has any claim upon its discovery, especially since the references to the origin of the system which are found in the nations of western Asia point unanimously towards India."^[169]

The testimony and opinions of men like Bühler, Kielhorn, V. A. Smith, Bhandarkar, and Thibaut are entitled to the most serious consideration. As authorities on ancient Indian epigraphy no others rank higher. Their work is accepted by Indian scholars the world over, and their united judgment as to the rise of the system with a place value—that it took place in India as early as the sixth century A.D.—must stand unless new evidence of great weight can be submitted to the contrary.

Many early writers remarked upon the diversity of Indian numeral forms. Al-Bīrūnī was probably the first; noteworthy is also Johannes Hispalensis,^[170] who gives the variant forms for seven and four. We insert on p. 49 a table of numerals used with place value. While the chief authority for this is Bühler,^[171] several specimens are given which are not found in his work and which are of unusual interest.

For purposes of comparison the modern Sanskrit and Arabic numeral forms are added.

NUMERALS USED WITH PLACE VALUE

[illegible]

m ^[183] १ २ ३ ४ ५ ६ ७ ८ ९ ०
n ^[184] ० १ २ ३ ४ ५ ६ ७ ८ ९ .

CHAPTER IV

THE SYMBOL ZERO

What has been said of the improved Hindu system with a place value does not touch directly the origin of a symbol for zero, although it assumes that such a symbol exists. The importance of such a sign, the fact that it is a prerequisite to a place-value system, and the further fact that without it the Hindu-Arabic numerals would never have dominated the computation system of the western world, make it proper to devote a chapter to its origin and history.

It was some centuries after the primitive Brāhmī and Kharoṣṭhī numerals had made their appearance in India that the zero first appeared there, although such a character was used by the Babylonians^[185] in the centuries immediately preceding the Christian era. The symbol is 𐎶 or 𐎵, and apparently it was not used in calculation. Nor does it always occur when units of any order are lacking; thus 180 is written 𐎶𐎶𐎶 with the meaning three sixties and no units, since 181 immediately following is 𐎶𐎶𐎶 𐎵, three sixties and one unit.^[186] The main use of this Babylonian symbol seems to have been in the fractions, 60ths, 3600ths, etc., and somewhat similar to the Greek use of ο, for οὐδέν, with the meaning *vacant*.

"The earliest undoubted occurrence of a zero in India is an inscription at Gwalior, dated Samvat 933 (876 A.D.). Where 50 garlands are mentioned (line 20), 50 is written ५०. 270 (line 4) is written २७०."^[187] The Bakhṣālī Manuscript^[188] probably antedates this, using the point or dot as a zero symbol. Bayley mentions a grant of Jaika Rashtrakūta of Bharuj, found at Okamandel, of date 738 A.D., which contains a zero, and also a coin with indistinct Gupta date 707 (897 A.D.), but the reliability of Bayley's work is questioned. As has been noted, the appearance of the numerals in inscriptions and on coins would be of much later occurrence than the origin and written exposition of the system. From the period mentioned the spread was rapid over all of India, save the southern part, where the Tamil and Malayalam people retain the old system even to the present day.^[189]

Aside from its appearance in early inscriptions, there is still another indication of the Hindu origin of the symbol in the special treatment of the concept zero in the early works on arithmetic. Brahmagupta, who lived in Ujjain, the center of Indian astronomy,^[190] in the early part of the seventh century, gives in his arithmetic^[191] a distinct treatment of the properties of zero. He does not discuss a symbol, but he shows by his treatment that in some way zero had acquired a special significance not found in the Greek or other ancient arithmetics. A still more scientific treatment is given by Bhāskara,^[192] although in one

place he permits himself an unallowed liberty in dividing by zero. The most recently discovered work of ancient Indian mathematical lore, the *Ganita-Sāra-Saṅgraha*^[193] of Mahāvīrācārya (c. 830 A.D.), while it does not use the numerals with place value, has a similar discussion of the calculation with zero.

What suggested the form for the zero is, of course, purely a matter of conjecture. The dot, which the Hindus used to fill up lacunæ in their manuscripts, much as we indicate a break in a sentence,^[194] would have been a more natural symbol; and this is the one which the Hindus first used^[195] and which most Arabs use to-day. There was also used for this purpose a cross, like our X, and this is occasionally found as a zero symbol.^[196] In the Bakhṣālī manuscript above mentioned, the word *śūnya*, with the dot as its symbol, is used to denote the unknown quantity, as well as to denote zero. An analogous use of the zero, for the unknown quantity in a proportion, appears in a Latin manuscript of some lectures by Gottfried Wolack in the University of Erfurt in 1467 and 1468.^[197] The usage was noted even as early as the eighteenth century.^[198]

The small circle was possibly suggested by the spurred circle which was used for ten.^[199] It has also been thought that the omicron used by Ptolemy in his *Almagest*, to mark accidental blanks in the sexagesimal system which he employed, may have influenced the Indian writers.^[200] This symbol was used quite generally in Europe and Asia, and the Arabic astronomer Al-Battānī^[201] (died 929 A.D.) used a similar symbol in connection with the alphabetic system of numerals. The occasional use by Al-Battānī of the Arabic negative, *lā*, to indicate the absence of minutes (or seconds), is noted by Nallino.^[202] Noteworthy is also the use of the ○ for unity in the Śāradā characters of the Kashmirian Atharva-Veda, the writing being at least 400 years old. Bhāskara (c. 1150) used a small circle above a number to indicate subtraction, and in the Tartar writing a redundant word is removed by drawing an oval around it. It would be interesting to know whether our score mark ④, read "four in the hole," could trace its pedigree to the same sources. O'Creat^[203] (c. 1130), in a letter to his teacher, Adelhard of Bath, uses τ for zero, being an abbreviation for the word *teca* which we shall see was one of the names used for zero, although it could quite as well be from τζίφρα. More rarely O'Creat uses ⓪, applying the name *cyfra* to both forms. Frater Sigsboto^[204] (c. 1150) uses the same symbol. Other peculiar forms are noted by Heiberg^[205] as being in use among the Byzantine Greeks in the fifteenth century. It is evident from the text that some of these writers did not understand the import of the new system.^[206]

Although the dot was used at first in India, as noted above, the small circle later replaced it and continues in use to this day. The Arabs, however, did not adopt the circle, since it bore some resemblance to the letter which expressed the number five in the alphabet system.^[207] The earliest Arabic zero known is the dot, used in a manuscript of 873 A.D.^[208] Sometimes both the dot and the circle are used in the same work, having the same meaning, which is the case in an Arabic MS., an abridged arithmetic of Jamshid,^[209] 982 A.H. (1575 A.D.). As given in this work the numerals are ٩ ٨ ٧ ٦ ٥ ٤ ٣ ٢ ١ ٠. The form for 5

varies, in some works becoming  or ;  is found in Egypt and  appears in some fonts of type. To-day the Arabs use the 0 only when, under European influence, they adopt the ordinary system. Among the Chinese the first definite trace of zero is in the work of Tsin^[210] of 1247 A.D. The form is the circular one of the Hindus, and undoubtedly was brought to China by some traveler.

The name of this all-important symbol also demands some attention, especially as we are even yet quite undecided as to what to call it. We speak of it to-day as *zero*, *naught*, and even *cipher*; the telephone operator often calls it *O*, and the illiterate or careless person calls it *aught*. In view of all this uncertainty we may well inquire what it has been called in the past.^[211]

As already stated, the Hindus called it *śūnya*, "void."^[212] This passed over into the Arabic as *aṣ-ṣifr* or *ṣifr*.^[213] When Leonard of Pisa (1202) wrote upon the Hindu numerals he spoke of this character as *zephirum*.^[214] Maximus Planudes (1330), writing under both the Greek and the Arabic influence, called it *tziphra*.^[215] In a treatise on arithmetic written in the Italian language by Jacob of Florence^[216] (1307) it is called *zeuero*,^[217] while in an arithmetic of Giovanni di Danti of Arezzo (1370) the word appears as *ḡeuero*.^[218] Another form is *zepiro*,^[219] which was also a step from *zephirum* to zero.^[220]

Of course the English *cipher*, French *chiffre*, is derived from the same Arabic word, *aṣ-ṣifr*, but in several languages it has come to mean the numeral figures in general. A trace of this appears in our word *ciphering*, meaning figuring or computing.^[221] Johann Huswirt^[222] uses the word with both meanings; he gives for the tenth character the four names *theca*, *circulus*, *cifra*, and *figura nihili*. In this statement Huswirt probably follows, as did many writers of that period, the *Algorismus* of Johannes de Sacrobosco (c. 1250 A.D.), who was also known as John of Halifax or John of Holywood. The commentary of Petrus de Dacia^[223] (c. 1291 A.D.) on the *Algorismus vulgaris* of Sacrobosco was also widely used. The widespread use of this Englishman's work on arithmetic in the universities of that time is attested by the large number^[224] of MSS. from the thirteenth to the seventeenth century still extant, twenty in Munich, twelve in Vienna, thirteen in Erfurt, several in England given by Halliwell,^[225] ten listed in Coxe's *Catalogue of the Oxford College Library*, one in the Plimpton collection,^[226] one in the Columbia University Library, and, of course, many others.

From *aṣ-ṣifr* has come *zephyr*, *cipher*, and finally the abridged form *zero*. The earliest printed work in which is found this final form appears to be Calandri's arithmetic of 1491,^[227] while in manuscript it appears at least as early as the middle of the fourteenth century.^[228] It also appears in a work, *Le Kadran des marchans*, by Jehan Certain,^[229] written in 1485. This word soon became fairly well known in Spain^[230] and France.^[231] The medieval writers also spoke of it as the *sipos*,^[232] and occasionally as the *wheel*,^[233] *circulus*^[234] (in German *das Ringlein*^[235]), *circular note*,^[236] *theca*,^[237] long supposed to be from its resemblance to the Greek theta, but explained by Petrus de Dacia as being

derived from the name of the iron^[238] used to brand thieves and robbers with a circular mark placed on the forehead or on the cheek. It was also called *omicron*^[239] (the Greek *o*), being sometimes written *ō* or *ϕ* to distinguish it from the letter *o*. It also went by the name *null*^[240] (in the Latin books *nihil*^[241] or *nulla*,^[242] and in the French *rien*^[243]), and very commonly by the name *cipher*.^[244] Wallis^[245] gives one of the earliest extended discussions of the various forms of the word, giving certain other variations worthy of note, as *ziphra*, *zifera*, *siphra*, *ciphra*, *tsiphra*, *tziphra*, and the Greek *τζίφρα*.^[246]

CHAPTER V

THE QUESTION OF THE INTRODUCTION OF THE NUMERALS INTO EUROPE BY BOETHIUS

Just as we were quite uncertain as to the origin of the numeral forms, so too are we uncertain as to the time and place of their introduction into Europe. There are two general theories as to this introduction. The first is that they were carried by the Moors to Spain in the eighth or ninth century, and thence were transmitted to Christian Europe, a theory which will be considered later. The second, advanced by Woepcke,^[247] is that they were not brought to Spain by the Moors, but that they were already in Spain when the Arabs arrived there, having reached the West through the Neo-Pythagoreans. There are two facts to support this second theory: (1) the forms of these numerals are characteristic, differing materially from those which were brought by Leonardo of Pisa from Northern Africa early in the thirteenth century (before 1202 A.D.); (2) they are essentially those which tradition has so persistently assigned to Boethius (c. 500 A.D.), and which he would naturally have received, if at all, from these same Neo-Pythagoreans or from the sources from which they derived them. Furthermore, Woepcke points out that the Arabs on entering Spain (711 A.D.) would naturally have followed their custom of adopting for the computation of taxes the numerical systems of the countries they conquered,^[248] so that the numerals brought from Spain to Italy, not having undergone the same modifications as those of the Eastern Arab empire, would have differed, as they certainly did, from those that came through Bagdad. The theory is that the Hindu system, without the zero, early reached Alexandria (say 450 A.D.), and that the Neo-Pythagorean love for the mysterious and especially for the Oriental led to its use as something bizarre and cabalistic; that it was then passed along the Mediterranean, reaching Boethius in Athens or in Rome, and to the schools of Spain, being discovered in Africa and Spain by the Arabs even before they themselves knew the improved system with the place value.

A recent theory set forth by Bubnov^[249] also deserves mention, chiefly because of the seriousness of purpose shown by this well-known writer. Bubnov holds that the forms first found in Europe are derived from ancient symbols used on the abacus, but that the zero is of Hindu origin. This theory does not seem tenable, however, in the light of the evidence already set forth.

Two questions are presented by Woepcke's theory: (1) What was the nature of these Spanish numerals, and how were they made known to Italy? (2) Did Boethius know them?

The Spanish forms of the numerals were called the *ḥurūf al-ğobār*, the *ğobār* or dust numerals, as distinguished from the *ḥurūf al-jumal* or alphabetic numerals. Probably the latter, under the influence of the Syrians or Jews,^[250] were also used by the Arabs. The significance of the term *ğobār* is doubtless that these numerals were written on the dust abacus, this plan being distinct from the counter method of representing numbers. It is also worthy of note that Al-Bīrūnī states that the Hindus often performed numerical computations in the sand. The term is found as early as c. 950, in the verses of an anonymous writer of Kairwān, in Tunis, in which the author speaks of one of his works on *ğobār* calculation,^[251] and, much later, the Arab writer Abū Bekr Moḥammed ibn 'Abdallāh, surnamed al-Ḥaṣṣār (the arithmetician), wrote a work of which the second chapter was "On the dust figures."^[252]

The *ğobār* numerals themselves were first made known to modern scholars by Silvestre de Sacy, who discovered them in an Arabic manuscript from the library of the ancient abbey of St.-Germain-des-Prés.^[253] The system has nine characters, but no zero. A dot above a character indicates tens, two dots hundreds, and so on, $\dot{5}$ meaning 50, and $\ddot{5}$ meaning 5000. It has been suggested that possibly these dots, sprinkled like dust above the numerals, gave rise to the word *ğobār*,^[254] but this is not at all probable. This system of dots is found in Persia at a much later date with numerals quite like the modern Arabic;^[255] but that it was used at all is significant, for it is hardly likely that the western system would go back to Persia, when the perfected Hindu one was near at hand.

At first sight there would seem to be some reason for believing that this feature of the *ğobār* system was of Arabic origin, and that the present zero of these people,^[256] the dot, was derived from it. It was entirely natural that the Semitic people generally should have adopted such a scheme, since their diacritical marks would suggest it, not to speak of the possible influence of the Greek accents in the Hellenic number system. When we consider, however, that the dot is found for zero in the Bakhṣālī manuscript,^[257] and that it was used in subscript form in the *Kitāb al-Fihrist*^[258] in the tenth century, and as late as the sixteenth century,^[259] although in this case probably under Arabic influence, we are forced to believe that this form may also have been of Hindu origin.

The fact seems to be that, as already stated,^[260] the Arabs did not immediately adopt the Hindu zero, because it resembled their 5; they used the superscript dot as serving their purposes fairly well; they may, indeed, have carried this to the west and have added it to the *ğobār* forms already there, just as they transmitted it to the Persians. Furthermore, the Arab and Hebrew scholars of Northern Africa in the tenth century knew these numerals as Indian forms, for a commentary on the *Sēfer Yeṣirāh* by Abū Sahl ibn Tamim (probably composed at Kairwān, c. 950) speaks of "the Indian arithmetic known under the name of *ğobār* or dust calculation."^[261] All this suggests that the Arabs may very likely have known the *ğobār* forms before the numerals reached them again in 773.^[262] The term

"ġobār numerals" was also used without any reference to the peculiar use of dots.^[263] In this connection it is worthy of mention that the Algerians employed two different forms of numerals in manuscripts even of the fourteenth century,^[264] and that the Moroccans of to-day employ the European forms instead of the present Arabic.

The Indian use of subscript dots to indicate the tens, hundreds, thousands, etc., is established by a passage in the *Kitāb al-Fihrist*^[265] (987 A.D.) in which the writer discusses the written language of the people of India. Notwithstanding the importance of this reference for the early history of the numerals, it has not been mentioned by previous writers on this subject. The numeral forms given are those which have usually been called Indian,^[266] in opposition to ġobār. In this document the dots are placed below the characters, instead of being superposed as described above. The significance was the same.

In form these ġobār numerals resemble our own much more closely than the Arab numerals do. They varied more or less, but were substantially as follows:

1 ^[267]	٩	٨	٧	٦	٥	٤	٣	٢	١
2 ^[268]	٩	٨	٧	٦	٥	٤	٣	٢	١
3 ^[269]	٠	٩	٧	٥	٤	٣	٢	١	
4 ^[270]	٠	٩	٧	٥	٤	٣	٢	١	
5 ^[271]	١	٨	٧	٥	٤	٣	٢	١	
6 ^[271]	١	٨	٧	٥	٤	٣	٢	١	

The question of the possible influence of the Egyptian demotic and hieratic ordinal forms has been so often suggested that it seems well to introduce them at this point, for comparison with the ġobār forms. They would as appropriately be used in connection with the Hindu forms, and the evidence of a relation of the first three with all these systems is apparent. The only further resemblance is in the Demotic 4 and in the 9, so that the statement that the Hindu forms in general came from this source has no foundation. The first four Egyptian cardinal numerals^[272] resemble more the modern Arabic.

1	1
2	2
3	3, 3
4	2, 2
5	2, 2
6	2, 2
7	2, 2
8	2, 2
9	2, 2
10	2, 2
11	2, 2
12	2, 2
13	2, 2
14	2, 2
15	2, 2
16	2, 2
17	2, 2
18	2, 2
19	2, 2
20	2, 2
21	2, 2
22	2, 2
23	2, 2
24	2, 2
25	2, 2
26	2, 2
27	2, 2
28	2, 2
29	2, 2
30	2, 2
31	2, 2
32	2, 2
33	2, 2
34	2, 2
35	2, 2
36	2, 2
37	2, 2
38	2, 2
39	2, 2
40	2, 2
41	2, 2
42	2, 2
43	2, 2
44	2, 2
45	2, 2
46	2, 2
47	2, 2
48	2, 2
49	2, 2
50	2, 2
51	2, 2
52	2, 2
53	2, 2
54	2, 2
55	2, 2
56	2, 2
57	2, 2
58	2, 2
59	2, 2
60	2, 2
61	2, 2
62	2, 2
63	2, 2
64	2, 2
65	2, 2
66	2, 2
67	2, 2
68	2, 2
69	2, 2
70	2, 2
71	2, 2
72	2, 2
73	2, 2
74	2, 2
75	2, 2
76	2, 2
77	2, 2
78	2, 2
79	2, 2
80	2, 2
81	2, 2
82	2, 2
83	2, 2
84	2, 2
85	2, 2
86	2, 2
87	2, 2
88	2, 2
89	2, 2
90	2, 2
91	2, 2
92	2, 2
93	2, 2
94	2, 2
95	2, 2
96	2, 2
97	2, 2
98	2, 2
99	2, 2
100	2, 2

DEMOTIC AND
HIERATIC ORDINALS

This theory of the very early introduction of the numerals into Europe fails in several points. In the first place the early Western forms are not known; in the second place some early Eastern forms are like the *gobār*, as is seen in the third line on p. 69, where the forms are from a manuscript written at Shiraz about 970 A.D., and in which some western Arabic forms, e.g. **پ** for 2, are also used. Probably most significant of all is the fact that the *gobār* numerals as given by Sacy are all, with the exception of the symbol for eight, either single Arabic letters or combinations of letters. So much for the Woepcke theory and the meaning of the *gobār* numerals.

We now have to consider the question as to whether Boethius knew these *gobār* forms, or forms akin to them.

This large question^[273] suggests several minor ones: (1) Who was Boethius? (2) Could he have known these numerals? (3) Is there any positive or strong circumstantial evidence that he did know them? (4) What are the probabilities in the case?

First, who was Boethius,—Divus^[274] Boethius as he was called in the Middle Ages? Anicius Manlius Severinus Boethius^[275] was born at Rome c. 475. He was a member of the distinguished family of the Anicii,^[276] which had for some time before his birth been Christian. Early left an orphan, the tradition is that he was taken to Athens at about the age of ten, and that he remained there eighteen years.^[277] He married Rusticiana, daughter of the senator Symmachus, and this union of two such powerful families allowed him to move in the highest circles.^[278] Standing strictly for the right, and against all iniquity at court, he became the object of hatred on the part of all the unscrupulous element near the throne, and his bold defense of the ex-consul Albinus, unjustly accused of treason, led to his imprisonment at Pavia^[279] and his execution in 524.^[280] Not many generations after his death, the period being one in which historical criticism was at its lowest ebb, the church found it profitable to look upon his execution as a martyrdom.^[281] He was accordingly looked upon as a saint,^[282] his bones were enshrined,^[283] and as a natural consequence his books were among the

classics in the church schools for a thousand years.^[284] It is pathetic, however, to think of the medieval student trying to extract mental nourishment from a work so abstract, so meaningless, so unnecessarily complicated, as the arithmetic of Boethius.

He was looked upon by his contemporaries and immediate successors as a master, for Cassiodorus^[285] (c. 490-c. 585 A.D.) says to him: "Through your translations the music of Pythagoras and the astronomy of Ptolemy are read by those of Italy, and the arithmetic of Nicomachus and the geometry of Euclid are known to those of the West."^[286] Founder of the medieval scholasticism, distinguishing the trivium and quadrivium,^[287] writing the only classics of his time, Gibbon well called him "the last of the Romans whom Cato or Tully could have acknowledged for their countryman."^[288]

The second question relating to Boethius is this: Could he possibly have known the Hindu numerals? In view of the relations that will be shown to have existed between the East and the West, there can only be an affirmative answer to this question. The numerals had existed, without the zero, for several centuries; they had been well known in India; there had been a continued interchange of thought between the East and West; and warriors, ambassadors, scholars, and the restless trader, all had gone back and forth, by land or more frequently by sea, between the Mediterranean lands and the centers of Indian commerce and culture. Boethius could very well have learned one or more forms of Hindu numerals from some traveler or merchant.

To justify this statement it is necessary to speak more fully of these relations between the Far East and Europe. It is true that we have no records of the interchange of learning, in any large way, between eastern Asia and central Europe in the century preceding the time of Boethius. But it is one of the mistakes of scholars to believe that they are the sole transmitters of knowledge. As a matter of fact there is abundant reason for believing that Hindu numerals would naturally have been known to the Arabs, and even along every trade route to the remote west, long before the zero entered to make their place-value possible, and that the characters, the methods of calculating, the improvements that took place from time to time, the zero when it appeared, and the customs as to solving business problems, would all have been made known from generation to generation along these same

trade routes from the Orient to the Occident. It must always be kept in mind that it was to the tradesman and the wandering scholar that the spread of such learning was due, rather than to the school man. Indeed, Avicenna^[289] (980-1037 A.D.) in a short biography of himself relates that when his people were living at Bokhāra his father sent him to the house of a grocer to learn the Hindu art of reckoning, in which this grocer (oil dealer, possibly) was expert. Leonardo of Pisa, too, had a similar training.

The whole question of this spread of mercantile knowledge along the trade routes is so connected with the ḡobār numerals, the Boethius question, Gerbert, Leonardo of Pisa, and other names and events, that a digression for its consideration now becomes necessary.^[290]

Even in very remote times, before the Hindu numerals were sculptured in the cave of Nānā Ghāt, there were trade relations between Arabia and India. Indeed, long before the Aryans went to India the great Turanian race had spread its civilization from the Mediterranean to the Indus.^[291] At a much later period the Arabs were the intermediaries between Egypt and Syria on the west, and the farther Orient.^[292] In the sixth century B.C., Hecatæus,^[293] the father of geography, was acquainted not only with the Mediterranean lands but with the countries as far as the Indus,^[294] and in Biblical times there were regular triennial voyages to India. Indeed, the story of Joseph bears witness to the caravan trade from India, across Arabia, and on to the banks of the Nile. About the same time as Hecatæus, Scylax, a Persian admiral under Darius, from Caryanda on the coast of Asia Minor, traveled to northwest India and wrote upon his ventures.^[295] He induced the nations along the Indus to acknowledge the Persian supremacy, and such number systems as there were in these lands would naturally have been known to a man of his attainments.

A century after Scylax, Herodotus showed considerable knowledge of India, speaking of its cotton and its gold,^[296] telling how Sesostris^[297] fitted out ships to sail to that country, and mentioning the routes to the east. These routes were generally by the Red Sea, and had been followed by the Phœnicians and the Sabæans, and later were taken by the Greeks and Romans.^[298]

In the fourth century B.C. the West and East came into very close relations. As early as 330, Pytheas of Massilia (Marseilles) had explored as far north as the northern end of the British Isles and the coasts of the German Sea, while Macedon, in close touch with southern France, was also sending her armies under Alexander^[299] through Afghanistan as far east as the Punjab.^[300] Pliny tells us that Alexander the Great employed surveyors to measure the roads of India; and one of the great highways is described by Megasthenes, who in 295 B.C., as the ambassador of Seleucus, resided at Pātalīpuṭra, the present Patna.^[301]

The Hindus also learned the art of coining from the Greeks, or possibly from the Chinese, and the stores of Greco-Hindu coins still found in northern India are a constant source of historical information.^[302] The Rāmāyana speaks of merchants traveling in great caravans and embarking by sea for foreign lands.^[303] Ceylon traded with Malacca and Siam, and Java was colonized by Hindu traders, so that mercantile knowledge was being spread about the Indies during all the formative period of the numerals.

Moreover the results of the early Greek invasion were embodied by Dicæarchus of Messana (about 320 B.C.) in a map that long remained a standard. Furthermore, Alexander did not allow his influence on the East to cease. He divided India into three satrapies,^[304] placing Greek governors over two of them and leaving a Hindu ruler in charge of the third, and in Bactriana, a part of Ariana or ancient Persia, he left governors; and in these the western civilization was long in evidence. Some of the Greek and Roman metrical and astronomical terms found their way, doubtless at this time, into the Sanskrit language.^[305] Even as late as from the second to the fifth centuries A.D., Indian coins showed the Hellenic influence. The Hindu astronomical terminology reveals the same relationship to western thought, for Varāha-Mihira (6th century A.D.), a contemporary of Āryabhaṭa, entitled a work of his the *Brhat-Saṃhitā*, a literal translation of μεγάλη σύνταξις of Ptolemy;^[306] and in various ways is this interchange of ideas apparent.^[307] It could not have been at all unusual for the ancient Greeks to go to India, for Strabo lays down the route, saying that all who make the journey start from Ephesus and traverse Phrygia and Cappadocia before taking the direct road.^[308] The products of the East were always finding their way to the

West, the Greeks getting their ginger^[309] from Malabar, as the Phœnicians had long before brought gold from Malacca.

Greece must also have had early relations with China, for there is a notable similarity between the Greek and Chinese life, as is shown in their houses, their domestic customs, their marriage ceremonies, the public story-tellers, the puppet shows which Herodotus says were introduced from Egypt, the street jugglers, the games of dice,^[310] the game of finger-guessing,^[311] the water clock, the music system, the use of the myriad,^[312] the calendars, and in many other ways.^[313] In passing through the suburbs of Peking to-day, on the way to the Great Bell temple, one is constantly reminded of the semi-Greek architecture of Pompeii, so closely does modern China touch the old classical civilization of the Mediterranean. The Chinese historians tell us that about 200 B.C. their arms were successful in the far west, and that in 180 B.C. an ambassador went to Bactria, then a Greek city, and reported that Chinese products were on sale in the markets there.^[314] There is also a noteworthy resemblance between certain Greek and Chinese words,^[315] showing that in remote times there must have been more or less interchange of thought.

The Romans also exchanged products with the East. Horace says, "A busy trader, you hasten to the farthest Indies, flying from poverty over sea, over crags, over fires."^[316] The products of the Orient, spices and jewels from India, frankincense from Persia, and silks from China, being more in demand than the exports from the Mediterranean lands, the balance of trade was against the West, and thus Roman coin found its way eastward. In 1898, for example, a number of Roman coins dating from 114 B.C. to Hadrian's time were found at Paklī, a part of the Hazāra district, sixteen miles north of Abbottābād,^[317] and numerous similar discoveries have been made from time to time.

Augustus speaks of envoys received by him from India, a thing never before known,^[318] and it is not improbable that he also received an embassy from China.^[319] Suetonius (first century A.D.) speaks in his history of these relations,^[320] as do several of his contemporaries,^[321] and Vergil^[322] tells of Augustus doing battle in Persia. In Pliny's time the trade of the Roman Empire with Asia amounted to a million and a quarter dollars a year, a sum

far greater relatively then than now,^[323] while by the time of Constantine Europe was in direct communication with the Far East.^[324]

In view of these relations it is not beyond the range of possibility that proof may sometime come to light to show that the Greeks and Romans knew something of the number system of India, as several writers have maintained.^[325]

Returning to the East, there are many evidences of the spread of knowledge in and about India itself. In the third century B.C. Buddhism began to be a connecting medium of thought. It had already permeated the Himalaya territory, had reached eastern Turkestan, and had probably gone thence to China. Some centuries later (in 62 A.D.) the Chinese emperor sent an ambassador to India, and in 67 A.D. a Buddhist monk was invited to China.^[326] Then, too, in India itself Aśoka, whose name has already been mentioned in this work, extended the boundaries of his domains even into Afghanistan, so that it was entirely possible for the numerals of the Punjab to have worked their way north even at that early date.^[327]

Furthermore, the influence of Persia must not be forgotten in considering this transmission of knowledge. In the fifth century the Persian medical school at Jondi-Sapur admitted both the Hindu and the Greek doctrines, and Firdusī tells us that during the brilliant reign of Khosrū I,^[328] the golden age of Pahlavī literature, the Hindu game of chess was introduced into Persia, at a time when wars with the Greeks were bringing prestige to the Sassanid dynasty.

Again, not far from the time of Boethius, in the sixth century, the Egyptian monk Cosmas, in his earlier years as a trader, made journeys to Abyssinia and even to India and Ceylon, receiving the name *Indicopleustes* (the Indian traveler). His map (547 A.D.) shows some knowledge of the earth from the Atlantic to India. Such a man would, with hardly a doubt, have observed every numeral system used by the people with whom he sojourned,^[329] and whether or not he recorded his studies in permanent form he would have transmitted such scraps of knowledge by word of mouth.

As to the Arabs, it is a mistake to feel that their activities began with Mohammed. Commerce had always been held in honor by them, and the

Qoreish^[330] had annually for many generations sent caravans bearing the spices and textiles of Yemen to the shores of the Mediterranean. In the fifth century they traded by sea with India and even with China, and Hira was an emporium for the wares of the East,^[331] so that any numeral system of any part of the trading world could hardly have remained isolated.

Long before the warlike activity of the Arabs, Alexandria had become the great market-place of the world. From this center caravans traversed Arabia to Hadramaut, where they met ships from India. Others went north to Damascus, while still others made their way along the southern shores of the Mediterranean. Ships sailed from the isthmus of Suez to all the commercial ports of Southern Europe and up into the Black Sea. Hindus were found among the merchants^[332] who frequented the bazaars of Alexandria, and Brahmins were reported even in Byzantium.

Such is a very brief résumé of the evidence showing that the numerals of the Punjab and of other parts of India as well, and indeed those of China and farther Persia, of Ceylon and the Malay peninsula, might well have been known to the merchants of Alexandria, and even to those of any other seaport of the Mediterranean, in the time of Boethius. The Brāhmī numerals would not have attracted the attention of scholars, for they had no zero so far as we know, and therefore they were no better and no worse than those of dozens of other systems. If Boethius was attracted to them it was probably exactly as any one is naturally attracted to the bizarre or the mystic, and he would have mentioned them in his works only incidentally, as indeed they are mentioned in the manuscripts in which they occur.

In answer therefore to the second question, Could Boethius have known the Hindu numerals? the reply must be, without the slightest doubt, that he could easily have known them, and that it would have been strange if a man of his inquiring mind did not pick up many curious bits of information of this kind even though he never thought of making use of them.

Let us now consider the third question, Is there any positive or strong circumstantial evidence that Boethius did know these numerals? The question is not new, nor is it much nearer being answered than it was over two centuries ago when Wallis (1693) expressed his doubts about it^[333] soon after Vossius (1658) had called attention to the matter.^[334] Stated

briefly, there are three works on mathematics attributed to Boethius:^[335] (1) the arithmetic, (2) a work on music, and (3) the geometry.^[336]

The genuineness of the arithmetic and the treatise on music is generally recognized, but the geometry, which contains the Hindu numerals with the zero, is under suspicion.^[337] There are plenty of supporters of the idea that Boethius knew the numerals and included them in this book,^[338] and on the other hand there are as many who feel that the geometry, or at least the part mentioning the numerals, is spurious.^[339] The argument of those who deny the authenticity of the particular passage in question may briefly be stated thus:

1. The falsification of texts has always been the subject of complaint. It was so with the Romans,^[340] it was common in the Middle Ages,^[341] and it is much more prevalent to-day than we commonly think. We have but to see how every hymn-book compiler feels himself authorized to change at will the classics of our language, and how unknown editors have mutilated Shakespeare, to see how much more easy it was for medieval scribes to insert or eliminate paragraphs without any protest from critics.^[342]

2. If Boethius had known these numerals he would have mentioned them in his arithmetic, but he does not do so.^[343]

3. If he had known them, and had mentioned them in any of his works, his contemporaries, disciples, and successors would have known and mentioned them. But neither Capella (c. 475)^[344] nor any of the numerous medieval writers who knew the works of Boethius makes any reference to the system.^[345]

4. The passage in question has all the appearance of an interpolation by some scribe. Boethius is speaking of angles, in his work on geometry, when the text suddenly changes to a discussion of classes of numbers.^[346] This is followed by a chapter in explanation of the abacus,^[347] in which are described those numeral forms which are called *apices* or *caracteres*.^[348] The forms^[349] of these characters vary in different manuscripts, but in general are about as shown on page 88. They are commonly written with the 9 at the left, decreasing to the unit at the right, numerous writers stating

that this was because they were derived from Semitic sources in which the direction of writing is the opposite of our own. This practice continued until the sixteenth century.^[350] The writer then leaves the subject entirely, using the Roman numerals for the rest of his discussion, a proceeding so foreign to the method of Boethius as to be inexplicable on the hypothesis of authenticity. Why should such a scholarly writer have given them with no mention of their origin or use? Either he would have mentioned some historical interest attaching to them, or he would have used them in some discussion; he certainly would not have left the passage as it is.

FORMS OF THE NUMERALS, LARGELY FROM WORKS ON THE ABACUS^[351]

	1	2	3	4	5	6	7	8	9	0
a ^[352]	I	II	III	IIII	h	L	^	8	9	
b ^[353]	I	II	III	IIII	h	L	^	8	9	
c ^[354]	I	II	III	IIII	h	L	^	8	9	
d ^[355]	I	II	III	IIII	h	L	^	8	9	
e ^[356]	I	II			h	L	^	8	9	
f ^[357]		II	III	IIII	h	L	^	8	9	
g ^[358]	I	II	III	IIII	h	L	^	8	9	
h ^[359]	I	II	III	IIII	h	L	^	8	9	
i ^[360]	I	II	III	IIII	h	L	^	8	9	

Sir E. Clive Bayley has added^[361] a further reason for believing them spurious, namely that the 4 is not of the Nānā Ghāt type, but of the Kabul form which the Arabs did not receive until 776;^[362] so that it is not likely,

even if the characters were known in Europe in the time of Boethius, that this particular form was recognized. It is worthy of mention, also, that in the six abacus forms from the chief manuscripts as given by Friedlein,^[363] each contains some form of zero, which symbol probably originated in India about this time or later. It could hardly have reached Europe so soon.

As to the fourth question, Did Boethius probably know the numerals? It seems to be a fair conclusion, according to our present evidence, that (1) Boethius might very easily have known these numerals without the zero, but, (2) there is no reliable evidence that he did know them. And just as Boethius might have come in contact with them, so any other inquiring mind might have done so either in his time or at any time before they definitely appeared in the tenth century. These centuries, five in number, represented the darkest of the Dark Ages, and even if these numerals were occasionally met and studied, no trace of them would be likely to show itself in the literature of the period, unless by chance it should get into the writings of some man like Alcuin. As a matter of fact, it was not until the ninth or tenth century that there is any tangible evidence of their presence in Christendom. They were probably known to merchants here and there, but in their incomplete state they were not of sufficient importance to attract any considerable attention.

As a result of this brief survey of the evidence several conclusions seem reasonable: (1) commerce, and travel for travel's sake, never died out between the East and the West; (2) merchants had every opportunity of knowing, and would have been unreasonably stupid if they had not known, the elementary number systems of the peoples with whom they were trading, but they would not have put this knowledge in permanent written form; (3) wandering scholars would have known many and strange things about the peoples they met, but they too were not, as a class, writers; (4) there is every reason a priori for believing that the *ḡobār* numerals would have been known to merchants, and probably to some of the wandering scholars, long before the Arabs conquered northern Africa; (5) the wonder is not that the Hindu-Arabic numerals were known about 1000 A.D., and that they were the subject of an elaborate work in 1202 by Fibonacci, but rather that more extended manuscript evidence of their appearance before that time has not been found. That they were more or less known early in the Middle Ages, certainly to many merchants of Christian Europe, and

probably to several scholars, but without the zero, is hardly to be doubted. The lack of documentary evidence is not at all strange, in view of all of the circumstances.

CHAPTER VI

THE DEVELOPMENT OF THE NUMERALS AMONG THE ARABS

If the numerals had their origin in India, as seems most probable, when did the Arabs come to know of them? It is customary to say that it was due to the influence of Mohammedanism that learning spread through Persia and Arabia; and so it was, in part. But learning was already respected in these countries long before Mohammed appeared, and commerce flourished all through this region. In Persia, for example, the reign of Khosrū Nušīrwān, [364] the great contemporary of Justinian the law-maker, was characterized not only by an improvement in social and economic conditions, but by the cultivation of letters. Khosrū fostered learning, inviting to his court scholars from Greece, and encouraging the introduction of culture from the West as well as from the East. At this time Aristotle and Plato were translated, and portions of the *Hito-padēśa*, or Fables of Pilpay, were rendered from the Sanskrit into Persian. All this means that some three centuries before the great intellectual ascendancy of Bagdad a similar fostering of learning was taking place in Persia, and under pre-Mohammedan influences.

The first definite trace that we have of the introduction of the Hindu system into Arabia dates from 773 A.D., [365] when an Indian astronomer visited the court of the caliph, bringing with him astronomical tables which at the caliph's command were translated into Arabic by Al-Fazārī. [366] Al-Khowārazmī and Ḥabash (Aḥmed ibn ‘Abdallāh, died c. 870) based their well-known tables upon the work of Al-Fāzārī. It may be asserted as highly probable that the numerals came at the same time as the tables. They were certainly known a few decades later, and before 825 A.D., about which time the original of the *Algoritmi de numero Indorum* was written, as that work makes no pretense of being the first work to treat of the Hindu numerals.

The three writers mentioned cover the period from the end of the eighth to the end of the ninth century. While the historians Al-Maś‘ūdī and Al-Bīrūnī

follow quite closely upon the men mentioned, it is well to note again the Arab writers on Hindu arithmetic, contemporary with Al-Khowārazmī, who were mentioned in chapter I, viz. Al-Kindī, Sened ibn 'Alī, and Al-Šūfī.

For over five hundred years Arabic writers and others continued to apply to works on arithmetic the name "Indian." In the tenth century such writers are 'Abdallāh ibn al-Ḥasan, Abū 'l-Qāsim^[367] (died 987 A.D.) of Antioch, and Moḥammed ibn 'Abdallāh, Abū Naṣr^[368] (c. 982), of Kalwādā near Bagdad. Others of the same period or earlier (since they are mentioned in the *Fihrist*,^[369] 987 A.D.), who explicitly use the word "Hindu" or "Indian," are Sinān ibn al-Faṭḥ^[370] of Ḥarrān, and Ahmed ibn 'Omar, al-Karābīsī.^[371] In the eleventh century come Al-Bīrūnī^[372] (973-1048) and 'Ali ibn Aḥmed, Abū 'l-Ḥasan, Al-Nasawī^[373] (c. 1030). The following century brings similar works by Ishāq ibn Yūsuf al-Šardafī^[374] and Samū'īl ibn Yaḥyā ibn 'Abbās al-Mağrebī al-Andalusī^[375] (c. 1174), and in the thirteenth century are 'Abdallatīf ibn Yūsuf ibn Moḥammed, Muwaffaq al-Dīn Abū Moḥammed al-Bağdādī^[376] (c. 1231), and Ibn al-Bannā.^[377]

The Greek monk Maximus Planudes, writing in the first half of the fourteenth century, followed the Arabic usage in calling his work *Indian Arithmetic*.^[378] There were numerous other Arabic writers upon arithmetic, as that subject occupied one of the high places among the sciences, but most of them did not feel it necessary to refer to the origin of the symbols, the knowledge of which might well have been taken for granted.

One document, cited by Woepcke,^[379] is of special interest since it shows at an early period, 970 A.D., the use of the ordinary Arabic forms alongside the ḡobār. The title of the work is *Interesting and Beautiful Problems on Numbers* copied by Aḥmed ibn Moḥammed ibn 'Abdaljalīl, Abū Sa'īd, al-Sijzī,^[380] (951-1024) from a work by a priest and physician, Naẓīf ibn Yumn,^[381] al-Qass (died c. 990). Suter does not mention this work of Naẓīf.

The second reason for not ascribing too much credit to the purely Arab influence is that the Arab by himself never showed any intellectual strength. What took place after Moḥammed had lighted the fire in the hearts of his people was just what always takes place when different types of strong races blend,—a great renaissance in divers lines. It was seen in the blending

of such types at Miletus in the time of Thales, at Rome in the days of the early invaders, at Alexandria when the Greek set firm foot on Egyptian soil, and we see it now when all the nations mingle their vitality in the New World. So when the Arab culture joined with the Persian, a new civilization rose and flourished.^[382] The Arab influence came not from its purity, but from its intermingling with an influence more cultured if less virile.

As a result of this interactivity among peoples of diverse interests and powers, Mohammedanism was to the world from the eighth to the thirteenth century what Rome and Athens and the Italo-Hellenic influence generally had been to the ancient civilization. "If they did not possess the spirit of invention which distinguished the Greeks and the Hindus, if they did not show the perseverance in their observations that characterized the Chinese astronomers, they at least possessed the virility of a new and victorious people, with a desire to understand what others had accomplished, and a taste which led them with equal ardor to the study of algebra and of poetry, of philosophy and of language."^[383]

It was in 622 A.D. that Moḥammed fled from Mecca, and within a century from that time the crescent had replaced the cross in Christian Asia, in Northern Africa, and in a goodly portion of Spain. The Arab empire was an ellipse of learning with its foci at Bagdad and Cordova, and its rulers not infrequently took pride in demanding intellectual rather than commercial treasure as the result of conquest.^[384]

It was under these influences, either pre-Mohammedan or later, that the Hindu numerals found their way to the North. If they were known before Moḥammed's time, the proof of this fact is now lost. This much, however, is known, that in the eighth century they were taken to Bagdad. It was early in that century that the Mohammedans obtained their first foothold in northern India, thus foreshadowing an epoch of supremacy that endured with varied fortunes until after the golden age of Akbar the Great (1542-1605) and Shah Jehan. They also conquered Khorassan and Afghanistan, so that the learning and the commercial customs of India at once found easy access to the newly-established schools and the bazaars of Mesopotamia and western Asia. The particular paths of conquest and of commerce were either by way of the Khyber Pass and through Kabul, Herat and Khorassan, or by sea through the strait of Ormuz to Basra (Busra) at the head of the Persian Gulf,

and thence to Bagdad. As a matter of fact, one form of Arabic numerals, the one now in use by the Arabs, is attributed to the influence of Kabul, while the other, which eventually became our numerals, may very likely have reached Arabia by the other route. It is in Bagdad,^[385] Dār al-Salām—"the Abode of Peace," that our special interest in the introduction of the numerals centers. Built upon the ruins of an ancient town by Al-Manṣūr^[386] in the second half of the eighth century, it lies in one of those regions where the converging routes of trade give rise to large cities.^[387] Quite as well of Bagdad as of Athens might Cardinal Newman have said:^[388]

"What it lost in conveniences of approach, it gained in its neighborhood to the traditions of the mysterious East, and in the loveliness of the region in which it lay. Hither, then, as to a sort of ideal land, where all archetypes of the great and the fair were found in substantial being, and all departments of truth explored, and all diversities of intellectual power exhibited, where taste and philosophy were majestically enthroned as in a royal court, where there was no sovereignty but that of mind, and no nobility but that of genius, where professors were rulers, and princes did homage, thither flocked continually from the very corners of the *orbis terrarum* the many-tongued generation, just rising, or just risen into manhood, in order to gain wisdom." For here it was that Al-Manṣūr and Al-Māmūn and Hārūn al-Rashīd (Aaron the Just) made for a time the world's center of intellectual activity in general and in the domain of mathematics in particular.^[389] It was just after the *Sindhind* was brought to Bagdad that Moḥammed ibn Mūsā al-Khowārazmī, whose name has already been mentioned,^[390] was called to that city. He was the most celebrated mathematician of his time, either in the East or West, writing treatises on arithmetic, the sundial, the astrolabe, chronology, geometry, and algebra, and giving through the Latin transliteration of his name, *algoritmi*, the name of algorism to the early arithmetics using the new Hindu numerals.^[391] Appreciating at once the value of the position system so recently brought from India, he wrote an arithmetic based upon these numerals, and this was translated into Latin in the time of Adelhard of Bath (c. 1180), although possibly by his contemporary countryman Robert Cestrensis.^[392] This translation was found in Cambridge and was published by Boncompagni in 1857.^[393]

Contemporary with Al-Khowārazmī, and working also under Al-Māmūn, was a Jewish astronomer, Abū 'l-Ṭeiyib, Sened ibn 'Alī, who is said to have adopted the Mohammedan religion at the caliph's request. He also wrote a work on Hindu arithmetic,^[394] so that the subject must have been attracting considerable attention at that time. Indeed, the struggle to have the Hindu numerals replace the Arabic did not cease for a long time thereafter. 'Alī ibn Aḥmed al-Nasawī, in his arithmetic of c. 1025, tells us that the symbolism of number was still unsettled in his day, although most people preferred the strictly Arabic forms.^[395]

We thus have the numerals in Arabia, in two forms: one the form now used there, and the other the one used by Al-Khowārazmī. The question then remains, how did this second form find its way into Europe? and this question will be considered in the next chapter.

CHAPTER VII

THE DEFINITE INTRODUCTION OF THE NUMERALS INTO EUROPE

It being doubtful whether Boethius ever knew the Hindu numeral forms, certainly without the zero in any case, it becomes necessary now to consider the question of their definite introduction into Europe. From what has been said of the trade relations between the East and the West, and of the probability that it was the trader rather than the scholar who carried these numerals from their original habitat to various commercial centers, it is evident that we shall never know when they first made their inconspicuous entrance into Europe. Curious customs from the East and from the tropics, —concerning games, social peculiarities, oddities of dress, and the like,—are continually being related by sailors and traders in their resorts in New York, London, Hamburg, and Rotterdam to-day, customs that no scholar has yet described in print and that may not become known for many years, if ever. And if this be so now, how much more would it have been true a thousand years before the invention of printing, when learning was at its lowest ebb. It was at this period of low esteem of culture that the Hindu numerals undoubtedly made their first appearance in Europe.

There were many opportunities for such knowledge to reach Spain and Italy. In the first place the Moors went into Spain as helpers of a claimant of the throne, and remained as conquerors. The power of the Goths, who had held Spain for three centuries, was shattered at the battle of Jerez de la Frontera in 711, and almost immediately the Moors became masters of Spain and so remained for five hundred years, and masters of Granada for a much longer period. Until 850 the Christians were absolutely free as to religion and as to holding political office, so that priests and monks were not infrequently skilled both in Latin and Arabic, acting as official translators, and naturally reporting directly or indirectly to Rome. There was indeed at this time a complaint that Christian youths cultivated too assiduously a love for the literature of the Saracen, and married too frequently the daughters of the infidel.^[396] It is true that this happy state of affairs was not permanent, but while it lasted the learning and the customs of the East must have become more or less the property of Christian Spain. At this time the ḡobār numerals were probably in that country, and these may well have made their way into Europe from the schools of Cordova, Granada, and Toledo.

Furthermore, there was abundant opportunity for the numerals of the East to reach Europe through the journeys of travelers and ambassadors. It was from the records of Suleimān the Merchant, a well-known Arab trader of the ninth century, that part of the story of Sindbād the Sailor was taken.^[397] Such a merchant would have been particularly likely to know the numerals of the people whom he met, and he is a type of man that may well have taken such symbols to European markets. A little later, Abū 'l-Ḥasan 'Alī al-Mas'ūdī (d. 956) of Bagdad traveled to the China Sea on the east, at least as far south as Zanzibar, and to the Atlantic on the west,^[398] and he speaks of the nine figures with which the Hindus reckoned.^[399]

There was also a Bagdad merchant, one Abū 'l-Qāsim 'Obeidallāh ibn Aḥmed, better known by his Persian name Ibn Khordāḡbeh,^[400] who wrote about 850 A.D. a work entitled *Book of Roads and Provinces*^[401] in which the following graphic account appears:^[402] "The Jewish merchants speak Persian, Roman (Greek and Latin), Arabic, French, Spanish, and Slavic. They travel from the West to the East, and from the East to the West, sometimes by land, sometimes by sea. They take ship from France on the

Western Sea, and they voyage to Farama (near the ruins of the ancient Pelusium); there they transfer their goods to caravans and go by land to Colzom (on the Red Sea). They there reëmbark on the Oriental (Red) Sea and go to Hejaz and to Jiddah, and thence to the Sind, India, and China. Returning, they bring back the products of the oriental lands.... These journeys are also made by land. The merchants, leaving France and Spain, cross to Tangier and thence pass through the African provinces and Egypt. They then go to Ramleh, visit Damascus, Kufa, Bagdad, and Basra, penetrate into Ahwaz, Fars, Kerman, Sind, and thus reach India and China." Such travelers, about 900 A.D., must necessarily have spread abroad a knowledge of all number systems used in recording prices or in the computations of the market. There is an interesting witness to this movement, a cruciform brooch now in the British Museum. It is English, certainly as early as the eleventh century, but it is inlaid with a piece of paste on which is the Mohammedan inscription, in Kufic characters, "There is no God but God." How did such an inscription find its way, perhaps in the time of Alcuin of York, to England? And if these Kufic characters reached there, then why not the numeral forms as well?

Even in literature of the better class there appears now and then some stray proof of the important fact that the great trade routes to the far East were never closed for long, and that the customs and marks of trade endured from generation to generation. The *Gulistān* of the Persian poet Sa'dī^[403] contains such a passage:

"I met a merchant who owned one hundred and forty camels, and fifty slaves and porters.... He answered to me: 'I want to carry sulphur of Persia to China, which in that country, as I hear, bears a high price; and thence to take Chinese ware to Roum; and from Roum to load up with brocades for Hind; and so to trade Indian steel (*pûlab*) to Halib. From Halib I will convey its glass to Yeman, and carry the painted cloths of Yeman back to Persia.'"^[404] On the other hand, these men were not of the learned class, nor would they preserve in treatises any knowledge that they might have, although this knowledge would occasionally reach the ears of the learned as bits of curious information.

There were also ambassadors passing back and forth from time to time, between the East and the West, and in particular during the period when

these numerals probably began to enter Europe. Thus Charlemagne (c. 800) sent emissaries to Bagdad just at the time of the opening of the mathematical activity there.^[405] And with such ambassadors must have gone the adventurous scholar, inspired, as Alcuin says of Archbishop Albert of York (766-780),^[406] to seek the learning of other lands. Furthermore, the Nestorian communities, established in Eastern Asia and in India at this time, were favored both by the Persians and by their Mohammedan conquerors. The Nestorian Patriarch of Syria, Timotheus (778-820), sent missionaries both to India and to China, and a bishop was appointed for the latter field. Ibn Wahab, who traveled to China in the ninth century, found images of Christ and the apostles in the Emperor's court.^[407] Such a learned body of men, knowing intimately the countries in which they labored, could hardly have failed to make strange customs known as they returned to their home stations. Then, too, in Alfred's time (849-901) emissaries went from England as far as India,^[408] and generally in the Middle Ages groceries came to Europe from Asia as now they come from the colonies and from America. Syria, Asia Minor, and Cyprus furnished sugar and wool, and India yielded her perfumes and spices, while rich tapestries for the courts and the wealthy burghers came from Persia and from China.^[409] Even in the time of Justinian (c. 550) there seems to have been a silk trade with China, which country in turn carried on commerce with Ceylon,^[410] and reached out to Turkestan where other merchants transmitted the Eastern products westward. In the seventh century there was a well-defined commerce between Persia and India, as well as between Persia and Constantinople.^[411] The Byzantine *commercarii* were stationed at the outposts not merely as customs officers but as government purchasing agents.^[412]

Occasionally there went along these routes of trade men of real learning, and such would surely have carried the knowledge of many customs back and forth. Thus at a period when the numerals are known to have been partly understood in Italy, at the opening of the eleventh century, one Constantine, an African, traveled from Italy through a great part of Africa and Asia, even on to India, for the purpose of learning the sciences of the Orient. He spent thirty-nine years in travel, having been hospitably received in Babylon, and upon his return he was welcomed with great honor at Salerno.^[413]

A very interesting illustration of this intercourse also appears in the tenth century, when the son of Otto I (936-973) married a princess from Constantinople. This monarch was in touch with the Moors of Spain and invited to his court numerous scholars from abroad,^[414] and his intercourse with the East as well as the West must have brought together much of the learning of each.

Another powerful means for the circulation of mysticism and philosophy, and more or less of culture, took its start just before the conversion of Constantine (c. 312), in the form of Christian pilgrim travel. This was a feature peculiar to the zealots of early Christianity, found in only a slight degree among their Jewish predecessors in the annual pilgrimage to Jerusalem, and almost wholly wanting in other pre-Christian peoples. Chief among these early pilgrims were the two Placentians, John and Antonine the Elder (c. 303), who, in their wanderings to Jerusalem, seem to have started a movement which culminated centuries later in the crusades.^[415] In 333 a Bordeaux pilgrim compiled the first Christian guide-book, the *Itinerary from Bordeaux to Jerusalem*,^[416] and from this time on the holy pilgrimage never entirely ceased.

Still another certain route for the entrance of the numerals into Christian Europe was through the pillaging and trading carried on by the Arabs on the northern shores of the Mediterranean. As early as 652 A.D., in the thirtieth year of the Hejira, the Mohammedans descended upon the shores of Sicily and took much spoil. Hardly had the wretched Constans given place to the young Constantine IV when they again attacked the island and plundered ancient Syracuse. Again in 827, under Asad, they ravaged the coasts. Although at this time they failed to conquer Syracuse, they soon held a good part of the island, and a little later they successfully besieged the city. Before Syracuse fell, however, they had plundered the shores of Italy, even to the walls of Rome itself; and had not Leo IV, in 849, repaired the neglected fortifications, the effects of the Moslem raid of that year might have been very far-reaching. Ibn Khordāḍbeh, who left Bagdad in the latter part of the ninth century, gives a picture of the great commercial activity at that time in the Saracen city of Palermo. In this same century they had established themselves in Piedmont, and in 906 they pillaged Turin.^[417] On the Sorrento peninsula the traveler who climbs the hill to the beautiful

Ravello sees still several traces of the Arab architecture, reminding him of the fact that about 900 A.D. Amalfi was a commercial center of the Moors.^[418] Not only at this time, but even a century earlier, the artists of northern India sold their wares at such centers, and in the courts both of Hārūn al-Rashīd and of Charlemagne.^[419] Thus the Arabs dominated the Mediterranean Sea long before Venice

"held the gorgeous East in fee
And was the safeguard of the West,"

and long before Genoa had become her powerful rival.^[420]

Only a little later than this the brothers Nicolo and Maffeo Polo entered upon their famous wanderings.^[421] Leaving Constantinople in 1260, they went by the Sea of Azov to Bokhara, and thence to the court of Kublai Khan, penetrating China, and returning by way of Acre in 1269 with a commission which required them to go back to China two years later. This time they took with them Nicolo's son Marco, the historian of the journey, and went across the plateau of Pamir; they spent about twenty years in China, and came back by sea from China to Persia.

The ventures of the Poli were not long unique, however: the thirteenth century had not closed before Roman missionaries and the merchant Petrus de Lucolongo had penetrated China. Before 1350 the company of missionaries was large, converts were numerous, churches and Franciscan convents had been organized in the East, travelers were appealing for the truth of their accounts to the "many" persons in Venice who had been in China, Tsuan-chau-fu had a European merchant community, and Italian trade and travel to China was a thing that occupied two chapters of a commercial handbook.^[422]

It is therefore reasonable to conclude that in the Middle Ages, as in the time of Boethius, it was a simple matter for any inquiring scholar to become acquainted with such numerals of the Orient as merchants may have used for warehouse or price marks. And the fact that Gerbert seems to have known only the forms of the simplest of these, not comprehending their full significance, seems to prove that he picked them up in just this way.

Even if Gerbert did not bring his knowledge of the Oriental numerals from Spain, he may easily have obtained them from the marks on merchant's goods, had he been so inclined. Such knowledge was probably obtainable in various parts of Italy, though as parts of mere mercantile knowledge the forms might soon have been lost, it needing the pen of the scholar to preserve them. Trade at this time was not stagnant. During the eleventh and twelfth centuries the Slavs, for example, had very great commercial interests, their trade reaching to Kiev and Novgorod, and thence to the East. Constantinople was a great clearing-house of commerce with the Orient,^[423] and the Byzantine merchants must have been entirely familiar with the various numerals of the Eastern peoples. In the eleventh century the Italian town of Amalfi established a factory^[424] in Constantinople, and had trade relations with Antioch and Egypt. Venice, as early as the ninth century, had a valuable trade with Syria and Cairo.^[425] Fifty years after Gerbert died, in the time of Cnut, the Dane and the Norwegian pushed their commerce far beyond the northern seas, both by caravans through Russia to the Orient, and by their venturesome barks which sailed through the Strait of Gibraltar into the Mediterranean.^[426] Only a little later, probably before 1200 A.D., a clerk in the service of Thomas à Becket, present at the latter's death, wrote a life of the martyr, to which (fortunately for our purposes) he prefixed a brief eulogy of the city of London.^[427] This clerk, William Fitz Stephen by name, thus speaks of the British capital:

Aurum mittit Arabs: species et thura Sabæus:
Arma Sythes: oleum palmarum divite sylva
Pingue solum Babylon: Nilus lapides pretiosos:
Norwegi, Russi, varium grisum, sabdinas:
Seres, purpureas vestes: Galli, sua vina.

Although, as a matter of fact, the Arabs had no gold to send, and the Scythians no arms, and Egypt no precious stones save only the turquoise, the Chinese (*Seres*) may have sent their purple vestments, and the north her sables and other furs, and France her wines. At any rate the verses show very clearly an extensive foreign trade.

Then there were the Crusades, which in these times brought the East in touch with the West. The spirit of the Orient showed itself in the songs of

the troubadours, and the *baudekin*,^[428] the canopy of Bagdad,^[429] became common in the churches of Italy. In Sicily and in Venice the textile industries of the East found place, and made their way even to the Scandinavian peninsula.^[430]

We therefore have this state of affairs: There was abundant intercourse between the East and West for some centuries before the Hindu numerals appear in any manuscripts in Christian Europe. The numerals must of necessity have been known to many traders in a country like Italy at least as early as the ninth century, and probably even earlier, but there was no reason for preserving them in treatises. Therefore when a man like Gerbert made them known to the scholarly circles, he was merely describing what had been familiar in a small way to many people in a different walk of life.

Since Gerbert^[431] was for a long time thought to have been the one to introduce the numerals into Italy,^[432] a brief sketch of this unique character is proper. Born of humble parents,^[433] this remarkable man became the counselor and companion of kings, and finally wore the papal tiara as Sylvester II, from 999 until his death in 1003.^[434] He was early brought under the influence of the monks at Aurillac, and particularly of Raimund, who had been a pupil of Odo of Cluny, and there in due time he himself took holy orders. He visited Spain in about 967 in company with Count Borel,^[435] remaining there three years, and studying under Bishop Hatto of Vich,^[436] a city in the province of Barcelona,^[437] then entirely under Christian rule. Indeed, all of Gerbert's testimony is as to the influence of the Christian civilization upon his education. Thus he speaks often of his study of Boethius,^[438] so that if the latter knew the numerals Gerbert would have learned them from him.^[439] If Gerbert had studied in any Moorish schools he would, under the decree of the emir Hishām (787-822), have been obliged to know Arabic, which would have taken most of his three years in Spain, and of which study we have not the slightest hint in any of his letters.^[440] On the other hand, Barcelona was the only Christian province in immediate touch with the Moorish civilization at that time.^[441] Furthermore we know that earlier in the same century King Alonzo of Asturias (d. 910) confided the education of his son Ordoño to the Arab scholars of the court

of the wālī of Saragossa,^[442] so that there was more or less of friendly relation between Christian and Moor.

After his three years in Spain, Gerbert went to Italy, about 970, where he met Pope John XIII, being by him presented to the emperor Otto I. Two years later (972), at the emperor's request, he went to Rheims, where he studied philosophy, assisting to make of that place an educational center; and in 983 he became abbot at Bobbio. The next year he returned to Rheims, and became archbishop of that diocese in 991. For political reasons he returned to Italy in 996, became archbishop of Ravenna in 998, and the following year was elected to the papal chair. Far ahead of his age in wisdom, he suffered as many such scholars have even in times not so remote by being accused of heresy and witchcraft. As late as 1522, in a biography published at Venice, it is related that by black art he attained the papacy, after having given his soul to the devil.^[443] Gerbert was, however, interested in astrology,^[444] although this was merely the astronomy of that time and was such a science as any learned man would wish to know, even as to-day we wish to be reasonably familiar with physics and chemistry.

That Gerbert and his pupils knew the ġobār numerals is a fact no longer open to controversy.^[445] Bernelinus and Richer^[446] call them by the well-known name of "caracteres," a word used by Radulph of Laon in the same sense a century later.^[447] It is probable that Gerbert was the first to describe these ġobār numerals in any scientific way in Christian Europe, but without the zero. If he knew the latter he certainly did not understand its use.^[448]

The question still to be settled is as to where he found these numerals. That he did not bring them from Spain is the opinion of a number of careful investigators.^[449] This is thought to be the more probable because most of the men who made Spain famous for learning lived after Gerbert was there. Such were Ibn Sīnā (Avicenna) who lived at the beginning, and Gerber of Seville who flourished in the middle, of the eleventh century, and Abū Roshd (Averroës) who lived at the end of the twelfth.^[450] Others hold that his proximity to the Arabs for three years makes it probable that he assimilated some of their learning, in spite of the fact that the lines between Christian and Moor at that time were sharply drawn.^[451] Writers fail, however, to recognize that a commercial numeral system would have been

more likely to be made known by merchants than by scholars. The itinerant peddler knew no forbidden pale in Spain, any more than he has known one in other lands. If the *ḡobār* numerals were used for marking wares or keeping simple accounts, it was he who would have known them, and who would have been the one rather than any Arab scholar to bring them to the inquiring mind of the young French monk. The facts that Gerbert knew them only imperfectly, that he used them solely for calculations, and that the forms are evidently like the Spanish *ḡobār*, make it all the more probable that it was through the small tradesman of the Moors that this versatile scholar derived his knowledge. Moreover the part of the geometry bearing his name, and that seems unquestionably his, shows the Arab influence, proving that he at least came into contact with the transplanted Oriental learning, even though imperfectly.^[452] There was also the persistent Jewish merchant trading with both peoples then as now, always alive to the acquiring of useful knowledge, and it would be very natural for a man like Gerbert to welcome learning from such a source.

On the other hand, the two leading sources of information as to the life of Gerbert reveal practically nothing to show that he came within the Moorish sphere of influence during his sojourn in Spain. These sources are his letters and the history written by Richer. Gerbert was a master of the epistolary art, and his exalted position led to the preservation of his letters to a degree that would not have been vouchsafed even by their classic excellence.^[453] Richer was a monk at St. Remi de Rheims, and was doubtless a pupil of Gerbert. The latter, when archbishop of Rheims, asked Richer to write a history of his times, and this was done. The work lay in manuscript, entirely forgotten until Pertz discovered it at Bamberg in 1833.^[454] The work is dedicated to Gerbert as archbishop of Rheims,^[455] and would assuredly have testified to such efforts as he may have made to secure the learning of the Moors.

Now it is a fact that neither the letters nor this history makes any statement as to Gerbert's contact with the Saracens. The letters do not speak of the Moors, of the Arab numerals, nor of Cordova. Spain is not referred to by that name, and only one Spanish scholar is mentioned. In one of his letters he speaks of Joseph Ispanus,^[456] or Joseph Sapiens, but who this Joseph the Wise of Spain may have been we do not know. Possibly it was he who

contributed the morsel of knowledge so imperfectly assimilated by the young French monk.^[457] Within a few years after Gerbert's visit two young Spanish monks of lesser fame, and doubtless with not that keen interest in mathematical matters which Gerbert had, regarded the apparently slight knowledge which they had of the Hindu numeral forms as worthy of somewhat permanent record^[458] in manuscripts which they were transcribing. The fact that such knowledge had penetrated to their modest cloisters in northern Spain—the one Albelda or Albaida—indicates that it was rather widely diffused.

Gerbert's treatise *Libellus de numerorum divisione*^[459] is characterized by Chasles as "one of the most obscure documents in the history of science."^[460] The most complete information in regard to this and the other mathematical works of Gerbert is given by Bubnov,^[461] who considers this work to be genuine.^[462]

So little did Gerbert appreciate these numerals that in his works known as the *Regula de abaco computi* and the *Libellus* he makes no use of them at all, employing only the Roman forms.^[463] Nevertheless Bernelinus^[464] refers to the nine *gōbār* characters.^[465] These Gerbert had marked on a thousand *jetons* or counters,^[466] using the latter on an abacus which he had a sign-maker prepare for him.^[467] Instead of putting eight counters in say the tens' column, Gerbert would put a single counter marked 8, and so for the other places, leaving the column empty where we would place a zero, but where he, lacking the zero, had no counter to place. These counters he possibly called *caracteres*, a name which adhered also to the figures themselves. It is an interesting speculation to consider whether these *apices*, as they are called in the Boethius interpolations, were in any way suggested by those Roman *jetons* generally known in numismatics as *tesserae*, and bearing the figures I-XVI, the sixteen referring to the number of *assi* in a *sestertius*.^[468] The name *apices* adhered to the Hindu-Arabic numerals until the sixteenth century.^[469]

To the figures on the *apices* were given the names Igin, andras, ormis, arbas, quimas, calctis or caltis, zenis, temenias, celentis, sipos,^[470] the origin and meaning of which still remain a mystery. The Semitic origin of several of the words seems probable. *Wahud*, *thaneine*, *thalata*, *arba*,

kumsa, setta, sebba, timinia, taseud are given by the Rev. R. Patrick^[471] as the names, in an Arabic dialect used in Morocco, for the numerals from one to nine. Of these the words for four, five, and eight are strikingly like those given above.

The name *apices* was not, however, a common one in later times. *Notae* was more often used, and it finally gave the name to notation.^[472] Still more common were the names *figures, ciphers, signs, elements, and characters*.^[473]

So little effect did the teachings of Gerbert have in making known the new numerals, that O'Creat, who lived a century later, a friend and pupil of Adelhard of Bath, used the zero with the Roman characters, in contrast to Gerbert's use of the *ḡobār* forms without the zero.^[474] O'Creat uses three forms for zero, o, *ō*, and *τ*, as in Maximus Planudes. With this use of the zero goes, naturally, a place value, for he writes III III for 33, ICCOO and I. II. *τ*. *τ* for 1200, I. O. VIII. IX for 1089, and I. III. III. *τττ* for the square of 1200.

The period from the time of Gerbert until after the appearance of Leonardo's monumental work may be called the period of the abacists. Even for many years after the appearance early in the twelfth century of the books explaining the Hindu art of reckoning, there was strife between the abacists, the advocates of the abacus, and the algorists, those who favored the new numerals. The words *cifra* and *algorismus cifra* were used with a somewhat derisive significance, indicative of absolute uselessness, as indeed the zero is useless on an abacus in which the value of any unit is given by the column which it occupies.^[475] So Gautier de Coincy (1177-1236) in a work on the miracles of Mary says:

A horned beast, a sheep,
An algorismus-cipher,
Is a priest, who on such a feast day
Does not celebrate the holy Mother.^[476]

So the abacus held the field for a long time, even against the new algorism employing the new numerals. Geoffrey Chaucer^[477] describes in *The Miller's Tale* the clerk with

"His Almageste and bokes grete and smale,
His astrelabie, longinge for his art,
His augrim-stones layen faire apart
On shelves couched at his beddes heed."

So, too, in Chaucer's explanation of the astrolabe,^[478] written for his son Lewis, the number of degrees is expressed on the instrument in Hindu-Arabic numerals: "Over the whiche degrees ther ben noubres of augrim, that devyden thilke same degrees fro fyve to fyve," and "... the nombres ... ben writen in augrim," meaning in the way of the algorism. Thomas Usk about 1387 writes:^[479] "a sypher in augrim have no might in signification of it-selve, yet he yeveth power in signification to other." So slow and so painful is the assimilation of new ideas.

Bernelinus^[480] states that the abacus is a well-polished board (or table), which is covered with blue sand and used by geometers in drawing geometrical figures. We have previously mentioned the fact that the Hindus also performed mathematical computations in the sand, although there is no evidence to show that they had any column abacus.^[481] For the purposes of computation, Bernelinus continues, the board is divided into thirty vertical columns, three of which are reserved for fractions. Beginning with the units columns, each set of three columns (*lineae* is the word which Bernelinus uses) is grouped together by a semicircular arc placed above them, while a smaller arc is placed over the units column and another joins the tens and hundreds columns. Thus arose the designation *arcus pictagore*^[482] or sometimes simply *arcus*.^[483] The operations of addition, subtraction, and multiplication upon this form of the abacus required little explanation, although they were rather extensively treated, especially the multiplication of different orders of numbers. But the operation of division was effected with some difficulty. For the explanation of the method of division by the use of the complementary difference,^[484] long the stumbling-block in the way of the medieval arithmetician, the reader is referred to works on the history of mathematics^[485] and to works relating particularly to the abacus.^[486]

Among the writers on the subject may be mentioned Abbo^[487] of Fleury (c. 970), Heriger^[488] of Lobbes or Laubach (c. 950-1007), and Hermannus

Contractus^[489] (1013-1054), all of whom employed only the Roman numerals. Similarly Adelhard of Bath (c. 1130), in his work *Regulae Abaci*,^[490] gives no reference to the new numerals, although it is certain that he knew them. Other writers on the abacus who used some form of Hindu numerals were Gerland^[491] (first half of twelfth century) and Turchill^[492] (c. 1200). For the forms used at this period the reader is referred to the plate on page 88.

After Gerbert's death, little by little the scholars of Europe came to know the new figures, chiefly through the introduction of Arab learning. The Dark Ages had passed, although arithmetic did not find another advocate as prominent as Gerbert for two centuries. Speaking of this great revival, Raoul Glaber^[493] (985-c. 1046), a monk of the great Benedictine abbey of Cluny, of the eleventh century, says: "It was as though the world had arisen and tossed aside the worn-out garments of ancient time, and wished to apparel itself in a white robe of churches." And with this activity in religion came a corresponding interest in other lines. Algorisms began to appear, and knowledge from the outside world found interested listeners. Another Raoul, or Radulph, to whom we have referred as Radulph of Laon,^[494] a teacher in the cloister school of his city, and the brother of Anselm of Laon^[495] the celebrated theologian, wrote a treatise on music, extant but unpublished, and an arithmetic which Nagl first published in 1890.^[496] The latter work, preserved to us in a parchment manuscript of seventy-seven leaves, contains a curious mixture of Roman and ġobār numerals, the former for expressing large results, the latter for practical calculation. These ġobār "characteres" include the sipos (zero), , of which, however, Radulph did not know the full significance; showing that at the opening of the twelfth century the system was still uncertain in its status in the church schools of central France.

At the same time the words *algorismus* and *cifra* were coming into general use even in non-mathematical literature. Jordan^[497] cites numerous instances of such use from the works of Alanus ab Insulis^[498] (Alain de Lille), Gautier de Coincy (1177-1236), and others.

Another contributor to arithmetic during this interesting period was a prominent Spanish Jew called variously John of Luna, John of Seville,

Johannes Hispalensis, Johannes Toletanus, and Johannes Hispanensis de Luna.^[499] His date is rather closely fixed by the fact that he dedicated a work to Raimund who was archbishop of Toledo between 1130 and 1150.^[500] His interests were chiefly in the translation of Arabic works, especially such as bore upon the Aristotelian philosophy. From the standpoint of arithmetic, however, the chief interest centers about a manuscript entitled *Joannis Hispalensis liber Algorismi de Practica Arismetrice* which Boncompagni found in what is now the *Bibliothèque nationale* at Paris. Although this distinctly lays claim to being Al-Khowārazmī's work,^[501] the evidence is altogether against the statement,^[502] but the book is quite as valuable, since it represents the knowledge of the time in which it was written. It relates to the operations with integers and sexagesimal fractions, including roots, and contains no applications.^[503]

Contemporary with John of Luna, and also living in Toledo, was Gherard of Cremona,^[504] who has sometimes been identified, but erroneously, with Gernardus,^[505] the author of a work on algorism. He was a physician, an astronomer, and a mathematician, translating from the Arabic both in Italy and in Spain. In arithmetic he was influential in spreading the ideas of algorism.

Four Englishmen—Adelhard of Bath (c. 1130), Robert of Chester (Robertus Cestrensis, c. 1143), William Shelley, and Daniel Morley (1180)—are known^[506] to have journeyed to Spain in the twelfth century for the purpose of studying mathematics and Arabic. Adelhard of Bath made translations from Arabic into Latin of Al-Khowārazmī's astronomical tables^[507] and of Euclid's Elements,^[508] while Robert of Chester is known as the translator of Al-Khowārazmī's algebra.^[509] There is no reason to doubt that all of these men, and others, were familiar with the numerals which the Arabs were using.

The earliest trace we have of computation with Hindu numerals in Germany is in an *Algorismus* of 1143, now in the Hofbibliothek in Vienna.^[510] It is bound in with a *Computus* by the same author and bearing the date given. It contains chapters "De additione," "De diminutione," "De mediatione," "De divisione," and part of a chapter on multiplication. The numerals are in the usual medieval forms except the 2 which, as will be seen from the

illustration,^[511] is somewhat different, and the 3, which takes the peculiar shape **⦿**, a form characteristic of the twelfth century.

It was about the same time that the *Sefer ha-Mispar*,^[512] the Book of Number, appeared in the Hebrew language. The author, Rabbi Abraham ibn Meïr ibn Ezra,^[513] was born in Toledo (c. 1092). In 1139 he went to Egypt, Palestine, and the Orient, spending also some years in Italy. Later he lived in southern France and in England. He died in 1167. The probability is that he acquired his knowledge of the Hindu arithmetic^[514] in his native town of Toledo, but it is also likely that the knowledge of other systems which he acquired on travels increased his appreciation of this one. We have mentioned the fact that he used the first letters of the Hebrew alphabet, א ב ג ד ה ו ז ח ט, for the numerals 9 8 7 6 5 4 3 2 1, and a circle for the zero. The quotation in the note given below shows that he knew of the Hindu origin; but in his manuscript, although he set down the Hindu forms, he used the above nine Hebrew letters with place value for all computations.

CHAPTER VIII

THE SPREAD OF THE NUMERALS IN EUROPE

Of all the medieval writers, probably the one most influential in introducing the new numerals to the scholars of Europe was Leonardo Fibonacci, of Pisa.^[515] This remarkable man, the most noteworthy mathematical genius of the Middle Ages, was born at Pisa about 1175.^[516]

The traveler of to-day may cross the Via Fibonacci on his way to the Campo Santo, and there he may see at the end of the long corridor, across the quadrangle, the statue of Leonardo in scholars garb. Few towns have honored a mathematician more, and few mathematicians have so distinctly honored their birthplace. Leonardo was born in the golden age of this city, the period of its commercial, religious, and intellectual prosperity.^[517] Situated practically at the mouth of the Arno, Pisa formed with Genoa and Venice the trio of the greatest commercial centers of Italy at the opening of the thirteenth century. Even before Venice had captured the Levantine trade, Pisa had close relations with the East. An old Latin chronicle relates that in

1005 "Pisa was captured by the Saracens," that in the following year "the Pisans overthrew the Saracens at Reggio," and that in 1012 "the Saracens came to Pisa and destroyed it." The city soon recovered, however, sending no fewer than a hundred and twenty ships to Syria in 1099,^[518] founding a merchant colony in Constantinople a few years later,^[519] and meanwhile carrying on an interurban warfare in Italy that seemed to stimulate it to great activity.^[520] A writer of 1114 tells us that at that time there were many heathen people—Turks, Libyans, Parthians, and Chaldeans—to be found in Pisa. It was in the midst of such wars, in a cosmopolitan and commercial town, in a center where literary work was not appreciated,^[521] that the genius of Leonardo appears as one of the surprises of history, warning us again that "we should draw no horoscope; that we should expect little, for what we expect will not come to pass."^[522]

Leonardo's father was one William,^[523] and he had a brother named Bonaccingus,^[524] but nothing further is known of his family. As to Fibonacci, most writers^[525] have assumed that his father's name was Bonaccio,^[526] whence *filius Bonaccii*, or Fibonacci. Others^[527] believe that the name, even in the Latin form of *filius Bonaccii* as used in Leonardo's work, was simply a general one, like our Johnson or Bronson (Brown's son); and the only contemporary evidence that we have bears out this view. As to the name Bigollo, used by Leonardo, some have thought it a self-assumed one meaning blockhead, a term that had been applied to him by the commercial world or possibly by the university circle, and taken by him that he might prove what a blockhead could do. Milanese,^[528] however, has shown that the word Bigollo (or Pigollo) was used in Tuscany to mean a traveler, and was naturally assumed by one who had studied, as Leonardo had, in foreign lands.

Leonardo's father was a commercial agent at Bugia, the modern Bougie,^[529] the ancient Saldae on the coast of Barbary,^[530] a royal capital under the Vandals and again, a century before Leonardo, under the Beni Hammad. It had one of the best harbors on the coast, sheltered as it is by Mt. Lalla Guraia,^[531] and at the close of the twelfth century it was a center of African commerce. It was here that Leonardo was taken as a child, and here he went to school to a Moorish master. When he reached the years of young

manhood he started on a tour of the Mediterranean Sea, and visited Egypt, Syria, Greece, Sicily, and Provence, meeting with scholars as well as with merchants, and imbibing a knowledge of the various systems of numbers in use in the centers of trade. All these systems, however, he says he counted almost as errors compared with that of the Hindus.^[532] Returning to Pisa, he wrote his *Liber Abaci*^[533] in 1202, rewriting it in 1228.^[534] In this work the numerals are explained and are used in the usual computations of business. Such a treatise was not destined to be popular, however, because it was too advanced for the mercantile class, and too novel for the conservative university circles. Indeed, at this time mathematics had only slight place in the newly established universities, as witness the oldest known statute of the Sorbonne at Paris, dated 1215, where the subject is referred to only in an incidental way.^[535] The period was one of great commercial activity, and on this very account such a book would attract even less attention than usual.^[536]

It would now be thought that the western world would at once adopt the new numerals which Leonardo had made known, and which were so much superior to anything that had been in use in Christian Europe. The antagonism of the universities would avail but little, it would seem, against such an improvement. It must be remembered, however, that there was great difficulty in spreading knowledge at this time, some two hundred and fifty years before printing was invented. "Popes and princes and even great religious institutions possessed far fewer books than many farmers of the present age. The library belonging to the Cathedral Church of San Martino at Lucca in the ninth century contained only nineteen volumes of abridgments from ecclesiastical commentaries."^[537] Indeed, it was not until the early part of the fifteenth century that Palla degli Strozzi took steps to carry out the project that had been in the mind of Petrarch, the founding of a public library. It was largely by word of mouth, therefore, that this early knowledge had to be transmitted. Fortunately the presence of foreign students in Italy at this time made this transmission feasible. (If human nature was the same then as now, it is not impossible that the very opposition of the faculties to the works of Leonardo led the students to investigate them the more zealously.) At Vicenza in 1209, for example, there were Bohemians, Poles, Frenchmen, Burgundians, Germans, and Spaniards, not to speak of representatives of divers towns of Italy; and what

was true there was also true of other intellectual centers. The knowledge could not fail to spread, therefore, and as a matter of fact we find numerous bits of evidence that this was the case. Although the bankers of Florence were forbidden to use these numerals in 1299, and the statutes of the university of Padua required stationers to keep the price lists of books "non per cifras, sed per literas claros,"^[538] the numerals really made much headway from about 1275 on.

It was, however, rather exceptional for the common people of Germany to use the Arabic numerals before the sixteenth century, a good witness to this fact being the popular almanacs. Calendars of 1457-1496^[539] have generally the Roman numerals, while Köbel's calendar of 1518 gives the Arabic forms as subordinate to the Roman. In the register of the Kreuzschule at Dresden the Roman forms were used even until 1539.

While not minimizing the importance of the scientific work of Leonardo of Pisa, we may note that the more popular treatises by Alexander de Villa Dei (c. 1240 A.D.) and John of Halifax (Sacrobosco, c. 1250 A.D.) were much more widely used, and doubtless contributed more to the spread of the numerals among the common people.

The *Carmen de Algorismo*^[540] of Alexander de Villa Dei was written in verse, as indeed were many other textbooks of that time. That it was widely used is evidenced by the large number of manuscripts^[541] extant in European libraries. Sacrobosco's *Algorismus*,^[542] in which some lines from the Carmen are quoted, enjoyed a wide popularity as a textbook for university instruction.^[543] The work was evidently written with this end in view, as numerous commentaries by university lecturers are found. Probably the most widely used of these was that of Petrus de Dacia^[544] written in 1291. These works throw an interesting light upon the method of instruction in mathematics in use in the universities from the thirteenth even to the sixteenth century. Evidently the text was first read and copied by students.^[545] Following this came line by line an exposition of the text, such as is given in Petrus de Dacia's commentary.

Sacrobosco's work is of interest also because it was probably due to the extended use of this work that the term *Arabic numerals* became common. In two places there is mention of the inventors of this system. In the

introduction it is stated that this science of reckoning was due to a philosopher named Albus, whence the name *algorismus*,^[546] and in the section on numeration reference is made to the Arabs as the inventors of this science.^[547] While some of the commentators, Petrus de Dacia^[548] among them, knew of the Hindu origin, most of them undoubtedly took the text as it stood; and so the Arabs were credited with the invention of the system.

The first definite trace that we have of an algorism in the French language is found in a manuscript written about 1275.^[549] This interesting leaf, for the part on algorism consists of a single folio, was noticed by the Abbé Lebœuf as early as 1741,^[550] and by Daunou in 1824.^[551] It then seems to have been lost in the multitude of Paris manuscripts; for although Chasles^[552] relates his vain search for it, it was not rediscovered until 1882. In that year M. Ch. Henry found it, and to his care we owe our knowledge of the interesting manuscript. The work is anonymous and is devoted almost entirely to geometry, only two pages (one folio) relating to arithmetic. In these the forms of the numerals are given, and a very brief statement as to the operations, it being evident that the writer himself had only the slightest understanding of the subject.

Once the new system was known in France, even thus superficially, it would be passed across the Channel to England. Higden,^[553] writing soon after the opening of the fourteenth century, speaks of the French influence at that time and for some generations preceding:^[554] "For two hundred years children in scole, agenst the usage and manir of all other nations beeth compelled for to leave hire own language, and for to construe hir lessons and hire thynges in Frensche.... Gentilmen children beeth taught to speke Frensche from the tyme that they bith rokked in hir cradell; and uplondissche men will likne himself to gentylmen, and fondeth with greet besynesse for to speke Frensche."

The question is often asked, why did not these new numerals attract more immediate attention? Why did they have to wait until the sixteenth century to be generally used in business and in the schools? In reply it may be said that in their elementary work the schools always wait upon the demands of trade. That work which pretends to touch the life of the people must come

reasonably near doing so. Now the computations of business until about 1500 did not demand the new figures, for two reasons: First, cheap paper was not known. Paper-making of any kind was not introduced into Europe until the twelfth century, and cheap paper is a product of the nineteenth. Pencils, too, of the modern type, date only from the sixteenth century. In the second place, modern methods of operating, particularly of multiplying and dividing (operations of relatively greater importance when all measures were in compound numbers requiring reductions at every step), were not yet invented. The old plan required the erasing of figures after they had served their purpose, an operation very simple with counters, since they could be removed. The new plan did not as easily permit this. Hence we find the new numerals very tardily admitted to the counting-house, and not welcomed with any enthusiasm by teachers.^[555]

Aside from their use in the early treatises on the new art of reckoning, the numerals appeared from time to time in the dating of manuscripts and upon monuments. The oldest definitely dated European document known to contain the numerals is a Latin manuscript,^[556] the Codex Vigilanus, written in the Albelda Cloister not far from Logroño in Spain, in 976 A.D. The nine characters (of *ḡobār* type), without the zero, are given as an addition to the first chapters of the third book of the *Origines* by Isidorus of Seville, in which the Roman numerals are under discussion. Another Spanish copy of the same work, of 992 A.D., contains the numerals in the corresponding section. The writer ascribes an Indian origin to them in the following words: "Item de figuris arithmetice. Scire debemus in Indos subtilissimum ingenium habere et ceteras gentes eis in arithmetica et geometria et ceteris liberalibus disciplinis concedere. Et hoc manifestum est in nobem figuris, quibus designant unumquemque gradum cuiuslibet gradus. Quarum hec sunt forma." The nine *ḡobār* characters follow. Some of the abacus forms^[557] previously given are doubtless also of the tenth century. The earliest Arabic documents containing the numerals are two manuscripts of 874 and 888 A.D.^[558] They appear about a century later in a work^[559] written at Shiraz in 970 A.D. There is also an early trace of their use on a pillar recently discovered in a church apparently destroyed as early as the tenth century, not far from the Jeremias Monastery, in Egypt. A graffito in Arabic on this pillar has the date 349 A.H., which corresponds to

961 A.D.^[560] For the dating of Latin documents the Arabic forms were used as early as the thirteenth century.^[561]

On the early use of these numerals in Europe the only scientific study worthy the name is that made by Mr. G. F. Hill of the British Museum.^[562] From his investigations it appears that the earliest occurrence of a date in these numerals on a coin is found in the reign of Roger of Sicily in 1138.^[563] Until recently it was thought that the earliest such date was 1217 A.D. for an Arabic piece and 1388 for a Turkish one.^[564] Most of the seals and medals containing dates that were at one time thought to be very early have been shown by Mr. Hill to be of relatively late workmanship. There are, however, in European manuscripts, numerous instances of the use of these numerals before the twelfth century. Besides the example in the Codex Vigilanus, another of the tenth century has been found in the St. Gall MS. now in the University Library at Zürich, the forms differing materially from those in the Spanish codex.

The third specimen in point of time in Mr. Hill's list is from a Vatican MS. of 1077. The fourth and fifth specimens are from the Erlangen MS. of Boethius, of the same (eleventh) century, and the sixth and seventh are also from an eleventh-century MS. of Boethius at Chartres. These and other early forms are given by Mr. Hill in this table, which is reproduced with his kind permission.

EARLIEST MANUSCRIPT FORMS

1	I	2	3	4	5	6	7	8	9	0	976
2	T	U	V	P	Q	R	S	3	S	SS	X
3	7	8	9	10	11	12	13	14	15		977
4	1	2	3	4	5	6	7	8	9		XI
5	1	2	3	4	5	6	7	8	9	0	XI
6	1	2	3	4	5	6	7	8	9	0	XI
7	1	2	3	4	5	6	7	8	9		XI
8	1	2	3	4	5	6	7	8	9		XI-XII
9	1	2	3	4	5	6	7	8	9		XI-XII
10	1	2	3	4	5	6	7	8	9		XI-XII
11	1	2	3	4	5	6	7	8	9		XI-XII
12	1	2	3	4	5	6	7	8	9		XI-XII
13	1	2	3	4	5	6	7	8	9		XI-XII
14	1	2	3	4	5	6	7	8	9		c. 1200
15	1	2	3	4	5	6	7	8	9		c. 1200
16	1	2	3	4	5	6	7	8	9		?
17	1	2	3	4	5	6	7	8	9		?
18	1	2	3	4	5	6	7	8	9		?
19	1	2	3	4	5	6	7	8	9		XV
20	1	2	3	4	5	6	7	8	9		XV
21	1	2	3	4	5	6	7	8	9	0	XVI-XVII

This is one of more than fifty tables given in Mr. Hill's valuable paper, and to this monograph students are referred for details as to the development of number-forms in Europe from the tenth to the sixteenth century. It is of interest to add that he has found that among the earliest dates of European coins or medals in these numerals, after the Sicilian one already mentioned, are the following: Austria, 1484; Germany, 1489 (Cologne); Switzerland, 1424 (St. Gall); Netherlands, 1474; France, 1485; Italy, 1390. ^[565]

The earliest English coin dated in these numerals was struck in 1551, ^[566] although there is a Scotch piece of 1539. ^[567] In numbering pages of a printed book these numerals were first used in a work of Petrarch's published at Cologne in 1471. ^[568] The date is given in the following form in the *Biblia Pauperum*, ^[569] a block-book of 1470,

3210

while in another block-book which possibly goes back to c. 1430^[570] the numerals appear in several illustrations, with forms as follows:

1 2 3 4 5 6 7 8 9 0
Y

Many printed works anterior to 1471 have pages or chapters numbered by hand, but many of these numerals are of date much later than the printing of the work. Other works were probably numbered directly after printing. Thus the chapters 2, 3, 4, 5, 6 in a book of 1470^[571] are numbered as follows: Capitulum zm.,... 3m.,... 4m.,... v.,... vi, and followed by Roman numerals. This appears in the body of the text, in spaces left by the printer to be filled in by hand. Another book^[572] of 1470 has pages numbered by hand with a mixture of Roman and Hindu numerals, thus,

Cz7 for 125 Cy0 for 150
C8A for 147 c2 for 202

As to monumental inscriptions,^[573] there was once thought to be a gravestone at Katharein, near Troppau, with the date 1007, and one at Biebrich of 1299. There is no doubt, however, of one at Pforzheim of 1371 and one at Ulm of 1388.^[574] Certain numerals on Wells Cathedral have been assigned to the thirteenth century, but they are undoubtedly considerably later.^[575]

The table on page 143 will serve to supplement that from Mr. Hill's work.^[576]

EARLY MANUSCRIPT FORMS

	1	2	3	4	5	6	7	8	9	0	
a ^[577]	1	2	3	4	5	6	7	8	9	0	Twelfth century A.D.
b ^[578]	1	2	3	4	5	6	7	8	9	0	1197 A.D.

c ^[579] 1̣ 2̣ 3̣ 4̣ 5̣ 6̣ 7̣ 8̣ 9̣ 0̣ 1275 A.D.

d ^[580] 1 2 3 4 5 6 7 8 9 0 c. 1294 A.D.

e ^[581] 1 2 3 4 5 6 7 8 9 0 c. 1303 A.D.

f ^[582] 1 2 3 4 5 6 7 8 9 0 c. 1360 A.D.

g ^[583] 1 2 3 4 5 6 7 8 9 0 c. 1442 A.D.

v	—1028416.
t	—428288
o	—252128.
si	—131041.
q	—64436.
p	—32218.
o	—16384.
n	—8192.
m	—4096.
l	—2048.
k	—1024.
i	—512.
j	—256.
h	—128.
g	—64.
f	—32.
e	—16.
d	—8.
b	—4.
a	—2.

For the sake of further comparison, three illustrations from works in Mr. Plimpton's library, reproduced from the *Rara Arithmetica*, may be considered. The first is from a Latin manuscript on arithmetic,^[584] of which the original was written at Paris in 1424 by Rollandus, a Portuguese physician, who prepared the work at the command of John of Lancaster, Duke of Bedford, at one time Protector of England and Regent of France, to whom the work is dedicated. The figures show the successive powers of 2. The second illustration is from Luca da Firenze's *Inprencipio darte dabacho*,^[585] c. 1475, and the third is from an anonymous manuscript^[586] of about 1500.

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. —

As to the forms of the numerals, fashion played a leading part until printing was invented. This tended to fix these forms, although in writing there is still a great variation, as witness the French 5 and the German 7 and 9. Even in printing there is not complete uniformity, and it is often difficult for a foreigner to distinguish between the 3 and 5 of the French types.

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|----|----|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |

As to the particular numerals, the following are some of the forms to be found in the later manuscripts and in the early printed books.

1. In the early printed books "one" was often i, perhaps to save types, just as some modern typewriters use the same character for l and 1.^[587] In the manuscripts the "one" appears in such forms as^[588]

1, 2, 3, 4, 5, 6, 7.

2. "Two" often appears as z in the early printed books, 12 appearing as iz.

[589] In the medieval manuscripts the following forms are common: [590]

2, 1, 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839

It is evident, from the early traces, that it is merely a cursive form for the primitive Ξ , just as 3 comes from Ξ , as in the Nānā Ghāt inscriptions.




3. "Three" usually had a special type in the first printed books, although occasionally it appears as **3**.^[591] In the medieval manuscripts it varied rather less than most of the others. The following are common forms.^[592]

3, 3, 7, 8, 2, 3, 5, 2, 3, 6

4. "Four" has changed greatly; and one of the first tests as to the age of a manuscript on arithmetic, and the place where it was written, is the examination of this numeral. Until the time of printing the most common form was , although the Florentine manuscript of Leonard of Pisa's work has the form ,^[593] but the manuscripts show that the Florentine arithmeticians and astronomers rather early began to straighten the first of these forms up to forms like ^[594] and ^[594] or ^[595] more closely resembling our own. The first printed books generally used our present form^[596] with the closed top , the open top used in writing () being purely modern. The following are other forms of the four, from various manuscripts:^[597]

A, a, y, e, r, u, u, d, u, a, u, n
 e, e, y, t, d, y. A
 y, u, u, u, u, u, u


5. "Five" also varied greatly before the time of printing. The following are some of the forms:^[598]


6. "Six" has changed rather less than most of the others. The chief variation has been in the slope of the top, as will be seen in the following:^[599]



7. "Seven," like "four," has assumed its present erect form only since the fifteenth century. In medieval times it appeared as follows:^[600]




8. "Eight," like "six," has changed but little. In medieval times there are a few variants of interest as follows:^[601]




In the sixteenth century, however, there was manifested a tendency to write it .^[602]

9. "Nine" has not varied as much as most of the others. Among the medieval forms are the following:^[603]



0. The shape of the zero also had a varied history. The following are common medieval forms:^[604]



The explanation of the place value was a serious matter to most of the early writers. If they had been using an abacus constructed like the Russian chotü, and had placed this before all learners of the positional system, there would have been little trouble. But the medieval line-reckoning, where the lines stood for powers of 10 and the spaces for half of such powers, did not lend itself to this comparison. Accordingly we find such labored explanations as the following, from *The Crafte of Nombrynge*:

"Euery of these figuris bitokens hym selfe & no more, yf he stonde in the first place of the rewele....

"If it stonde in the secunde place of the rewle, he betokens ten tymes hym selfe, as this figure 2 here 20 tokens ten tyme hym selfe, that is twenty, for he hym selfe betokens tweyne, & ten tymes twene is twenty. And for he stondis on the lyft side & in the secunde place, he betokens ten tyme hym selfe. And so go forth....


"Nil cifra significat sed dat signare sequenti. Expone this verse. A cifre tokens nozt, bot he makes the figure to betoken that comes after hym more than he shuld & he were away, as thus 10. here the figure of one tokens ten, & yf the cifre were away & no figure byfore hym he schuld token bot one, for than he schuld stonde in the first place...."^[605]

It would seem that a system that was thus used for dating documents, coins, and monuments, would have been generally adopted much earlier than it was, particularly in those countries north of Italy where it did not come into general use until the sixteenth century. This, however, has been the fate of many inventions, as witness our neglect of logarithms and of contracted processes to-day.

As to Germany, the fifteenth century saw the rise of the new symbolism; the sixteenth century saw it slowly gain the mastery; the seventeenth century saw it finally conquer the system that for two thousand years had dominated the arithmetic of business. Not a little of the success of the new plan was due to Luther's demand that all learning should go into the vernacular.^[606]

During the transition period from the Roman to the Arabic numerals, various anomalous forms found place. For example, we have in the fourteenth century cα for 104;^[607] 1000. 300. 80 et 4 for 1384;^[608] and in a manuscript of the fifteenth century 12901 for 1291.^[609] In the same century m. cccc. 8II appears for 1482,^[610] while M^oCCCC^o50 (1450) and MCCCCXL6 (1446) are used by Theodoricus Ruffi about the same time.^[611] To the next century belongs the form 1vojj for 1502. Even in Sfortunati's *Nuovo lume*^[612] the use of ordinals is quite confused, the propositions on a single page being numbered "tertia," "4," and "V."

Although not connected with the Arabic numerals in any direct way, the medieval astrological numerals may here be mentioned. These are given by several early writers, but notably by Noviomagus (1539),^[613] as follows^[614]:



Thus we find the numerals gradually replacing the Roman forms all over Europe, from the time of Leonardo of Pisa until the seventeenth century. But in the Far East to-day they are quite unknown in many countries, and they still have their way to make. In many parts of India, among the common people of Japan and China, in Siam and generally about the Malay Peninsula, in Tibet, and among the East India islands, the natives still adhere to their own numeral forms. Only as Western civilization is making its way into the commercial life of the East do the numerals as used by us find place, save as the Sanskrit forms appear in parts of India. It is therefore with surprise that the student of mathematics comes to realize how modern are these forms so common in the West, how limited is their use even at the present time, and how slow the world has been and is in adopting such a simple device as the Hindu-Arabic numerals.

INDEX

Transcriber's note: many of the entries refer to footnotes linked from the page numbers given.

Abbo of Fleury, [122](#)
‘Abdallāh ibn al-Ḥasan, [92](#)
‘Abdallatīf ibn Yūsuf, [93](#)
‘Abdalqādir ibn ‘Alī al-Sakhāwī, [6](#)
Abenragel, [34](#)
Abraham ibn Meīr ibn Ezra, *see* Rabbi ben Ezra
Abū ‘Alī al-Ḥosein ibn Sīnā, [74](#)
Abū 'l-Ḥasan, [93](#), [100](#)
Abū 'l-Qāsim, [92](#)
Abū 'l-Ṭeiyib, [97](#)
Abū Naṣr, [92](#)
Abū Roshd, [113](#)
Abu Sahl Dunash ibn Tamim, [65](#), [67](#)
Adelhard of Bath, [5](#), [55](#), [97](#), [119](#), [123](#), [126](#)
Adhemar of Chabanois, [111](#)
Aḥmed al-Nasawī, [98](#)
Aḥmed ibn ‘Abdallāh, [9](#), [92](#)
Aḥmed ibn Moḥammed, [94](#)
Aḥmed ibn ‘Omar, [93](#)
Akṣaras, [32](#)
Alanus ab Insulis, [124](#)
Al-Baġdādī, [93](#)
Al-Battānī, [54](#)
Albelda (Albaida) MS., [116](#)
Albert, J., [62](#)
Albert of York, [103](#)
Al-Bīrūnī, [6](#), [41](#), [49](#), [65](#), [92](#), [93](#)
Alcuin, [103](#)
Alexander the Great, [76](#)
Alexander de Villa Dei, [11](#), [133](#)
Alexandria, [64](#), [82](#)
Al-Fazārī, [92](#)
Alfred, [103](#)
Algebra, etymology, [5](#)

Algerian numerals, 68
Algorism, 97
Algorismus, 124, 126, 135
Algorismus cifra, 120
Al-Ḥaṣṣār, 65
‘Alī ibn Abī Bekr, 6
‘Alī ibn Aḥmed, 93, 98
Al-Karābīsī, 93
Al-Khowārazmī, 4, 9, 10, 92, 97, 98, 125, 126
Al-Kindī, 10, 92
Almagest, 54
Al-Mağrebī, 93
Al-Maḥallī, 6
Al-Māmūn, 10, 97
Al-Manṣūr, 96, 97
Al-Mas‘ūdī, 7, 92
Al-Nadīm, 9
Al-Nasawī, 93, 98
Alphabetic numerals, 39, 40, 43
Al-Qāsim, 92
Al-Qass, 94
Al-Sakhāwī, 6
Al-Ṣardafī, 93
Al-Sijzī, 94
Al-Sūfī, 10, 92
Ambrosoli, 118
Ankapalli, 43
Apices, 87, 117, 118
Arabs, 91-98
Arbuthnot, 141
Archimedes, 15, 16
Arcus Pictagore, 122
Arjuna, 15
Arnold, E., 15, 102
Ars memorandi, 141
Āryabhaṭa, 39, 43, 44
Aryan numerals, 19

Aschbach, [134](#)
Ashmole, [134](#)
Aśoka, [19](#), [20](#), [22](#), [81](#)
Aṣ-ṣifr, [57](#), [58](#)
Astrological numerals, [150](#)
Atharva-Veda, [48](#), [49](#), [55](#)
Augustus, [80](#)
Averroës, [113](#)
Avicenna, [58](#), [74](#), [113](#)

Babylonian numerals, [28](#)
Babylonian zero, [51](#)
Bacon, R., [131](#)
Bactrian numerals, [19](#), [30](#)
Bæda, [2](#), [72](#)
Bagdad, [4](#), [96](#)
Bakhṣālī manuscript, [43](#), [49](#), [52](#), [53](#)
Ball, C. J., [35](#)
Ball, W. W. R., [36](#), [131](#)
Bāṇa, [44](#)
Barth, A., [39](#)
Bayang inscriptions, [39](#)
Bayer, [33](#)
Bayley, E. C., [19](#), [23](#), [30](#), [32](#), [52](#), [89](#)
Beazley, [75](#)
Bede, *see* Bæda
Beldomandi, [137](#)
Beloch, J., [77](#)
Bendall, [25](#), [52](#)
Benfey, T., [26](#)
Bernelinus, [88](#), [112](#), [117](#), [121](#)
Besagne, [128](#)
Besant, W., [109](#)
Bettino, [36](#)
Bhandarkar, [18](#), [47](#), [49](#)
Bhāskara, [53](#), [55](#)
Biernatzki, [32](#)

Biot, [32](#)
Björnbo, A. A., [125](#), [126](#)
Blassière, [119](#)
Bloomfield, [48](#)
Blume, [85](#)
Boeckh, [62](#)
Boehmer, [143](#)
Boeschstein, [119](#)
Boethius, [63](#), [70-73](#), [83-90](#)
Boissière, [63](#)
Bombelli, [81](#)
Bonaini, [128](#)
Boncompagni, [5](#), [6](#), [10](#), [48](#), [49](#), [123](#), [125](#)
Borghi, [59](#)
Borgo, [119](#)
Bougie, [130](#)
Bowring, J., [56](#)
Brahmagupta, [52](#)
Brāhmaṇas, [12](#), [13](#)
Brāhmī, [19](#), [20](#), [31](#), [83](#)
Brandis, J., [54](#)
Bṛhat-Saṃhita, [39](#), [44](#), [78](#)
Brockhaus, [43](#)
Bubnov, [65](#), [84](#), [110](#), [116](#)
Buddha, education of, [15](#), [16](#)
Büdinger, [110](#)
Bugia, [130](#)
Bühler, G., [15](#), [19](#), [22](#), [31](#), [44](#), [49](#)
Burgess, [25](#)
Bürk, [13](#)
Burmese numerals, [36](#)
Burnell, A. C., [18](#), [40](#)
Buteo, [61](#)

Calandri, [59](#), [81](#)
Caldwell, R., [19](#)
Calendars, [133](#)

Calmet, [34](#)
Cantor, M., [5](#), [13](#), [30](#), [43](#), [84](#)
Capella, [86](#)
Cappelli, [143](#)
Caracteres, [87](#), [113](#), [117](#), [119](#)
Cardan, [119](#)
Carmen de Algorismo, [11](#), [134](#)
Casagrandi, [132](#)
Casiri, [8](#), [10](#)
Cassiodorus, [72](#)
Cataldi, [62](#)
Cataneo, [3](#)
Caxton, [143](#), [146](#)
Ceretti, [32](#)
Ceylon numerals, [36](#)
Chalfont, F. H., [28](#)
Champenois, [60](#)
Characters, *see* Caracteres
Charlemagne, [103](#)
Chasles, [54](#), [60](#), [85](#), [116](#), [122](#), [135](#)
Chassant, L. A., [142](#)
Chaucer, [121](#)
Chiarini, [145](#), [146](#)
Chiffre, [58](#)
Chinese numerals, [28](#), [56](#)
Chinese zero, [56](#)
Cifra, [120](#), [124](#)
Cipher, [58](#)
Circulus, [58](#), [60](#)
Clichtoveus, [61](#), [119](#), [145](#)
Codex Vigilanus, [138](#)
Codrington, O., [139](#)
Coins dated, [141](#)
Colebrooke, [8](#), [26](#), [46](#), [53](#)
Constantine, [104](#), [105](#)
Cosmas, [82](#)
Cossali, [5](#)

Counters, [117](#)
Courteille, [8](#)
Coxe, [59](#)
Crafte of Nombrynge, [11](#), [87](#), [149](#)
Crusades, [109](#)
Cunningham, A., [30](#), [75](#)
Curtze, [55](#), [59](#), [126](#), [134](#)
Cyfra, [55](#)

Dagomari, [146](#)
D'Alviella, [15](#)
Dante, [72](#)
Dasypodius, [33](#), [67](#), [63](#)
Daunou, [135](#)
Delambre, [54](#)
Devanāgarī, [7](#)
Devoulx, A., [68](#)
Dhruva, [49](#)
Dicæarchus of Messana, [77](#)
Digits, [119](#)
Diodorus Siculus, [76](#)
Du Cange, [62](#)
Dumesnil, [36](#)
Dutt, R. C., [12](#), [15](#), [18](#), [75](#)
Dvivedī, [44](#)

East and West, relations, [73-81](#), [100-109](#)
Egyptian numerals, [27](#)
Eisenlohr, [28](#)
Elia Misrachi, [57](#)
Enchiridion Algorismi, [58](#)
Eneström, [5](#), [48](#), [59](#), [97](#), [125](#), [128](#)
Europe, numerals in, [63](#), [99](#), [128](#), [136](#)
Eusebius Caesariensis, [142](#)
Euting, [21](#)
Ewald, P., [116](#)

Fazzari, [53](#), [54](#)
Fibonacci, *see* Leonardo of Pisa
Figura nihili, [58](#)
Figures, [119](#). *See* numerals.
Fihrist, [67](#), [68](#), [93](#)
Finaeus, [57](#)
Firdusī, [81](#)
Fitz Stephen, W., [109](#)
Fleet, J. C., [19](#), [20](#), [49](#)
Florus, [80](#)
Flügel, G., [68](#)
Francisco de Retza, [142](#)
François, [58](#)
Friedlein, G., [84](#), [113](#), [116](#), [122](#)
Froude, J. A., [129](#)

Gandhāra, [19](#)
Garbe, [48](#)
Gasbarri, [58](#)
Gautier de Coincy, [120](#), [124](#)
Gemma Frisius, [2](#), [3](#), [119](#)
Gerber, [113](#)
Gerbert, [108](#), [110-120](#), [122](#)
Gerhardt, C. I., [43](#), [56](#), [93](#), [118](#)
Gerland, [88](#), [123](#)
Gherard of Cremona, [125](#)
Gibbon, [72](#)
Giles, H. A., [79](#)
Ginanni, [81](#)
Giovanni di Danti, [58](#)
Glareanus, [4](#), [119](#)
Gnecchi, [71](#), [117](#)
Ġobār numerals, [65](#), [100](#), [112](#), [124](#), [138](#)
Gow, J., [81](#)
Grammateus, [61](#)
Greek origin, [33](#)
Green, J. R., [109](#)

Greenwood, I., [62](#), [119](#)
Guglielmini, [128](#)
Gulistān, [102](#)
Günther, S., [131](#)
Guyard, S., [82](#)

Ḥabash, [9](#), [92](#)
Hager, J. (G.), [28](#), [32](#)
Halliwell, [59](#), [85](#)
Hankel, [93](#)
Hārūn al-Rashīd, [97](#), [106](#)
Havet, [110](#)
Heath, T. L., [125](#)
Hebrew numerals, [127](#)
Hecataeus, [75](#)
Heiberg, J. L., [55](#), [85](#), [148](#)
Heilbronner, [5](#)
Henry, C., [5](#), [31](#), [55](#), [87](#), [120](#), [135](#)
Heriger, [122](#)
Hermannus Contractus, [123](#)
Herodotus, [76](#), [78](#)
Heyd, [75](#)
Higden, [136](#)
Hill, G. F., [52](#), [139](#), [142](#)
Hillebrandt, A., [15](#), [74](#)
Hilprecht, H. V., [28](#)
Hindu forms, early, [12](#)
Hindu number names, [42](#)
Hodder, [62](#)
Hoernle, [43](#), [49](#)
Holywood, *see* Sacrobosco
Hopkins, E. W., [12](#)
Horace, [79](#), [80](#)
Ḥosein ibn Moḥammed al-Maḥallī, [6](#)
Hostus, M., [56](#)
Howard, H. H., [29](#)
Hrabanus Maurus, [72](#)

Huart, [7](#)
Huet, [33](#)
Hugo, H., [57](#)
Humboldt, A. von, [62](#)
Huswirt, [58](#)

Iamblichus, [81](#)
Ibn Abī Ya‘qūb, [9](#)
Ibn al-Adamī, [92](#)
Ibn al-Bannā, [93](#)
Ibn Khordādbēh, [101](#), [106](#)
Ibn Wahab, [103](#)
India, history of, [14](#)
 writing in, [18](#)
Indicopleustes, [83](#)
Indo-Bactrian numerals, [19](#)
Indrājī, [23](#)
Ishāq ibn Yūsuf al-Ṣardafī, [93](#)

Jacob of Florence, [57](#)
Jacquet, E., [38](#)
Jamshid, [56](#)
Jehan Certain, [59](#)
Jetons, [58](#), [117](#)
Jevons, F. B., [76](#)
Johannes Hispalensis, [48](#), [88](#), [124](#)
John of Halifax, *see* Sacrobosco
John of Luna, *see* Johannes Hispalensis
Jordan, L., [58](#), [124](#)
Joseph Ispanus (Joseph Sapiens), [115](#)
Justinian, [104](#)

Kále, M. R., [26](#)
Karabacek, [56](#)
Karpinski, L. C., [126](#), [134](#), [138](#)
Kātyāyana, [39](#)
Kaye, C. R., [6](#), [16](#), [43](#), [46](#), [121](#)

Keane, J., [75](#), [82](#)
Keene, H. G., [15](#)
Kern, [44](#)
Kharoṣṭhī, [19](#), [20](#)
Khosrū, [82](#), [91](#)
Kielhorn, F., [46](#), [47](#)
Kircher, A., [34](#)
Kitāb al-Fihrist, *see* Fihrist
Kleinwächter, [32](#)
Klos, [62](#)
Köbel, [4](#), [58](#), [60](#), [119](#), [123](#)
Krumbacher, K., [57](#)
Kuckuck, [62](#), [133](#)
Kugler, F. X., [51](#)

Lachmann, [85](#)
Lacouperie, [33](#), [35](#)
Lalitavistara, [15](#), [17](#)
Lami, G., [57](#)
La Roche, [61](#)
Lassen, [39](#)
Lāṭyāyana, [39](#)
Lebœuf, [135](#)
Leonardo of Pisa, [5](#), [10](#), [57](#), [64](#), [74](#), [120](#), [128-133](#)
Lethaby, W. R., [142](#)
Levi, B., [13](#)
Levias, [3](#)
Libri, [73](#), [85](#), [95](#)
Light of Asia, [16](#)
Luca da Firenze, [144](#)
Lucas, [128](#)

Mahābhārata, [18](#)
Mahāvīrācārya, [53](#)
Malabar numerals, [36](#)
Malayalam numerals, [36](#)
Mannert, [81](#)

Margarita Philosophica, [146](#)
Marie, [78](#)
Marquardt, J., [85](#)
Marshman, J. C., [17](#)
Martin, T. H., [30](#), [62](#), [85](#), [113](#)
Martines, D. C., [58](#)
Māshāllāh, [3](#)
Maspero, [28](#)
Mauch, [142](#)
Maximus Planudes, [2](#), [57](#), [66](#), [93](#), [120](#)
Megasthenes, [77](#)
Merchants, [114](#)
Meynard, [8](#)
Migne, [87](#)
Mikami, Y., [56](#)
Milanesi, [128](#)
Moḥammed ibn ‘Abdallāh, [92](#)
Moḥammed ibn Aḥmed, [6](#)
Moḥammed ibn ‘Alī ‘Abdī, [8](#)
Moḥammed ibn Mūsā, *see* Al-Khowārazmī
Molinier, [123](#)
Monier-Williams, [17](#)
Morley, D., [126](#)
Moroccan numerals, [68](#), [119](#)
Mortet, V., [11](#)
Moseley, C. B., [33](#)
Moṭahhar ibn Ṭāhir, [7](#)
Mueller, A., [68](#)
Mumford, J. K., [109](#)
Muwaffaq al-Dīn, [93](#)

Nabatean forms, [21](#)
Nallino, [4](#), [54](#), [55](#)
Nagl, A., [55](#), [110](#), [113](#), [126](#)
Nānā Ghāt inscriptions, [20](#), [22](#), [23](#), [40](#)
Narducci, [123](#)
Nasik cave inscriptions, [24](#)

Nazīf ibn Yumn, [94](#)
Neander, A., [75](#)
Neophytos, [57](#), [62](#)
Neo-Pythagoreans, [64](#)
Nesselmann, [58](#)
Newman, Cardinal, [96](#)
Newman, F. W., [131](#)
Nöldeke, Th., [91](#)
Notation, [61](#)
Note, [61](#), [119](#)
Noviomagus, [45](#), [61](#), [119](#), [150](#)
Null, [61](#)
Numerals,
 Algerian, [68](#)
 astrological, [150](#)
 Brāhmī, [19-22](#), [83](#)
 early ideas of origin, [1](#)
 Hindu, [26](#)
 Hindu, classified, [19](#), [38](#)
 Kharoṣṭhī, [19-22](#)
 Moroccan, [68](#)
 Nabatean, [21](#)
 origin, [27](#), [30](#), [31](#), [37](#)
 supposed Arabic origin, [2](#)
 supposed Babylonian origin, [28](#)
 supposed Chaldean and Jewish origin, [3](#)
 supposed Chinese origin, [28](#), [32](#)
 supposed Egyptian origin, [27](#), [30](#), [69](#), [70](#)
 supposed Greek origin, [33](#)
 supposed Phœnician origin, [32](#)
 tables of, [22-27](#), [36](#), [48](#), [49](#), [69](#), [88](#), [140](#), [143](#), [145-148](#)

O'Creat, [5](#), [55](#), [119](#), [120](#)
Olleris, [110](#), [113](#)
Oppert, G., [14](#), [75](#)

Pali, [22](#)

Pañcasiddhāntikā, [44](#)
Paravey, [32](#), [57](#)
Pātalīputra, [77](#)
Patna, [77](#)
Patrick, R., [119](#)
Payne, E. J., [106](#)
Pegolotti, [107](#)
Peletier, [2](#), [62](#)
Perrot, [80](#)
Persia, [66](#), [91](#), [107](#)
Pertz, [115](#)
Petrus de Dacia, [59](#), [61](#), [62](#)
Pez, P. B., [117](#)
"Philalethes," [75](#)
Phillips, G., [107](#)
Picavet, [105](#)
Pichler, F., [141](#)
Pihan, A. P., [36](#)
Pisa, [128](#)
Place value, [26](#), [42](#), [46](#), [48](#)
Planudes, *see* Maximus Planudes
Plimpton, G. A., [56](#), [59](#), [85](#), [143](#), [144](#), [145](#), [148](#)
Pliny, [76](#)
Polo, N. and M., [107](#)
Prändel, J. G., [54](#)
Prinsep, J., [20](#), [31](#)
Propertius, [80](#)
Prodocimo de' Beldomandi, [137](#)
Prou, [143](#)
Ptolemy, [54](#), [78](#)
Putnam, [103](#)
Pythagoras, [63](#)
Pythagorean numbers, [13](#)
Pytheas of Massilia, [76](#)

Rabbi ben Ezra, [60](#), [127](#)
Radulph of Laon, [60](#), [113](#), [118](#), [124](#)

Raets, [62](#)
Rainer, *see* Gemma Frisius
Rāmāyana, [18](#)
Ramus, [2](#), [41](#), [60](#), [61](#)
Raoul Glaber, [123](#)
Rapson, [77](#)
Rauhfuß, *see* Dasypodius
Raumer, K. von, [111](#)
Reclus, E., [14](#), [96](#), [130](#)
Recorde, [3](#), [58](#)
Reinaud, [67](#), [74](#), [80](#)
Reveillaud, [36](#)
Richer, [110](#), [112](#), [115](#)
Riese, A., [119](#)
Robertson, [81](#)
Robertus Cestrensis, [97](#), [126](#)
Rodet, [5](#), [44](#)
Roediger, J., [68](#)
Rollandus, [144](#)
Romagnosi, [81](#)
Rosen, F., [5](#)
Rotula, [60](#)
Rudolff, [85](#)
Rudolph, [62](#), [67](#)
Ruffi, [150](#)

Sachau, [6](#)
Sacrobosco, [3](#), [58](#), [133](#)
Sacy, S. de, [66](#), [70](#)
Sa'dī, [102](#)
Śaka inscriptions, [20](#)
Samū'īl ibn Yaḥyā, [93](#)
Śāradā characters, [55](#)
Savonne, [60](#)
Scaliger, J. C., [73](#)
Scheubel, [62](#)
Schlegel, [12](#)

Schmidt, [133](#)
Schonerus, [87](#), [119](#)
Schroeder, L. von, [13](#)
Scylax, [75](#)
Sedillot, [8](#), [34](#)
Senart, [20](#), [24](#), [25](#)
Sened ibn ‘Alī, [10](#), [98](#)
Sfortunati, [62](#), [150](#)
Shelley, W., [126](#)
Siamese numerals, [36](#)
Siddhānta, [8](#), [18](#)
Şifr, [57](#)
Sigsboto, [55](#)
Sihāb al-Dīn, [67](#)
Silberberg, [60](#)
Simon, [13](#)
Sinān ibn al-Faḥ, [93](#)
Sindbad, [100](#)
Sindhind, [97](#)
Sipos, [60](#)
Sirr, H. C., [75](#)
Skeel, C. A., [74](#)
Smith, D. E., [11](#), [17](#), [53](#), [86](#), [141](#), [143](#)
Smith, V. A., [20](#), [35](#), [46](#), [47](#)
Smith, Wm., [75](#)
Smṛti, [17](#)
Spain, [64](#), [65](#), [100](#)
Spitta-Bey, [5](#)
Sprenger, [94](#)
Śrautasūtra, [39](#)
Steffens, F., [116](#)
Steinschneider, [5](#), [57](#), [65](#), [66](#), [98](#), [126](#)
Stifel, [62](#)
Subandhus, [44](#)
Suetonius, [80](#)
Suleimān, [100](#)
Śūnya, [43](#), [53](#), [57](#)

Suter, [5](#), [9](#), [68](#), [69](#), [93](#), [116](#), [131](#)

Sūtras, [13](#)

Sykes, P. M., [75](#)

Sylvester II, *see* Gerbert

Symonds, J. A., [129](#)

Tannery, P., [62](#), [84](#), [85](#)

Tartaglia, [4](#), [61](#)

Taylor, I., [19](#), [30](#)

Teca, [55](#), [61](#)

Tennent, J. E., [75](#)

Texada, [60](#)

Theca, [58](#), [61](#)

Theophanes, [64](#)

Thibaut, G., [12](#), [13](#), [16](#), [44](#), [47](#)

Tibetan numerals, [36](#)

Timotheus, [103](#)

Tonstall, C., [3](#), [61](#)

Trenchant, [60](#)

Treutlein, [5](#), [63](#), [123](#)

Trevisa, [136](#)

Treviso arithmetic, [145](#)

Trivium and quadrivium, [73](#)

Tsin, [56](#)

Tunis, [65](#)

Turchill, [88](#), [118](#), [123](#)

Turnour, G., [75](#)

Tziphra, [57](#), [62](#)

τζίφρα, [55](#), [57](#), [62](#)

Tzwivel, [61](#), [118](#), [145](#)

Ujjain, [32](#)

Unger, [133](#)

Upanishads, [12](#)

Usk, [121](#)

Valla, G., [61](#)

Van der Schuere, [62](#)
Varāha-Mihira, [39](#), [44](#), [78](#)
Vāsavadattā, [44](#)
Vaux, Carra de, [9](#), [74](#)
Vaux, W. S. W., [91](#)
Vedāṅgas, [17](#)
Vedas, [12](#), [15](#), [17](#)
Vergil, [80](#)
Vincent, A. J. H., [57](#)
Vogt, [13](#)
Voizot, P., [36](#)
Vossius, [4](#), [76](#), [81](#), [84](#)

Wallis, [3](#), [62](#), [84](#), [116](#)
Wappler, E., [54](#), [126](#)
Wäschke, H., [2](#), [93](#)
Wattenbach, [143](#)
Weber, A., [31](#)
Weidler, I. F., [34](#), [66](#)
Weidler, I. F. and G. I., [63](#), [66](#)
Weissenborn, [85](#), [110](#)
Wertheim, G., [57](#), [61](#)
Whitney, W. D., [13](#)
Wilford, F., [75](#)
Wilkins, [62](#)
Wilkinson, J. G., [70](#)
Willichius, [3](#)
Woepcke, [3](#), [6](#), [42](#), [63](#), [64](#), [65](#), [67](#), [69](#), [70](#), [94](#), [113](#), [138](#)
Wolack, G., [54](#)
Woodruff, C. E., [32](#)
Word and letter numerals, [38](#), [44](#)
Wüstenfeld, [74](#)

Yule, H., [107](#)

Zephyrum, [57](#), [58](#)
Zephyr, [59](#)

Zepiro, [58](#)

Zero, [26](#), [38](#), [40](#), [43](#), [45](#), [49](#), [51-62](#), [67](#)

Zeuro, [58](#)

ANNOUNCEMENTS

WENTWORTH'S

COLLEGE ALGEBRA

REVISED EDITION

12mo. Half morocco. 530 pages. List price, \$1.50; mailing price, \$1.65

This book is a thorough revision of the author's "College Algebra." Some chapters of the old edition have been wholly rewritten, and the other chapters have been rewritten in part and greatly improved. The order of topics has been changed to a certain extent; the plan is to have each chapter as complete in itself as possible, so that the teacher may vary the order of succession at his discretion.

As the name implies, the work is intended for colleges and scientific schools. The first part is simply a review of the principles of algebra preceding Quadratic Equations, with just enough examples to illustrate and enforce these principles. By this brief treatment of the first chapters sufficient space is allowed, without making the book cumbersome, for a full discussion of Quadratic Equations, The Binomial Theorem, Choice Chance, Series, Determinants, and the General Properties of Equations.

Every effort has been made to present in the clearest light each subject discussed, and to give in matter and methods the best training in algebraic analysis at present attainable.

ADDITIONAL PUBLICATIONS

By G. A. WENTWORTH

| | List
price | Mailing
price |
|--|---------------|------------------|
| Plane and Solid Geometry (Revised Edition) | \$1.25 | \$1.40 |
| Plane Geometry (Revised Edition) | .75 | .85 |
| Solid Geometry (Revised Edition) | .75 | .85 |

| | | |
|--|------|------|
| Analytic Geometry | 1.25 | 1.35 |
| Trigonometries (Second Revised Editions) | | |

A list of the various editions of Wentworth's Trigonometries will be sent on request.

GINN AND COMPANY PUBLISHERS

ALGEBRA FOR BEGINNERS

By DAVID EUGENE SMITH,

Professor of Mathematics in Teachers College, Columbia University

12mo, cloth, 154 pages, 50 cents

This work is intended to serve as an introduction to the study of algebra, and is adapted to the needs of the seventh or eighth school year. It is arranged in harmony with the leading courses of study that include algebra in the curriculum of the grades.

The relation of algebra to arithmetic is emphasized, the subject is treated topically, and each important point is touched at least twice. The book begins by showing the uses of algebra, employing such practical applications as are within the pupil's range of knowledge. When an interest has thus been awakened in the subject, the fundamental operations are presented with the simple explanations necessary to make the student independent of dogmatic rules. Throughout the book abundant oral and written drill exercises are provided. The work includes linear equations with two unknown quantities, and easy quadratics.

The leading features may be summarized as follows: (1) an arrangement in harmony with existing courses of study; (2) a presentation designed to awaken the interest of the pupils; (3) a topical arrangement for each half year, every important topic being repeated; (4) simplicity of explanations; (5) development of the relation of algebra to arithmetic both in theory and in applications; (6) emphasis laid on the importance of oral as well as written algebra.

GINN & COMPANY PUBLISHERS

BOOKS FOR TEACHERS

| | List
price |
|---|---------------|
| Allen: Civics and Health | \$1.25 |
| Brigham: Geographic Influences in American History | 1.25 |
| Channing and Hart: Guide to the Study of American History | 2.00 |
| Hall: Aspects of Child Life and Education | 1.50 |
| Hodge: Nature Study and Life | 1.50 |
| Johnson: Education by Plays and Games | .90 |
| Johnson: What to Do at Recess | .25 |
| Kern: Among Country Schools | 1.25 |
| Mace: Method in History | 1.00 |
| MacVicar: The Principles of Education | .60 |
| Moral Training in the Public Schools | 1.25 |
| Prince: Courses of Studies and Methods of Teaching | .75 |
| Scott: Social Education | 1.25 |
| Tompkins: Philosophy of School Management | .75 |
| Tompkins: Philosophy of Teaching | .75 |
| Wiltse: Place of the Story in Early Education, and Other Essays. A
Manual for Teachers | .50 |

FOR CLASS RECORDS

| | |
|---|-----|
| Comings: Complete Record—Attendance and Scholarship | |
| Graded-School Edition | .30 |
| High-School Edition | .30 |
| Ginn and Company: Teacher's Class Books | |
| No. I | .30 |

| | |
|--------------------------|-----|
| No. II | .40 |
| Twenty Weeks' Class Book | .30 |

GINN AND COMPANY Publishers

TEXTBOOKS ON MATHEMATICS

FOR HIGHER SCHOOLS AND COLLEGES

| | List
price |
|--|---------------|
| Bailey and Woods: Analytic Geometry | \$2.00 |
| Beman and Smith: Academic Algebra | 1.12 |
| Beman and Smith: Higher Arithmetic | .80 |
| Beman and Smith: New Plane and Solid Geometry | 1.25 |
| Breckenridge, Mersereau, and Moore: Shop Problems in
Mathematics | 1.00 |
| Byerly: Differential Calculus | 2.00 |
| Byerly: Integral Calculus (Second Edition. Revised and Enlarged) | 2.00 |
| Eisenhart: Differential Geometry of Curves and Surfaces | 4.50 |
| Faunce: Descriptive Geometry | 1.25 |
| Fine: College Algebra | 1.50 |
| Granville: Plane and Spherical Trigonometry and Tables | 1.25 |
| Granville: Plane and Spherical Trigonometry Without Tables | 1.00 |
| Granville: Plane Trigonometry and Tables | 1.00 |
| Granville: Logarithmic Tables | .50 |
| Granville and Smith: Elements of Differential and Integral
Calculus | 2.50 |
| Hardy: Analytic Geometry | 1.50 |
| Hardy: Elements of the Calculus | 1.50 |
| Hawkes: Advanced Algebra | 1.40 |
| Hawkes, Luby, and Touton: First Course in Algebra | 1.00 |
| Hedrick: Goursat's Mathematical Analysis. Vol. I | 4.00 |
| Hedrick and Kellogg: Applications of the Calculus to Mechanics | 1.25 |
| Hooper and Wells: Electrical Problems | 1.25 |

| | |
|---|------|
| Lester: Integrals of Mechanics | .80 |
| Peirce, B. O.: Newtonian Potential Function (Third, Revised, and Enlarged Edition) | 2.50 |
| Peirce, J. M.: Elements of Logarithms | .50 |
| Peirce, J. M.: Mathematical Tables | .40 |
| Pierpont: Theory of Functions of Real Variables. Vol. I | 4.50 |
| Shepard: Problems in the Strength of Materials | 1.25 |
| Slocum and Hancock: Textbook on the Strength of Materials | 3.00 |
| Smith and Gale: Elements of Analytic Geometry | 2.00 |
| Smith and Gale: Introduction to Analytic Geometry | 1.25 |
| Smith and Longley: Theoretical Mechanics | 2.50 |
| Taylor: Elements of the Calculus (Revised and Enlarged Edition) | 2.00 |
| Taylor: Plane and Spherical Trigonometry | 1.00 |
| Taylor: Plane Trigonometry | .75 |
| Taylor and Puryear: Elements of Plane and Spherical Trigonometry | 1.25 |
| Wentworth: Advanced Arithmetic | 1.00 |
| Wentworth: Analytic Geometry | 1.25 |
| Wentworth: College Algebra (Revised Edition) | 1.50 |
| Wentworth: Elementary Algebra | 1.12 |
| Wentworth: Higher Algebra | 1.40 |
| Wentworth: New School Algebra | 1.12 |
| Wentworth: Plane and Solid Geometry (Revised Edition) | 1.25 |
| Wentworth: Plane Geometry (Revised Edition); Solid Geometry (Revised Edition), each | .75 |
| Wentworth: Trigonometries (Second Revised Editions) | |
| (For list, see Descriptive Catalogue) | |
| Woods and Bailey: A Course In Mathematics | |
| Volume I | 2.25 |
| Volume II | 2.25 |

GINN AND COMPANY PUBLISHERS

Notes

[1] "*Discipulus*. Quis primus invenit numerum apud Hebræos et Ægyptios? *Magister*. Abraham primus invenit numerum apud Hebræos, deinde Moses; et Abraham tradidit istam scientiam numeri ad Ægyptios, et docuit eos: deinde Josephus." [Bede, *De computo dialogus* (doubtfully assigned to him), *Opera omnia*, Paris, 1862, Vol. I, p. 650.]

"Alii referunt ad Phœnices inventores arithmeticae, propter eandem commerciorum causam: Alii ad Indos: Ioannes de Sacrobosco, cujus sepulchrum est Lutetiae in comitio Maturinensi, refert ad Arabes." [Ramus, *Arithmeticae libri duo*, Basel, 1569, p. 112.]

Similar notes are given by Peletarius in his commentary on the arithmetic of Gemma Frisius (1563 ed., fol. 77), and in his own work (1570 Lyons ed., p. 14): "La valeur des Figures commence au coste dextre tirant vers le coste senestre: au rebours de notre maniere d'escrire par ce que la premiere pratique est venue des Chaldee: ou des Pheniciens, qui ont été les premiers traffiquers de marchandise."

[2] Maximus Planudes (c. 1330) states that "the nine symbols come from the Indians." [Wäschke's German translation, Halle, 1878, p. 3.] Willichius speaks of the "Zyphræ Indicae," in his *Arithmeticae libri tres* (Strasburg, 1540, p. 93), and Cataneo of "le noue figure de gli Indi," in his *Le pratiche delle dve prime mathematiche* (Venice, 1546, fol. 1). Woepcke is not correct, therefore, in saying ("Mémoire sur la propagation des chiffres indiens," hereafter referred to as *Propagation* [*Journal Asiatique*, Vol. I (6), 1863, p. 34]) that Wallis (*A Treatise on Algebra, both historical and practical*, London, 1685, p. 13, and *De algebra tractatus*, Latin edition in his *Opera omnia*, 1693, Vol. II, p. 10) was one of the first to give the Hindu origin.

[3] From the 1558 edition of *The Grovnd of Artes*, fol. C, 5. Similarly Bishop Tonstall writes: "Qui a Chaldeis primum in finitimos, deinde in omnes pene gentes fluxit.... Numerandi artem a Chaldeis esse profectam: qui dum scribunt, a dextra incipiunt, et

in leuam progrediuntur." [*De arte supputandi*, London, 1522, fol. B, 3.] Gemma Frisius, the great continental rival of Recorde, had the same idea: "Primùm autem appellamus dexterum locum, eo quòd haec ars vel à Chaldæis, vel ab Hebræis ortum habere credatur, qui etiam eo ordine scribunt"; but this refers more evidently to the Arabic numerals. [*Arithmeticae practicae methodvs facilis*, Antwerp, 1540, fol. 4 of the 1563 ed.] Sacrobosco (c. 1225) mentions the same thing. Even the modern Jewish writers claim that one of their scholars, Māshāllāh (c. 800), introduced them to the Mohammedan world. [C. Levias, *The Jewish Encyclopedia*, New York, 1905, Vol. IX, p. 348.]

[4] "... & que esto fu trouato di fare da gli Arabi con diece figure." [*La prima parte del general trattato di nvmeri, et misvre*, Venice, 1556, fol. 9 of the 1592 edition.]

[5] "Vom welchen Arabischen auch disz Kunst entsprungen ist." [*Ain nerv geordnet Rechenbiechlin*, Augsburg, 1514, fol. 13 of the 1531 edition. The printer used the letters *rv* for *w* in "new" in the first edition, as he had no *w* of the proper font.]

[6] Among them Glareanus: "Characteres simplices sunt nouem significatiui, ab Indis usque, siue Chaldæis asciti .1.2.3.4.5.6.7.8.9. Est item unus .0 circulus, qui nihil significat." [*De VI. Arithmeticae practicae speciebus*, Paris, 1539, fol. 9 of the 1543 edition.]

[7] "Barbarische oder gemeine Ziffern." [Anonymous, *Das Einmahl Eins cum notis variorum*, Dresden, 1703, p. 3.] So Vossius (*De universae matheseos natura et constitutione liber*, Amsterdam, 1650, p. 34) calls them "Barbaras numeri notas." The word at that time was possibly synonymous with Arabic.

[8] His full name was 'Abū 'Abdallāh Moḥammed ibn Mūsā al-Khowārazmī. He was born in Khowārezm, "the lowlands," the country about the present Khiva and bordering on the Oxus, and lived at Bagdad under the caliph al-Māmūn. He died probably between 220 and 230 of the Mohammedan era, that is, between 835 and 845 A.D., although some put the date as early as 812. The

best account of this great scholar may be found in an article by C. Nallino, "Al-Ḥuwārizmī" in the *Atti della R. Accad. dei Lincei*, Rome, 1896. See also *Verhandlungen des 5. Congresses der Orientalisten*, Berlin, 1882, Vol. II, p. 19; W. Spitta-Bey in the *Zeitschrift der deutschen Morgenländ. Gesellschaft*, Vol. XXXIII, p. 224; Steinschneider in the *Zeitschrift der deutschen Morgenländ. Gesellschaft*, Vol. L, p. 214; Treutlein in the *Abhandlungen zur Geschichte der Mathematik*, Vol. I, p. 5; Suter, "Die Mathematiker und Astronomen der Araber und ihre Werke," *Abhandlungen zur Geschichte der Mathematik*, Vol. X, Leipzig, 1900, p. 10, and "Nachträge," in Vol. XIV, p. 158; Cantor, *Geschichte der Mathematik*, Vol. I, 3d ed., pp. 712-733 etc.; F. Woepcke in *Propagation*, p. 489. So recently has he become known that Heilbronner, writing in 1742, merely mentions him as "Ben-Musa, inter Arabes celebris Geometra, scripsit de figuris planis & sphericis." [*Historia matheseos universæ*, Leipzig, 1742, p. 438.]

In this work most of the Arabic names will be transliterated substantially as laid down by Suter in his work *Die Mathematiker* etc., except where this violates English pronunciation. The scheme of pronunciation of oriental names is set forth in the preface.

[9] Our word *algebra* is from the title of one of his works, Al-jabr wa'l-muqābalah, Completion and Comparison. The work was translated into English by F. Rosen, London, 1831, and treated in *L'Algèbre d'al-Khārizmi et les méthodes indienne et grecque*, Léon Rodet, Paris, 1878, extract from the *Journal Asiatique*. For the derivation of the word *algebra*, see Cossali, *Scritti Inediti*, pp. 381-383, Rome, 1857; Leonardo's *Liber Abbaci* (1202), p. 410, Rome, 1857; both published by B. Boncompagni. "Almuchabala" also was used as a name for algebra.

[10] This learned scholar, teacher of O'Creat who wrote the *Helceph* ("Prologus N. Ocreati in *Helceph ad Adelardum Batensem magistrum suum*"), studied in Toledo, learned Arabic, traveled as far east as Egypt, and brought from the Levant

numerous manuscripts for study and translation. See Henry in the *Abhandlungen zur Geschichte der Mathematik*, Vol. III, p. 131; Woepcke in *Propagation*, p. 518.

[11] The title is *Algoritmi de numero Indorum*. That he did not make this translation is asserted by Eneström in the *Bibliotheca Mathematica*, Vol. I (3), p. 520.

[12] Thus he speaks "de numero indorum per .IX. literas," and proceeds: "Dixit algoritmi: Cum uidissem yndos constituisse .IX. literas in uniuerso numero suo, propter dispositionem suam quam posuerunt, uolui patefacere de opera quod fit per eas aliquid quod esset leuius discentibus, si deus uoluerit." [Boncompagni, *Trattati d'Aritmetica*, Rome, 1857.] Discussed by F. Woepcke, *Sur l'introduction de l'arithmétique indienne en Occident*, Rome, 1859.

[13] Thus in a commentary by 'Alī ibn Abī Bekr ibn al-Jamāl al-Anṣārī al-Mekkī on a treatise on ḡobār arithmetic (explained later) called *Al-murshidah*, found by Woepcke in Paris (*Propagation*, p. 66), there is mentioned the fact that there are "nine Indian figures" and "a second kind of Indian figures ... although these are the figures of the ḡobār writing." So in a commentary by Ḥosein ibn Moḥammed al-Maḥallī (died in 1756) on the *Mokhtaṣar fī'ilm el-ḥisāb* (Extract from Arithmetic) by 'Abdalqādir ibn 'Alī al-Sakhāwī (died c. 1000) it is related that "the preface treats of the forms of the figures of Hindu signs, such as were established by the Hindu nation." [Woepcke, *Propagation*, p. 63.]

[14] See also Woepcke, *Propagation*, p. 505. The origin is discussed at much length by G. R. Kaye, "Notes on Indian Mathematics.—Arithmetical Notation," *Journ. and Proc. of the Asiatic Soc. of Bengal*, Vol. III, 1907, p. 489.

[15] *Alberuni's India*, Arabic version, London, 1887; English translation, *ibid.*, 1888.

[16] *Chronology of Ancient Nations*, London, 1879. Arabic and English versions, by C. E. Sachau.

[17] *India*, Vol. I, chap. xvi.

[18] The Hindu name for the symbols of the decimal place system.

[19] Sachau's English edition of the *Chronology*, p. 64.

[20] *Littérature arabe*, Cl. Huart, Paris, 1902.

[21] Huart, *History of Arabic Literature*, English ed., New York, 1903, p. 182 seq.

[22] Al-Mas'ūdī's *Meadows of Gold*, translated in part by Aloys Sprenger, London, 1841; *Les prairies d'or*, trad. par C. Barbier de Meynard et Pavet de Courteille, Vols. I to IX, Paris, 1861-1877.

[23] *Les prairies d'or*, Vol. VIII, p. 289 seq.

[24] *Essays*, Vol. II, p. 428.

[25] Loc. cit., p. 504.

[26] *Matériaux pour servir à l'histoire comparée des sciences mathématiques chez les Grecs et les Orientaux*, 2 vols., Paris, 1845-1849, pp. 438-439.

[27] He made an exception, however, in favor of the numerals, loc. cit., Vol. II, p. 503.

[28] *Bibliotheca Arabico-Hispana Escorialensis*, Madrid, 1760-1770, pp. 426-427.

[29] The author, Ibn al-Qifṭī, flourished A.D. 1198 [Colebrooke, loc. cit., note Vol. II, p. 510].

[30] "Liber Artis Logisticae à Mohamado Ben Musa Alkhwarezmita exornatus, qui ceteros omnes brevitae methodi ac facilitate praestat, Indorum que in praeclarissimis inventis ingenium & acumen ostendit." [Casiri, loc. cit., p. 427.]

[31] Maçoudi, *Le livre de l'avertissement et de la révision*. Translation by B. Carra de Vaux, Paris, 1896.

[32] Verifying the hypothesis of Woepcke, *Propagation*, that the Sindhind included a treatment of arithmetic.

[33] Aḥmed ibn 'Abdallāh, Suter, *Die Mathematiker*, etc., p. 12.

[34] *India*, Vol. II, p. 15.

[35] See H. Suter, "Das Mathematiker-Verzeichniss im Fihrist," *Abhandlungen zur Geschichte der Mathematik*, Vol. VI, Leipzig, 1892. For further references to early Arabic writers the reader is referred to H. Suter, *Die Mathematiker und Astronomen der Araber und ihre Werke*. Also "Nachträge und Berichtigungen" to the same (*Abhandlungen*, Vol. XIV, 1902, pp. 155-186).

[36] Suter, loc. cit., note 165, pp. 62-63.

[37] "Send Ben Ali,... tùm arithmetica scripta maximè celebrata, quae publici juris fecit." [Loc. cit., p. 440.]

[38] *Scritti di Leonardo Pisano*, Vol. I, *Liber Abbaci* (1857); Vol. II, *Scritti* (1862); published by Baldassarre Boncompagni, Rome. Also *Tre Scritti Inediti*, and *Intorno ad Opere di Leonardo Pisano*, Rome, 1854.

[39] "Ubi ex mirabili magisterio in arte per novem figuras indorum introductus" etc. In another place, as a heading to a separate division, he writes, "De cognitione novem figurarum yndorum" etc. "Novem figure indorum he sunt 9 8 7 6 5 4 3 2 1."

[40] See *An Ancient English Algorism*, by David Eugene Smith, in *Festschrift Moritz Cantor*, Leipzig, 1909. See also Victor Mortet, "Le plus ancien traité francais d'algorisme," *Bibliotheca Mathematica*, Vol. IX (3), pp. 55-64.

[41] These are the two opening lines of the *Carmen de Algorismo* that the anonymous author is explaining. They should read as follows:

Haec algorismus ars praesens dicitur, in qua
Talibus Indorum fruimur bis quinque figuris.

What follows is the translation.

[42] Thibaut, *Astronomie, Astrologie und Mathematik*, Strassburg, 1899.

[43] Gustave Schlegel, *Uranographie chinoise ou preuves directes que l'astronomie primitive est originaire de la Chine, et qu'elle a été empruntée par les anciens peuples occidentaux à la sphère chinoise; ouvrage accompagné d'un atlas céleste chinois et grec*, The Hague and Leyden, 1875.

[44] E. W. Hopkins, *The Religions of India*, Boston, 1898, p. 7.

[45] R. C. Dutt, *History of India*, London, 1906.

[46] W. D. Whitney, *Sanskrit Grammar*, 3d ed., Leipzig, 1896.

[47] "Das Āpastamba-Śulba-Sūtra," *Zeitschrift der deutschen Morgenländischen Gesellschaft*, Vol. LV, p. 543, and Vol. LVI, p. 327.

[48] *Geschichte der Math.*, Vol. I, 2d ed., p. 595.

[49] L. von Schroeder, *Pythagoras und die Inder*, Leipzig, 1884; H. Vogt, "Haben die alten Inder den Pythagoreischen Lehrsatz und das Irrationale gekannt?" *Bibliotheca Mathematica*, Vol. VII (3), pp. 6-20; A. Bürk, loc. cit.; Max Simon, *Geschichte der Mathematik im Altertum*, Berlin, 1909, pp. 137-165; three Sūtras are translated in part by Thibaut, *Journal of the Asiatic Society of Bengal*, 1875, and one appeared in *The Pandit*, 1875; Beppo Levi, "Osservazioni e congetture sopra la geometria degli indiani," *Bibliotheca Mathematica*, Vol. IX (3), 1908, pp. 97-105.

[50] Loc. cit.; also *Indiens Literatur und Cultur*, Leipzig, 1887.

[51] It is generally agreed that the name of the river Sindhu, corrupted by western peoples to Hindhu, Indos, Indus, is the root

of Hindustan and of India. Reclus, *Asia*, English ed., Vol. III, p. 14.

[52] See the comments of Oppert, *On the Original Inhabitants of Bharatavarṣa or India*, London, 1893, p. 1.

[53] A. Hillebrandt, *Alt-Indien*, Breslau, 1899, p. 111. Fragmentary records relate that Khāravela, king of Kalinga, learned as a boy *lekhā* (writing), *gaṇanā* (reckoning), and *rūpa* (arithmetic applied to monetary affairs and mensuration), probably in the 5th century B.C. [Bühler, *Indische Palaeographie*, Strassburg, 1896, p. 5.]

[54] R. C. Dutt, *A History of Civilization in Ancient India*, London, 1893, Vol. I, p. 174.

[55] The Buddha. The date of his birth is uncertain. Sir Edwin Arnold put it c. 620 B.C.

[56] I.e. $100 \cdot 10^7$.

[57] There is some uncertainty about this limit.

[58] This problem deserves more study than has yet been given it. A beginning may be made with Comte Goblet d'Alviella, *Ce que l'Inde doit à la Grèce*, Paris, 1897, and H. G. Keene's review, "The Greeks in India," in the *Calcutta Review*, Vol. CXIV, 1902, p. 1. See also F. Woepeke, *Propagation*, p. 253; G. R. Kaye, loc. cit., p. 475 seq., and "The Source of Hindu Mathematics," *Journal of the Royal Asiatic Society*, July, 1910, pp. 749-760; G. Thibaut, *Astronomie, Astrologie und Mathematik*, pp. 43-50 and 76-79. It will be discussed more fully in Chapter VI.

[59] I.e. to 100,000. The lakh is still the common large unit in India, like the myriad in ancient Greece and the million in the West.

[60] This again suggests the *Psammites*, or *De harenae numero* as it is called in the 1544 edition of the *Opera* of Archimedes, a work in which the great Syracusan proposes to show to the king

"by geometric proofs which you can follow, that the numbers which have been named by us ... are sufficient to exceed not only the number of a sand-heap as large as the whole earth, but one as large as the universe." For a list of early editions of this work see D. E. Smith, *Rara Arithmetica*, Boston, 1909, p. 227.

[61] I.e. the Wise.

[62] Sir Monier Monier-Williams, *Indian Wisdom*, 4th ed., London, 1893, pp. 144, 177. See also J. C. Marshman, *Abridgment of the History of India*, London, 1893, p. 2.

[63] For a list and for some description of these works see R. C. Dutt, *A History of Civilization in Ancient India*, Vol. II, p. 121.

[64] Professor Ramkrishna Gopal Bhandarkar fixes the date as the fifth century B.C. ["Consideration of the Date of the Mahābhārata," in the *Journal of the Bombay Branch of the R. A. Soc.*, Bombay, 1873, Vol. X, p. 2.].

[65] Marshman, loc. cit., p. 2.

[66] A. C. Burnell, *South Indian Palæography*, 2d ed., London, 1878, p. 1, seq.

[67] This extensive subject of palpable arithmetic, essentially the history of the abacus, deserves to be treated in a work by itself.

[68] The following are the leading sources of information upon this subject: G. Bühler, *Indische Palaeographie*, particularly chap. vi; A. C. Burnell, *South Indian Palæography*, 2d ed., London, 1878, where tables of the various Indian numerals are given in Plate XXIII; E. C. Bayley, "On the Genealogy of Modern Numerals," *Journal of the Royal Asiatic Society*, Vol. XIV, part 3, and Vol. XV, part 1, and reprint, London, 1882; I. Taylor, in *The Academy*, January 28, 1882, with a repetition of his argument in his work *The Alphabet*, London, 1883, Vol. II, p. 265, based on Bayley; G. R. Kaye, loc. cit., in some respects one of the most critical articles thus far published; J. C. Fleet, *Corpus inscriptionum Indicarum*, London, 1888, Vol. III, with facsimiles

of many Indian inscriptions, and *Indian Epigraphy*, Oxford, 1907, reprinted from the *Imperial Gazetteer of India*, Vol. II, pp. 1-88, 1907; G. Thibaut, loc. cit., *Astronomie* etc.; R. Caldwell, *Comparative Grammar of the Dravidian Languages*, London, 1856, p. 262 seq.; and *Epigraphia Indica* (official publication of the government of India), Vols. I-IX. Another work of Bühler's, *On the Origin of the Indian Brāhma Alphabet*, is also of value.

[69] The earliest work on the subject was by James Prinsep, "On the Inscriptions of Piyadasi or Aśoka," etc., *Journal of the Asiatic Society of Bengal*, 1838, following a preliminary suggestion in the same journal in 1837. See also "Aśoka Notes," by V. A. Smith, *The Indian Antiquary*, Vol. XXXVII, 1908, p. 24 seq., Vol. XXXVIII, pp. 151-159, June, 1909; *The Early History of India*, 2d ed., Oxford, 1908, p. 154; J. F. Fleet, "The Last Words of Aśoka," *Journal of the Royal Asiatic Society*, October, 1909, pp. 981-1016; E. Senart, *Les inscriptions de Piyadasi*, 2 vols., Paris, 1887.

[70] For a discussion of the minor details of this system, see Bühler, loc. cit., p. 73.

[71] Julius Euting, *Nabatäische Inschriften aus Arabien*, Berlin, 1885, pp. 96-97, with a table of numerals.

[72] For the five principal theories see Bühler, loc. cit., p. 10.

[73] Bayley, loc. cit., reprint p. 3.

[74] Bühler, loc. cit.; *Epigraphia Indica*, Vol. III, p. 134; *Indian Antiquary*, Vol. VI, p. 155 seq., and Vol. X, p. 107.

[75] Pandit Bhagavānlāl Indrājī, "On Ancient Nāgāri Numeration; from an Inscription at Nāneghāt," *Journal of the Bombay Branch of the Royal Asiatic Society*, 1876, Vol. XII, p. 404.

[76] *Ib.*, p. 405. He gives also a plate and an interpretation of each numeral.

[77] These may be compared with Bühler's drawings, loc. cit.; with Bayley, loc. cit., p. 337 and plates; and with Bayley's article in the *Encyclopædia Britannica*, 9th ed., art. "Numerals."

[78] E. Senart, "The Inscriptions in the Caves at Nasik," *Epigraphia Indica*, Vol. VIII, pp. 59-96; "The Inscriptions in the Cave at Karle," *Epigraphia Indica*, Vol. VII, pp. 47-74; Bühler, *Palaeographie*, Tafel IX.

[79] See Fleet, loc. cit. See also T. Benfey, *Sanskrit Grammar*, London, 1863, p. 217; M. R. Kāle, *Higher Sanskrit Grammar*, 2d ed., Bombay, 1898, p. 110, and other authorities as cited.

[80] Kharoṣṭhī numerals, Aśoka inscriptions, c. 250 B.C. Senart, *Notes d'épigraphie indienne*. Given by Bühler, loc. cit., Tafel I.

[81] Same, Śaka inscriptions, probably of the first century B.C. Senart, loc. cit.; Bühler, loc. cit.

[82] Brāhmī numerals, Aśoka inscriptions, c. 250 B.C. *Indian Antiquary*, Vol. VI, p. 155 seq.

[83] Same, Nānā Ghāt inscriptions, c. 150 B.C. Bhagavānlāl Indrājī, *On Ancient Nāgarī Numeration*, loc. cit. Copied from a squeeze of the original.

[84] Same, Nasik inscription, c. 100 B.C. Burgess, *Archeological Survey Report, Western India*; Senart, *Epigraphia Indica*, Vol. VII, pp. 47-79, and Vol. VIII, pp. 59-96.

[85] Kṣatrapa coins, c. 200 A.D. *Journal of the Royal Asiatic Society*, 1890, p. 639.

[86] Kuṣana inscriptions, c. 150 A.D. *Epigraphia Indica*, Vol. I, p. 381, and Vol. II, p. 201.

[87] Gupta Inscriptions, c. 300 A.D. to 450 A.D. Fleet, loc. cit., Vol. III.

[88] Valhabī, c. 600 A.D. *Corpus*, Vol. III.

[89] Bendall's Table of Numerals, in *Cat. Sansk. Budd. MSS.*, British Museum.

[90] *Indian Antiquary*, Vol. XIII, 120; *Epigraphia Indica*, Vol. III, 127 ff.

[91] Fleet, loc. cit.

[92] Bayley, loc. cit., p. 335.

[93] From a copper plate of 493 A.D., found at Kārīṭalāī, Central India. [Fleet, loc. cit., Plate XVI.] It should be stated, however, that many of these copper plates, being deeds of property, have forged dates so as to give the appearance of antiquity of title. On the other hand, as Colebrooke long ago pointed out, a successful forgery has to imitate the writing of the period in question, so that it becomes evidence well worth considering, as shown in Chapter III.

[94] From a copper plate of 510 A.D., found at Majhgawāin, Central India. [Fleet, loc. cit., Plate XIV.]

[95] From an inscription of 588 A.D., found at Bōdh-Gayā, Bengal Presidency. [Fleet, loc. cit., Plate XXIV.]

[96] From a copper plate of 571 A.D., found at Māliyā, Bombay Presidency. [Fleet, loc. cit., Plate XXIV.]

[97] From a Bijayagaḍh pillar inscription of 372 A.D. [Fleet, loc. cit., Plate XXXVI, C.]

[98] From a copper plate of 434 A.D. [*Indian Antiquary*, Vol. I, p. 60.]

[99] Gadhwa inscription, c. 417 A.D. [Fleet, loc. cit., Plate IV, D.]

[100] Kārīṭalāī plate of 493 A.D., referred to above.

[101] It seems evident that the Chinese four, curiously enough called "eight in the mouth," is only a cursive 𑖀𑖀𑖀.

[102] Chalfont, F. H., *Memoirs of the Carnegie Museum*, Vol. IV, no. 1; J. Hager, *An Explanation of the Elementary Characters of the Chinese*, London, 1801.

[103] H. V. Hilprecht, *Mathematical, Metrological and Chronological Tablets from the Temple Library at Nippur*, Vol. XX, part I, of Series A, Cuneiform Texts Published by the Babylonian Expedition of the University of Pennsylvania, 1906; A. Eisenlohr, *Ein altbabylonischer Felderplan*, Leipzig, 1906; Maspero, *Dawn of Civilization*, p. 773.

[104] Sir H. H. Howard, "On the Earliest Inscriptions from Chaldea," *Proceedings of the Society of Biblical Archæology*, XXI, p. 301, London, 1899.

[105] For a bibliography of the principal hypotheses of this nature see Bühler, loc. cit., p. 77. Bühler (p. 78) feels that of all these hypotheses that which connects the Brāhmī with the Egyptian numerals is the most plausible, although he does not adduce any convincing proof. Th. Henri Martin, "Les signes numéraux et l'arithmétique chez les peuples de l'antiquité et du moyen âge" (being an examination of Cantor's *Mathematische Beiträge zum Culturleben der Völker*), *Annali di matematica pura ed applicata*, Vol. V, Rome, 1864, pp. 8, 70. Also, same author, "Recherches nouvelles sur l'origine de notre système de numération écrite," *Revue Archéologique*, 1857, pp. 36, 55. See also the tables given later in this work.

[106] *Journal of the Royal Asiatic Society, Bombay Branch*, Vol. XXIII.

[107] Loc. cit., reprint, Part I, pp. 12, 17. Bayley's deductions are generally regarded as unwarranted.

[108] *The Alphabet*; London, 1883, Vol. II, pp. 265, 266, and *The Academy* of Jan. 28, 1882.

[109] Taylor, *The Alphabet*, loc. cit., table on p. 266.

[110] Bühler, *On the Origin of the Indian Brāhma Alphabet*, Strassburg, 1898, footnote, pp. 52, 53.

[111] Albrecht Weber, *History of Indian Literature*, English ed., Boston, 1878, p. 256: "The Indian figures from 1-9 are abbreviated forms of the initial letters of the numerals themselves...: the zero, too, has arisen out of the first letter of the word *śunya* (empty) (it occurs even in Piṅgala). It is the decimal place value of these figures which gives them significance." C. Henry, "Sur l'origine de quelques notations mathématiques," *Revue Archéologique*, June and July, 1879, attempts to derive the Boethian forms from the initials of Latin words. See also J. Prinsep, "Examination of the Inscriptions from Girnar in Gujerat, and Dhauli in Cuttach," *Journal of the Asiatic Society of Bengal*, 1838, especially Plate XX, p. 348; this was the first work on the subject.

[112] Bühler, *Palaeographie*, p. 75, gives the list, with the list of letters (p. 76) corresponding to the number symbols.

[113] For a general discussion of the connection between the numerals and the different kinds of alphabets, see the articles by U. Ceretti, "Sulla origine delle cifre numerali moderne," *Rivista di fisica, matematica e scienze naturali*, Pisa and Pavia, 1909, anno X, numbers 114, 118, 119, and 120, and continuation in 1910.

[114] This is one of Bühler's hypotheses. See Bayley, loc. cit., reprint p. 4; a good bibliography of original sources is given in this work, p. 38.

[115] Loc. cit., reprint, part I, pp. 12, 17. See also Burnell, loc. cit., p. 64, and tables in plate XXIII.

[116] This was asserted by G. Hager (*Memoria sulle cifre arabiche*, Milan, 1813, also published in *Fundgruben des Orients*, Vienna, 1811, and in *Bibliothèque Britannique*, Geneva, 1812). See also the recent article by Major Charles E. Woodruff, "The Evolution of Modern Numerals from Tally Marks," *American Mathematical Monthly*, August-September, 1909. Biernatzki,

"Die Arithmetik der Chinesen," *Crelle's Journal für die reine und angewandte Mathematik*, Vol. LII, 1857, pp. 59-96, also asserts the priority of the Chinese claim for a place system and the zero, but upon the flimsiest authority. Ch. de Paravey, *Essai sur l'origine unique et hiéroglyphique des chiffres et des lettres de tous les peuples*, Paris, 1826; G. Kleinwächter, "The Origin of the Arabic Numerals," *China Review*, Vol. XI, 1882-1883, pp. 379-381, Vol. XII, pp. 28-30; Biot, "Note sur la connaissance que les Chinois ont eue de la valeur de position des chiffres," *Journal Asiatique*, 1839, pp. 497-502. A. Terrien de Lacouperie, "The Old Numerals, the Counting-Rods and the Swan-Pan in China," *Numismatic Chronicle*, Vol. III (3), pp. 297-340, and Crowder B. Moseley, "Numeral Characters: Theory of Origin and Development," *American Antiquarian*, Vol. XXII, pp. 279-284, both propose to derive our numerals from Chinese characters, in much the same way as is done by Major Woodruff, in the article above cited.

[117] The Greeks, probably following the Semitic custom, used nine letters of the alphabet for the numerals from 1 to 9, then nine others for 10 to 90, and further letters to represent 100 to 900. As the ordinary Greek alphabet was insufficient, containing only twenty-four letters, an alphabet of twenty-seven letters was used.

[118] *Institutiones mathematicae*, 2 vols., Strassburg, 1593-1596, a somewhat rare work from which the following quotation is taken:

"*Quis est harum Cyphrarum autor?*

"A quibus hae usitatae syphrarum notae sint inventae: hactenus incertum fuit: meo tamen iudicio, quod exiguum esse fateor: a graecis librarijs (quorum olim magna fuit copia) literae Graecorum quibus veteres Graeci tamquam numerorum notis sunt usi: fuerunt corruptae. vt ex his licet videre.

"Graecorum Literae corruptae.

"*Sed qua ratione graecorum literae ita fuerunt corruptae?*

"Finxerunt has corruptas Graecorum literarum notas: vel abiectioe vt in nota binarij numeri, vel additione vt in ternarij, vel inuersione vt in septenarij, numeri nota, nostrae notae, quibus hodie utimur: ab his sola differunt elegantia, vt apparet."

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| α | β | γ | δ | ε | ς | ζ | η | θ |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |

See also Bayer, *Historia regni Graecorum Bactriani*, St. Petersburg, 1788, pp. 129-130, quoted by Martin, *Recherches nouvelles*, etc., loc. cit.

[119] P. D. Huet, *Demonstratio evangelica*, Paris, 1769, note to p. 139 on p. 647: "Ab Arabibus vel ab Indis inventas esse, non vulgus eruditorum modo, sed doctissimi quique ad hanc diem arbitrati sunt. Ego vero falsum id esse, merosque esse Graecorum characteres aio; à librariis Graecae linguae ignaris interpolatos, et diuturna scribendi consuetudine corruptos. Nam primum 1 apex fuit, seu virgula, nota μονάδος. 2, est ipsum β extremis suis truncatum. γ, si in sinistram partem inclinaveris & cauda mutilaveris & sinistrum cornu sinistrorsum flexeris, fiet 3. Res ipsa loquitur 4 ipsissimum esse Δ, cujus crus sinistrum erigitur κατὰ κάθετον, & infra basim descendit; basis vero ipsa ultra crus producta eminet. Vides quam 5 simile sit τῷ ς; infimo tantum semicirculo, qui sinistrorsum patebat, dextrorsum converso. ἐπίσημον βαῦ quod ita notabatur ϛ, rotundato ventre, pede detracto, peperit τὸ 6. Ex Z basi sua mutilato, ortum est τὸ 7. Si H inflexis introrsum apicibus in rotundiolem & commodiorem formam mutaveris, exurget τὸ 8. At 9 ipsissimum est θ."

I. Weidler, *Spicilegium observationum ad historiam notarum numeralium*, Wittenberg, 1755, derives them from the Hebrew letters; Dom Augustin Calmet, "Recherches sur l'origine des chiffres d'arithmétique," *Mémoires pour l'histoire des sciences et des beaux arts*, Trévoux, 1707 (pp. 1620-1635, with two plates), derives the current symbols from the Romans, stating that they are relics of the ancient "Notae Tironianae." These "notes" were part of a system of shorthand invented, or at least perfected, by Tiro, a slave who was freed by Cicero. L. A. Sedillot, "Sur l'origine de nos chiffres," *Atti dell' Accademia pontificia dei nuovi*

Lincei, Vol. XVIII, 1864-1865, pp. 316-322, derives the Arabic forms from the Roman numerals.

[120] Athanasius Kircher, *Arithmologia sive De abditis Numerorum, mysterijs qua origo, antiquitas & fabrica Numerorum exponitur*, Rome, 1665.

[121] See Suter, *Die Mathematiker und Astronomen der Araber*, p. 100.

[122] "Et hi numeri sunt numeri Indiani, a Brachmanis Indiae Sapientibus ex figura circuli secti inuenti."

[123] V. A. Smith, *The Early History of India*, Oxford, 2d ed., 1908, p. 333.

[124] C. J. Ball, "An Inscribed Limestone Tablet from Sippara," *Proceedings of the Society of Biblical Archaeology*, Vol. XX, p. 25 (London, 1898). Terrien de Lacouperie states that the Chinese used the circle for 10 before the beginning of the Christian era. [*Catalogue of Chinese Coins*, London, 1892, p. xl.]

[125] For a purely fanciful derivation from the corresponding number of strokes, see W. W. R. Ball, *A Short Account of the History of Mathematics*, 1st ed., London, 1888, p. 147; similarly J. B. Reveillaud, *Essai sur les chiffres arabes*, Paris, 1883; P. Voizot, "Les chiffres arabes et leur origine," *La Nature*, 1899, p. 222; G. Dumesnil, "De la forme des chiffres usuels," *Annales de l'université de Grenoble*, 1907, Vol. XIX, pp. 657-674, also a note in *Revue Archéologique*, 1890, Vol. XVI (3), pp. 342-348; one of the earliest references to a possible derivation from points is in a work by Bettino entitled *Apiaria universae philosophiae mathematicae in quibus paradoxa et noua machinamenta ad usus eximios traducta, et facillimis demonstrationibus confirmata*, Bologna, 1545, Vol. II, Apiarium XI, p. 5.

[126] *Alphabetum Barmanum*, Romae, MDCCLXXVI, p. 50. The 1 is evidently Sanskrit, and the 4, 7, and possibly 9 are from India.

[127] *Alphabetum Grandonico-Malabaricum*, Romae, MDCCLXXII, p. 90. The zero is not used, but the symbols for 10, 100, and so on, are joined to the units to make the higher numbers.

[128] *Alphabetum Tangutanum*, Romae, MDCCLXXIII, p. 107. In a Tibetan MS. in the library of Professor Smith, probably of the eighteenth century, substantially these forms are given.

[129] Bayley, loc. cit., plate II. Similar forms to these here shown, and numerous other forms found in India, as well as those of other oriental countries, are given by A. P. Pihan, *Exposé des signes de numération usités chez les peuples orientaux anciens et modernes*, Paris, 1860.

[130] Bühler, loc. cit., p. 80; J. F. Fleet, *Corpus inscriptionum Indicarum*, Vol. III, Calcutta, 1888. Lists of such words are given also by Al-Bīrūnī in his work *India*; by Burnell, loc. cit.; by E. Jacquet, "Mode d'expression symbolique des nombres employé par les Indiens, les Tibétains et les Javanais," *Journal Asiatique*, Vol. XVI, Paris, 1835.

[131] This date is given by Fleet, loc. cit., Vol. III, p. 73, as the earliest epigraphical instance of this usage in India proper.

[132] Weber, *Indische Studien*, Vol. VIII, p. 166 seq.

[133] *Journal of the Royal Asiatic Society*, Vol. I (N.S.), p. 407.

[134] VIII, 20, 21.

[135] Th. H. Martin, *Les signes numériques ...*, Rome, 1864; Lassen, *Indische Alterthumskunde*, Vol. II, 2d ed., Leipzig and London, 1874, p. 1153.

[136] But see Burnell, loc. cit., and Thibaut, *Astronomie, Astrologie und Mathematik*, p. 71.

[137] A. Barth, "Inscriptions Sanscrites du Cambodge," in the *Notices et extraits des Mss. de la Bibliothèque nationale*, Vol. XXVII, Part I, pp. 1-180, 1885; see also numerous articles in *Journal Asiatique*, by Aymonier.

[138] Bühler, loc. cit., p. 82.

[139] Loc. cit., p. 79.

[140] Bühler, loc. cit., p. 83. The Hindu astrologers still use an alphabetical system of numerals. [Burnell, loc. cit., p. 79.]

[141] Well could Ramus say, "Quicunq; autem fuerit inventor decem notarum laudem magnam meruit."

[142] Al-Bīrūnī gives lists.

[143] *Propagation*, loc. cit., p. 443.

[144] See the quotation from *The Light of Asia* in Chapter II, p. 16.

[145] The nine ciphers were called *aṅka*.

[146] "Zur Geschichte des indischen Ziffernsystems," *Zeitschrift für die Kunde des Morgenlandes*, Vol. IV, 1842, pp. 74-83.

[147] It is found in the Bakhṣālī MS. of an elementary arithmetic which Hoernle placed, at first, about the beginning of our era, but the date is much in question. G. Thibaut, loc. cit., places it between 700 and 900 A.D.; Cantor places the body of the work about the third or fourth century A.D., *Geschichte der Mathematik*, Vol. I (3), p. 598.

[148] For the opposite side of the case see G. R. Kaye, "Notes on Indian Mathematics, No. 2.—Āryabhaṭa," *Journ. and Proc. of the Asiatic Soc. of Bengal*, Vol. IV, 1908, pp. 111-141.

[149] He used one of the alphabetic systems explained above. This ran up to 10^{18} and was not difficult, beginning as follows:

| | | | | |
|---|--------|--------|--------|----------------|
| ॠ | ॡ | ॢ | ॣ | । |
| 1 | 10^2 | 10^4 | 10^6 | 10^8 , etc., |

the same letter (*ka*) appearing in the successive consonant forms, *ka*, *kha*, *ga*, *gha*, etc. See C. I. Gerhardt, *Über die Entstehung und Ausbreitung des dekadischen Zahlensystems*, Programm, p. 17, Salzwedel, 1853, and *Études historiques sur l'arithmétique de position*, Programm, p. 24, Berlin, 1856; E. Jacquet, *Mode d'expression symbolique des nombres*, loc. cit., p. 97; L. Rodet, "Sur la véritable signification de la notation numérique inventée par Āryabhata," *Journal Asiatique*, Vol. XVI (7), pp. 440-485. On the two Āryabhaṭas see Kaye, *Bibl. Math.*, Vol. X (3), p. 289.

[150] Using *kha*, a synonym of *śūnya*. [Bayley, loc. cit., p. 22, and L. Rodet, *Journal Asiatique*, Vol. XVI (7), p. 443.]

[151] Varāha-Mihira, *Pañcasiddhāntikā*, translated by G. Thibaut and M. S. Dvivedī, Benares, 1889; see Bühler, loc. cit., p. 78; Bayley, loc. cit., p. 23.

[152] *Br̥hat Saṃhitā*, translated by Kern, *Journal of the Royal Asiatic Society*, 1870-1875.

[153] It is stated by Bühler in a personal letter to Bayley (loc. cit., p. 65) that there are hundreds of instances of this usage in the *Br̥hat Saṃhitā*. The system was also used in the *Pañcasiddhāntikā* as early as 505 A.D. [Bühler, *Palaeographie*, p. 80, and Fleet, *Journal of the Royal Asiatic Society*, 1910, p. 819.]

[154] Cantor, *Geschichte der Mathematik*, Vol. I (3), p. 608.

[155] Bühler, loc. cit., p. 78.

[156] Bayley, p. 38.

[157] Noviomagus, in his *De numeris libri duo*, Paris, 1539, confesses his ignorance as to the origin of the zero, but says: "D. Henricus Grauius, vir Graecè & Hebraicè eximè doctus, Hebraicam originem ostendit," adding that Valla "Indis Orientalibus gentibus inventionem tribuit."

[158] See *Essays*, Vol. II, pp. 287 and 288.

[159] Vol. XXX, p. 205 seqq.

[160] Loc. cit., p. 284 seqq.

[161] Colebrooke, loc. cit., p. 288.

[162] Loc. cit., p. 78.

[163] Hereafter, unless expressly stated to the contrary, we shall use the word "numerals" to mean numerals with place value.

[164] "The Gurjaras of Rājputāna and Kanauj," in *Journal of the Royal Asiatic Society*, January and April, 1909.

[165] Vol. IX, 1908, p. 248.

[166] *Epigraphia Indica*, Vol. IX, pp. 193 and 198.

[167] *Epigraphia Indica*, Vol. IX, p. 1.

[168] Loc. cit., p. 71.

[169] Thibaut, p. 71.

[170] "Est autem in aliquibus figurarum istaram apud multos diuersitas. Quidam enim septimam hanc figuram representant," etc. [Boncompagni, *Trattati*, p. 28.] Eneström has shown that very likely this work is incorrectly attributed to Johannes Hispalensis. [Bibliotheca Mathematica, Vol. IX (3), p. 2.]

[171] *Indische Palaeographie*, Tafel IX.

[172] Edited by Bloomfield and Garbe, Baltimore, 1901, containing photographic reproductions of the manuscript.

[173] Bakhṣālī MS. See page 43; Hoernle, R., *The Indian Antiquary*, Vol. XVII, pp. 33-48, 1 plate; Hoernle, *Verhandlungen des VII. Internationalen Orientalisten-Congresses, Arische Section*, Vienna, 1888, "On the Bakshālī Manuscript," pp. 127-147, 3 plates; Bühler, loc. cit.

[174] 3, 4, 6, from H. H. Dhruva, "Three Land-Grants from Sankheda," *Epigraphia Indica*, Vol. II, pp. 19-24 with plates; date

595 A.D. 7, 1, 5, from Bhandarkar, "Daulatabad Plates," *Epigraphia Indica*, Vol. IX, part V; date c. 798 A.D.

[175] 8, 7, 2, from "Buckhala Inscription of Nagabhatta," Bhandarkar, *Epigraphia Indica*, Vol. IX, part V; date 815 A.D. 5 from "The Morbi Copper-Plate," Bhandarkar, *The Indian Antiquary*, Vol. II, pp. 257-258, with plate; date 804 A.D. See Bühler, loc. cit.

[176] 8 from the above Morbi Copper-Plate. 4, 5, 7, 9, and 0, from "Asni Inscription of Mahipala," *The Indian Antiquary*, Vol. XVI, pp. 174-175; inscription is on red sandstone, date 917 A.D. See Bühler.

[177] 8, 9, 4, from "Rashtrakuta Grant of Amoghavarsha," J. F. Fleet, *The Indian Antiquary*, Vol. XII, pp. 263-272; copper-plate grant of date c. 972 A.D. See Bühler. 7, 3, 5, from "Torkhede Copper-Plate Grant of the Time of Govindaraja of Gujerat," Fleet, *Epigraphia Indica*, Vol. III, pp. 53-58. See Bühler.

[178] From "A Copper-Plate Grant of King Tritochanapâla Chanlukya of Lāṭadeśa," H.H. Dhruva, *Indian Antiquary*, Vol. XII, pp. 196-205; date 1050 A.D. See Bühler.

[179] Burnell, A. C., *South Indian Palæography*, plate XXIII, Telugu-Canarese numerals of the eleventh century. See Bühler.

[180] From a manuscript of the second half of the thirteenth century, reproduced in "Della vita e delle opere di Leonardo Pisano," Baldassare Boncompagni, Rome, 1852, in *Atti dell' Accademia Pontificia dei nuovi Lincei*, anno V.

[181] From a fourteenth-century manuscript, as reproduced in *Della vita etc.*, Boncompagni, loc. cit.

[182] From a Tibetan MS. in the library of D. E. Smith.

[183] From a Tibetan block-book in the library of D. E. Smith.

[184] Śāradā numerals from *The Kashmirian Atharva-Veda*, reproduced by chromophotography from the manuscript in the

University Library at Tübingen, Bloomfield and Garbe, Baltimore, 1901. Somewhat similar forms are given under "Numération Cachemirienne," by Pihan, *Exposé* etc., p. 84.

[185] Franz X. Kugler, *Die Babylonische Mondrechnung*, Freiburg i. Br., 1900, in the numerous plates at the end of the book; practically all of these contain the symbol to which reference is made. Cantor, *Geschichte*, Vol. I, p. 31.

[186] F. X. Kugler, *Sternkunde und Sterndienst in Babel*, I. Buch, from the beginnings to the time of Christ, Münster i. Westfalen, 1907. It also has numerous tables containing the above zero.

[187] From a letter to D. E. Smith, from G. F. Hill of the British Museum. See also his monograph "On the Early Use of Arabic Numerals in Europe," in *Archæologia*, Vol. LXII (1910), p. 137.

[188] R. Hoernle, "The Bakshālī Manuscript," *Indian Antiquary*, Vol. XVII, pp. 33-48 and 275-279, 1888; Thibaut, *Astronomie, Astrologie und Mathematik*, p. 75; Hoernle, *Verhandlungen*, loc. cit., p. 132.

[189] Bayley, loc. cit., Vol. XV, p. 29. Also Bendall, "On a System of Numerals used in South India," *Journal of the Royal Asiatic Society*, 1896, pp. 789-792.

[190] V. A. Smith, *The Early History of India*, 2d ed., Oxford, 1908, p. 14.

[191] Colebrooke, *Algebra, with Arithmetic and Mensuration, from the Sanskrit of Brahmagupta and Bhāscara*, London, 1817, pp. 339-340.

[192] Ibid., p. 138.

[193] D. E. Smith, in the *Bibliotheca Mathematica*, Vol. IX (3), pp. 106-110.

[194] As when we use three dots (...).

[195] "The Hindus call the nought explicitly *śūnyabindu* 'the dot marking a blank,' and about 500 A.D. they marked it by a simple dot, which latter is commonly used in inscriptions and MSS. in order to mark a blank, and which was later converted into a small circle." [Bühler, *On the Origin of the Indian Alphabet*, p. 53, note.]

[196] Fazzari, *Dell' origine delle parole zero e cifra*, Naples, 1903.

[197] E. Wappler, "Zur Geschichte der Mathematik im 15. Jahrhundert," in the *Zeitschrift für Mathematik und Physik*, Vol. XLV, *Hist.-lit. Abt.*, p. 47. The manuscript is No. C. 80, in the Dresden library.

[198] J. G. Prändel, *Algebra nebst ihrer literarischen Geschichte*, p. 572, Munich, 1795.

[199] See the table, p. 23. Does the fact that the early European arithmetics, following the Arab custom, always put the 0 after the 9, suggest that the 0 was derived from the old Hindu symbol for 10?

[200] Bayley, loc. cit., p. 48. From this fact Delambre (*Histoire de l'astronomie ancienne*) inferred that Ptolemy knew the zero, a theory accepted by Chasles, *Aperçu historique sur l'origine et le développement des méthodes en géométrie*, 1875 ed., p. 476; Nesselmann, however, showed (*Algebra der Griechen*, 1842, p. 138), that Ptolemy merely used O for οὐδὲν, with no notion of zero. See also G. Fazzari, "Dell' origine delle parole zero e cifra," *Ateneo*, Anno I, No. 11, reprinted at Naples in 1903, where the use of the point and the small cross for zero is also mentioned. Th. H. Martin, *Les signes numériques* etc., reprint p. 30, and J. Brandis, *Das Münz-, Mass- und Gewichtswesen in Vorderasien bis auf Alexander den Grossen*, Berlin, 1866, p. 10, also discuss this usage of O, without the notion of place value, by the Greeks.

[201] *Al-Battānī sive Albatēnii opus astronomicum*. Ad fidem codicis escurialensis arabice editum, latine versum,

adnotationibus instructum a Carolo Alphonso Nallino, 1899-1907. Pubblicazioni del R. Osservatorio di Brera in Milano, No. XL.

[202] Loc. cit., Vol. II, p. 271.

[203] C. Henry, "Prologus N. Ocreati in Helceph ad Adelardum Batensem magistrum suum," *Abhandlungen zur Geschichte der Mathematik*, Vol. III, 1880.

[204] Max. Curtze, "Ueber eine Algorismus-Schrift des XII. Jahrhunderts," *Abhandlungen zur Geschichte der Mathematik*, Vol. VIII, 1898, pp. 1-27; Alfred Nagl, "Ueber eine Algorismus-Schrift des XII. Jahrhunderts und über die Verbreitung der indisch-arabischen Rechenkunst und Zahlzeichen im christl. Abendlande," *Zeitschrift für Mathematik und Physik, Hist.-lit. Abth.*, Vol. XXXIV, pp. 129-146 and 161-170, with one plate.

[205] "Byzantinische Analekten," *Abhandlungen zur Geschichte der Mathematik*, Vol. IX, pp. 161-189.

[206] 𐤀 or 𐤁 for 0. 𐤀 also used for 5. | 𐤂 for 13. [Heiberg, loc. cit.]

[207] Gerhardt, *Études historiques sur l'arithmétique de position*, Berlin, 1856, p. 12; J. Bowring, *The Decimal System in Numbers, Coins, & Accounts*, London, 1854, p. 33.

[208] Karabacek, *Wiener Zeitschrift für die Kunde des Morgenlandes*, Vol. XI, p. 13; *Führer durch die Papyrus-Ausstellung Erzherzog Rainer*, Vienna, 1894, p. 216.

[209] In the library of G. A. Plimpton, Esq.

[210] Cantor, *Geschichte*, Vol. I (3), p. 674; Y. Mikami, "A Remark on the Chinese Mathematics in Cantor's *Geschichte der Mathematik*," *Archiv der Mathematik und Physik*, Vol. XV (3), pp. 68-70.

[211] Of course the earlier historians made innumerable guesses as to the origin of the word *cipher*. E.g. Matthew Hostus, *De numeratione emendata*, Antwerp, 1582, p. 10, says: "Siphra vox

Hebræam originem sapit refértque: & ut docti arbitrantur, à verbo saphar, quod Ordine numeravit significat. Unde Sephar numerus est: hinc Siphra (vulgo corruptius). Etsi verò gens Iudaica his notis, quæ hodie Siphrae vocantur, usa non fuit: mansit tamen rei appellatio apud multas gentes." Dasypodius, *Institutiones mathematicae*, Vol. I, 1593, gives a large part of this quotation word for word, without any mention of the source. Hermannus Hugo, *De prima scribendi origine*, Trajecti ad Rhenum, 1738, pp. 304-305, and note, p. 305; Karl Krumbacher, "Woher stammt das Wort Ziffer (Chiffre)?", *Études de philologie néo-grecque*, Paris, 1892.

[212] Bühler, loc. cit., p. 78 and p. 86.

[213] Fazzari, loc. cit., p. 4. So Elia Misrachi (1455-1526) in his posthumous *Book of Number*, Constantinople, 1534, explains *sifra* as being Arabic. See also Steinschneider, *Bibliotheca Mathematica*, 1893, p. 69, and G. Wertheim, *Die Arithmetik des Elia Misrachi*, Programm, Frankfurt, 1893.

[214] "Cum his novem figuris, et cum hoc signo 0, quod arabice zephirum appellatur, scribitur quilibet numerus."

[215] τζίφρα, a form also used by Neophytos (date unknown, probably c. 1330). It is curious that Finæus (1555 ed., f. 2) used the form *tziphra* throughout. A. J. H. Vincent ["Sur l'origine de nos chiffres," *Notices et Extraits des MSS.*, Paris, 1847, pp. 143-150] says: "Ce cercle fut nommé par les uns, *sipos*, *rota*, *galgal* ...; par les autres *tsiphra* (de צפר, *couronne* ou *diadème*) ou *ciphra* (de ספר, *numération*)." Ch. de Paravey, *Essai sur l'origine unique et hiéroglyphique des chiffres et des lettres de tous les peuples*, Paris, 1826, p. 165, a rather fanciful work, gives "vase, vase arrondi et fermé par un couvercle, qui est le symbole de la 10^e Heure, 𐍪," among the Chinese; also "Tsiphron Zéron, ou tout à fait vide en arabe, τζίφρα en grec ... d'où chiffre (qui dérive plutôt, suivant nous, de l'Hébreu *Sepher*, compter.)"

[216] "Compilatus a Magistro Jacobo de Florentia apud montem pesalanum," and described by G. Lami in his *Catalogus codicum*

manuscriptorum qui in bibliotheca Riccardiana Florentiæ adservantur. See Fazzari, loc. cit., p. 5.

[217] "Et doveto sapere chel zeuero per se solo non significa nulla ma è potentia di fare significare, ... Et decina o centinaia o migliaia non si puote scrivere senza questo segno 0. la quale si chiama zeuero." [Fazzari, loc. cit., p. 5.]

[218] Ibid., p. 6.

[219] Avicenna (980-1036), translation by Gasbarri et François, "più il punto (gli Arabi adoperavano il punto in vece dello zero il cui segno 0 in arabo si chiama *zepiro* donde il vocabolo zero), che per sè stesso non esprime nessun numero." This quotation is taken from D. C. Martines, *Origine e progressi dell' aritmetica*, Messina, 1865.

[220] Leo Jordan, "Materialien zur Geschichte der arabischen Zahlzeichen in Frankreich," *Archiv für Kulturgeschichte*, Berlin, 1905, pp. 155-195, gives the following two schemes of derivation, (1) "zefiro, zeviro, zeiro, zero," (2) "zefiro, zefro, zevro, zero."

[221] Köbel (1518 ed., f. A_4) speaks of the numerals in general as "die der gemain man Zyfer nendt." Recorde (*Grounde of Artes*, 1558 ed., f. B_6) says that the zero is "called priuatly a Cyphar, though all the other sometimes be likewise named."

[222] "Decimo X 0 theca, circulo⁹ cifra sive figura nihili appellat'." [*Enchiridion Algorismi*, Cologne, 1501.] Later, "quoniam de integris tam in cifris quam in proiectilibus,"—the word *proiectilibus* referring to markers "thrown" and used on an abacus, whence the French *jetons* and the English expression "to cast an account."

[223] "Decima vero o dicitur teca, circulus, vel cyfra vel figura nichili." [Maximilian Curtze, *Petri Philomeni de Dacia in Algorismum Vulgarem Johannis de Sacrobosco commentarius, una cum Algorismo ipso*, Copenhagen, 1897, p. 2.] Curtze cites five manuscripts (fourteenth and fifteenth centuries) of Dacia's

commentary in the libraries at Erfurt, Leipzig, and Salzburg, in addition to those given by Eneström, *Öfversigt af Kongl. Vetenskaps-Akademiens Förhandlingar*, 1885, pp. 15-27, 65-70; 1886, pp. 57-60.

[224] Curtze, loc. cit., p. vi.

[225] *Rara Mathematica*, London, 1841, chap. i, "Joannis de Sacro-Bosco Tractatus de Arte Numerandi."

[226] Smith, *Rara Arithmetica*, Boston, 1909.

[227] In the 1484 edition, Borghi uses the form "çefiro: ouero nulla:" while in the 1488 edition he uses "zefiro: ouero nulla," and in the 1540 edition, f. 3, appears "Chiamata zero, ouero nulla." Woepcke asserted that it first appeared in Calandri (1491) in this sentence: "Sono dieci le figure con le quali ciascuno numero si può significare: delle quali n'è una che si chiama zero: et per se sola nulla significa." (f. 4). [See *Propagation*, p. 522.]

[228] Boncompagni *Bulletino*, Vol. XVI, pp. 673-685.

[229] Leo Jordan, loc. cit. In the *Catalogue of MSS., Bibl. de l'Arsenal*, Vol. III, pp. 154-156, this work is No. 2904 (184 S.A.F.), Bibl. Nat., and is also called *Petit traicté de algorithme*.

[230] Texada (1546) says that there are "nueue letros yvn zero o cifra" (f. 3).

[231] Savonne (1563, 1751 ed., f. 1): "Vne ansi formee (o) qui s'appelle nulle, & entre marchans zero," showing the influence of Italian names on French mercantile customs. Trenchant (Lyons, 1566, 1578 ed., p. 12) also says: "La derniere qui s'apele nulle, ou zero;" but Champenois, his contemporary, writing in Paris in 1577 (although the work was not published until 1578), uses "cipher," the Italian influence showing itself less in this center of university culture than in the commercial atmosphere of Lyons.

[232] Thus Radulph of Laon (c. 1100): "Inscribitur in ultimo ordine et figura  sipos nomine, quae, licet numerum nullum

signitet, tantum ad alia quaedam utilis, ut insequentibus declarabitur." ["Der Arithmetische Tractat des Radulph von Laon," *Abhandlungen zur Geschichte der Mathematik*, Vol. V, p. 97, from a manuscript of the thirteenth century.] Chasles (*Comptes rendus*, t. 16, 1843, pp. 1393, 1408) calls attention to the fact that Radulph did not know how to use the zero, and he doubts if the sipos was really identical with it. Radulph says: "...figuram, cui sipos nomen est  in motum rotulae formatam nullius numeri significatione inscribi solere praediximus," and thereafter uses *rotula*. He uses the sipos simply as a kind of marker on the abacus.

[233] Rabbi ben Ezra (1092-1168) used both גלגל, *galgal* (the Hebrew for *wheel*), and ספרא, *sifra*. See M. Steinschneider, "Die Mathematik bei den Juden," in *Bibliotheca Mathematica*, 1893, p. 69, and Silberberg, *Das Buch der Zahl des R. Abraham ibn Esra*, Frankfurt a. M., 1895, p. 96, note 23; in this work the Hebrew letters are used for numerals with place value, having the zero.

[234] E.g., in the twelfth-century *Liber aligorismi* (see Boncompagni's *Trattati*, II, p. 28). So Ramus (*Libri II*, 1569 ed., p. 1) says: "Circulus quæ nota est ultima: nil per se significat." (See also the Schonerus ed. of Ramus, 1586, p. 1.)

[235] "Und wirt das ringlein o. die Ziffer genant die nichts bedeut." [Köbel's *Rechenbuch*, 1549 ed., f. 10, and other editions.]

[236] I.e. "circular figure," our word *notation* having come from the medieval *nota*. Thus Tzwivel (1507, f. 2) says: "Nota autem circularis .o. per se sumpta nihil vsus habet. alijs tamen adiuncta earum significantiam et auget et ordinem permutat quantum quo ponit ordinem. vt adiuncta note binarij hoc modo 20 facit eam significare bis decem etc." Also (ibid., f. 4), "figura circularis," "circularis nota." Clichtoveus (1503 ed., f. xxxvii) calls it "nota aut circularis o," "circularis nota," and "figura circularis." Tonstall (1522, f. B_3) says of it: "Decimo uero nota ad formam . litteræ circulari figura est: quam alij circulum, uulgo cyphram

uocat," and later (f. C_4) speaks of the "circulos." Grammateus, in his *Algorismus de integris* (Erfurt, 1523, f. A_2), speaking of the nine significant figures, remarks: "His autem superadditur decima figura circularis ut 0 existens que ratione sua nihil significat." Noviomagus (*De Numeris libri II*, Paris, 1539, chap. xvi, "De notis numerorum, quas zyphras vocant") calls it "circularis nota, quam ex his solam, alij sipheram, Georgius Valla zyphram."

[237] Huswirt, as above. Ramus (*Scholae mathematicae*, 1569 ed., p. 112) discusses the name interestingly, saying: "Circulum appellamus cum multis, quam alii thecam, alii figuram nihili, alii figuram privationis, seu figuram nullam vocant, alii ciphram, cū tamen hodie omnes hæ notæ vulgò ciphrae nomenclantur, & his notis numerare idem sit quod ciphrare." Tartaglia (1592 ed., f. 9) says: "si chiama da alcuni tecca, da alcuni circolo, da altri cifra, da altri zero, & da alcuni altri nulla."

[238] "Quare autem aliis nominibus vocetur, non dicit auctor, quia omnia alia nomina habent rationem suae lineationis sive figurationis. Quia rotunda est, dicitur haec figura teca ad similitudinem tecae. Teca enim est ferrum figurae rotundae, quod ignitum solet in quibusdam regionibus imprimi fronti vel maxillae furis seu latronum." [Loc. cit., p. 26.] But in Greek *theca* (ΘΗΚΗ,θήκη) is a place to put something, a receptacle. If a vacant column, e.g. in the abacus, was so called, the initial might have given the early forms  and  for the zero.

[239] Buteo, *Logistica*, Lyons, 1559. See also Wertheim in the *Bibliotheca Mathematica*, 1901, p. 214.

[240] "0 est appellee chiffre ou nulle ou figure de nulle valeur." [La Roche, *L'arithmétique*, Lyons, 1520.]

[241] "Decima autem figura nihil uocata," "figura nihili (quam etiam cifram uocant)." [Stifel, *Arithmetica integra*, 1544, f. 1.]

[242] "Zifra, & Nulla uel figura Nihili." [Scheubel, 1545, p. 1 of ch. 1.] *Nulla* is also used by Italian writers. Thus Sfortunati (1545

ed., f. 4) says: "et la decima nulla & e chiamata questa decima zero;" Cataldi (1602, p. 1): "La prima, che è o, si chiama nulla, ouero zero, ouero niente." It also found its way into the Dutch arithmetics, e.g. Raets (1576, 1580 ed., f. A_3): "Nullo dat ist niet;" Van der Schuere (1600, 1624 ed., f. 7); Wilkens (1669 ed., p. 1). In Germany Johann Albert (Wittenberg, 1534) and Rudolff (1526) both adopted the Italian *nulla* and popularized it. (See also Kuckuck, *Die Rechenkunst im sechzehnten Jahrhundert*, Berlin, 1874, p. 7; Günther, *Geschichte*, p. 316.)

[243] "La dixième s'appelle chiffre vulgairement: les vns l'appellant zero: nous la pourrons appeller vn Rien." [Peletier, 1607 ed., p. 14.]

[244] It appears in the Polish arithmetic of Kłos (1538) as *cyfra*. "The Ciphra 0 augmenteth places, but of himselfe signifieth not," Digges, 1579, p. 1. Hodder (10th ed., 1672, p. 2) uses only this word (cypher or cipher), and the same is true of the first native American arithmetic, written by Isaac Greenwood (1729, p. 1). Petrus de Dacia derives *cyfra* from circumference. "Vocatur etiam cyfra, quasi circumfacta vel circumferenda, quod idem est, quod circulus non habito respectu ad centrum." [Loc. cit., p. 26.]

[245] *Opera mathematica*, 1695, Oxford, Vol. I, chap. ix, *Mathesis universalis*, "De figuris numeralibus," pp. 46-49; Vol. II, *Algebra*, p. 10.

[246] Martin, *Origine de notre système de numération écrite*, note 149, p. 36 of reprint, spells τσίφρα from Maximus Planudes, citing Wallis as an authority. This is an error, for Wallis gives the correct form as above.

Alexander von Humboldt, "Über die bei verschiedenen Völkern üblichen Systeme von Zahlzeichen und über den Ursprung des Stellenwerthes in den indischen Zahlen," Crelle's *Journal für reine und angewandte Mathematik*, Vol. IV, 1829, called attention to the work ἀριθμοὶ Ἰνδικοί of the monk Neophytos, supposed to be of the fourteenth century. In this work the forms τζύφρα and τζύμφρα appear. See also Boeckh, *De abaco Graecorum*, Berlin,

1841, and Tannery, "Le Scholie du moine Néophytos," *Revue Archéologique*, 1885, pp. 99-102. Jordan, loc. cit., gives from twelfth and thirteenth century manuscripts the forms *cifra*, *ciffre*, *chifras*, and *cifrus*. Du Cange, *Glossarium mediae et infimae Latinitatis*, Paris, 1842, gives also *chilerae*. Dasypodius, *Institutiones Mathematicae*, Strassburg, 1593-1596, adds the forms *zyphra* and *syphra*. Boissière, *L'art d'arythmetique contenant toute dimention, tres-singulier et commode, tant pour l'art militaire que autres calculations*, Paris, 1554: "Puis y en a vn autre dict zero lequel ne designe nulle quantité par soy, ains seulement les loges vuides."

[247] *Propagation*, pp. 27, 234, 442. Treutlein, "Das Rechnen im 16. Jahrhundert," *Abhandlungen zur Geschichte der Mathematik*, Vol. I, p. 5, favors the same view. It is combated by many writers, e.g. A. C. Burnell, loc. cit., p. 59. Long before Woepcke, I. F. and G. I. Weidler, *De characteribus numerorum vulgaribus et eorum aetatibus*, Wittenberg, 1727, asserted the possibility of their introduction into Greece by Pythagoras or one of his followers: "Potuerunt autem ex oriente, uel ex phoenicia, ad graecos traduci, uel Pythagorae, uel eius discipulorum auxilio, cum aliquis eo, proficiendi in literis causa, iter faceret, et hoc quoque inuentum addisceret."

[248] E.g., they adopted the Greek numerals in use in Damascus and Syria, and the Coptic in Egypt. Theophanes (758-818 A.D.), *Chronographia*, *Scriptores Historiae Byzantinae*, Vol. XXXIX, Bonnae, 1839, p. 575, relates that in 699 A.D. the caliph Walīd forbade the use of the Greek language in the bookkeeping of the treasury of the caliphate, but permitted the use of the Greek alphabetic numerals, since the Arabs had no convenient number notation: καὶ ἐκώλυσε γράφεσθαι Ἑλληνιστὶ τοὺς δημοσίους τῶν λογοθεσίων κώδικας, ἀλλ' Ἀραβίοις αὐτὰ παρασημαίνεσθαι, χωρὶς τῶν ψήφων, ἐπειδὴ ἀδύνατον τῇ ἐκείνων γλώσσει μονάδα ἢ δυάδα ἢ τριάδα ἢ ὀκτὼ ἥμισυ ἢ τρία γράφεσθαι· διὸ καὶ ἕως σήμερόν εἰσιν σὺν αὐτοῖς νοτάριοι Χριστιανοί. The importance of this contemporaneous document was pointed out by Martin, loc. cit. Karabacek, "Die

Involutio im arabischen Schriftwesen," Vol. CXXXV of *Sitzungsberichte d. phil.-hist. Classe d. k. Akad. d. Wiss.*, Vienna, 1896, p. 25, gives an Arabic date of 868 A.D. in Greek letters.

[249] *The Origin and History of Our Numerals* (in Russian), Kiev, 1908; *The Independence of European Arithmetic* (in Russian), Kiev.

[250] Woepcke, loc. cit., pp. 462, 262.

[251] Woepcke, loc. cit., p. 240. *Hisāb-al-Ġobār*, by an anonymous author, probably Abū Sahl Dunash ibn Tamim, is given by Steinschneider, "Die Mathematik bei den Juden," *Bibliotheca Mathematica*, 1896, p. 26.

[252] Steinschneider in the *Abhandlungen*, Vol. III, p. 110.

[253] See his *Grammaire arabe*, Vol. I, Paris, 1810, plate VIII; Gerhardt, *Études*, pp. 9-11, and *Entstehung* etc., p. 8; I. F. Weidler, *Spicilegium observationum ad historiam notarum numeralium pertinentium*, Wittenberg, 1755, speaks of the "figura cifrarum Saracenicarum" as being different from that of the "characterum Boethianorum," which are similar to the "vulgar" or common numerals; see also Humboldt, loc. cit.

[254] Gerhardt mentions it in his *Entstehung* etc., p. 8; Woepcke, *Propagation*, states that these numerals were used not for calculation, but very much as we use Roman numerals. These superposed dots are found with both forms of numerals (*Propagation*, pp. 244-246).

[255] Gerhardt (*Études*, p. 9) from a manuscript in the Bibliothèque Nationale. The numeral forms are $\text{g}^{\cdot}\wedge^{\cdot}\vee^{\cdot}\psi^{\cdot}\circ^{\cdot}\varsigma^{\cdot}\mu^{\cdot}\iota^{\cdot}$, 20 being indicated by $\dot{\psi}$ and 200 by $\ddot{\psi}$. This scheme of zero dots was also adopted by the Byzantine Greeks, for a manuscript of Planudes in the Bibliothèque Nationale has numbers like $\text{π}^{\cdot}\alpha^{\cdot}$ for 8,100,000,000. See Gerhardt, *Études*, p. 19. Pihan, *Exposé* etc., p. 208, gives two forms, Asiatic and Maghrebian, of "Ghobār" numerals.

[256] See Chap. IV.

[257] Possibly as early as the third century A.D., but probably of the eighth or ninth. See Cantor, I (3), p. 598.

[258] Ascribed by the Arabic writer to India.

[259] See Woepcke's description of a manuscript in the Chasles library, "Recherches sur l'histoire des sciences mathématiques chez les orientaux," *Journal Asiatique*, IV (5), 1859, p. 358, note.

[260] P. 56.

[261] Reinaud, *Mémoire sur l'Inde*, p. 399. In the fourteenth century one Sihāb al-Dīn wrote a work on which, a scholiast to the Bodleian manuscript remarks: "The science is called Algobar because the inventor had the habit of writing the figures on a tablet covered with sand." [Gerhardt, *Études*, p. 11, note.]

[262] Gerhardt, *Entstehung* etc., p. 20.

[263] H. Suter, "Das Rechenbuch des Abū Zakarījā el-Ḥaṣṣār," *Bibliotheca Mathematica*, Vol. II (3), p. 15.

[264] A. Devoulx, "Les chiffres arabes," *Revue Africaine*, Vol. XVI, pp. 455-458.

[265] *Kitāb al-Fihrist*, G. Flügel, Leipzig, Vol. I, 1871, and Vol. II, 1872. This work was published after Professor Flügel's death by J. Roediger and A. Mueller. The first volume contains the Arabic text and the second volume contains critical notes upon it.

[266] Like those of line 5 in the illustration on page 69.

[267] Woepcke, *Recherches sur l'histoire des sciences mathématiques chez les orientaux*, loc. cit.; *Propagation*, p. 57.

[268] Al-Ḥaṣṣār's forms, Suter, *Bibliotheca Mathematica*, Vol. II (3), p. 15.

[269] Woepcke, *Sur une donnée historique*, etc., loc. cit. The name *ḡobār* is not used in the text. The manuscript from which

these are taken is the oldest (970 A.D.) Arabic document known to contain all of the numerals.

[270] Silvestre de Sacy, loc. cit. He gives the ordinary modern Arabic forms, calling them *Indien*.

[271] Woepcke, "Introduction au calcul Gobārī et Hawāī," *Atti dell' accademia pontificia dei nuovi Lincei*, Vol. XIX. The adjective applied to the forms in 5 is *gobārī* and to those in 6 *indienne*. This is the direct opposite of Woepcke's use of these adjectives in the *Recherches sur l'histoire* cited above, in which the ordinary Arabic forms (like those in row 5) are called *indiens*.

These forms are usually written from right to left.

[272] J. G. Wilkinson, *The Manners and Customs of the Ancient Egyptians*, revised by S. Birch, London, 1878, Vol. II, p. 493, plate XVI.

[273] There is an extensive literature on this "Boethius-Frage." The reader who cares to go fully into it should consult the various volumes of the *Jahrbuch über die Fortschritte der Mathematik*.

[274] This title was first applied to Roman emperors in posthumous coins of Julius Cæsar. Subsequently the emperors assumed it during their own lifetimes, thus deifying themselves. See F. Gnechi, *Monete romane*, 2d ed., Milan, 1900, p. 299.

[275] This is the common spelling of the name, although the more correct Latin form is Boëtius. See Harper's *Dict. of Class. Lit. and Antiq.*, New York, 1897, Vol. I, p. 213. There is much uncertainty as to his life. A good summary of the evidence is given in the last two editions of the *Encyclopædia Britannica*.

[276] His father, Flavius Manlius Boethius, was consul in 487.

[277] There is, however, no good historic evidence of this sojourn in Athens.

[278] His arithmetic is dedicated to Symmachus: "Domino suo patricio Symmacho Boetius." [Friedlein ed., p. 3.]

[279] It was while here that he wrote *De consolatione philosophiae*.

[280] It is sometimes given as 525.

[281] There was a medieval tradition that he was executed because of a work on the Trinity.

[282] Hence the *Divus* in his name.

[283] Thus Dante, speaking of his burial place in the monastery of St. Pietro in Ciel d'Oro, at Pavia, says:

"The saintly soul, that shows
The world's deceitfulness, to all who hear him,
Is, with the sight of all the good that is,
Blest there. The limbs, whence it was driven, lie
Down in Cieldauro; and from martyrdom
And exile came it here."—*Paradiso*, Canto X.

[284] Not, however, in the mercantile schools. The arithmetic of Boethius would have been about the last book to be thought of in such institutions. While referred to by Bæda (672-735) and Hrabanus Maurus (c. 776-856), it was only after Gerbert's time that the *Boëtii de institutione arithmetica libri duo* was really a common work.

[285] Also spelled Cassiodorius.

[286] As a matter of fact, Boethius could not have translated any work by Pythagoras on music, because there was no such work, but he did make the theories of the Pythagoreans known. Neither did he translate Nicomachus, although he embodied many of the ideas of the Greek writer in his own arithmetic. Gibbon follows Cassiodorus in these statements in his *Decline and Fall of the Roman Empire*, chap. xxxix. Martin pointed out with positiveness the similarity of the first book of Boethius to the first five books of Nicomachus. [*Les signes numériques* etc., reprint, p. 4.]

[287] The general idea goes back to Pythagoras, however.

[288] J. C. Scaliger in his *Poëtice* also said of him: "Boethii Severini ingenium, eruditio, ars, sapientia facile provocat omnes auctores, sive illi Graeci sint, sive Latini" [Heilbronner, *Hist. math. univ.*, p. 387]. Libri, speaking of the time of Boethius, remarks: "Nous voyons du temps de Théodoric, les lettres reprendre une nouvelle vie en Italie, les écoles florissantes et les savans honorés. Et certes les ouvrages de Boèce, de Cassiodore, de Symmaque, surpassent de beaucoup toutes les productions du siècle précédent." [*Histoire des mathématiques*, Vol. I, p. 78.]

[289] Carra de Vaux, *Avicenne*, Paris, 1900; Woepcke, *Sur l'introduction*, etc.; Gerhardt, *Entstehung* etc., p. 20. Avicenna is a corruption from Ibn Sīnā, as pointed out by Wüstenfeld, *Geschichte der arabischen Aerzte und Naturforscher*, Göttingen, 1840. His full name is Abū 'Alī al-Ḥosein ibn Sīnā. For notes on Avicenna's arithmetic, see Woepcke, *Propagation*, p. 502.

[290] On the early travel between the East and the West the following works may be consulted: A. Hillebrandt, *Alt-Indien*, containing "Chinesische Reisende in Indien," Breslau, 1899, p. 179; C. A. Skeel, *Travel in the First Century after Christ*, Cambridge, 1901, p. 142; M. Reinaud, "Relations politiques et commerciales de l'empire romain avec l'Asie orientale," in the *Journal Asiatique*, Mars-Avril, 1863, Vol. I (6), p. 93; Beazley, *Dawn of Modern Geography, a History of Exploration and Geographical Science from the Conversion of the Roman Empire to A.D. 1420*, London, 1897-1906, 3 vols.; Heyd, *Geschichte des Levanthandels im Mittelalter*, Stuttgart, 1897; J. Keane, *The Evolution of Geography*, London, 1899, p. 38; A. Cunningham, *Corpus inscriptionum Indicarum*, Calcutta, 1877, Vol. I; A. Neander, *General History of the Christian Religion and Church*, 5th American ed., Boston, 1855, Vol. III, p. 89; R. C. Dutt, *A History of Civilization in Ancient India*, Vol. II, Bk. V, chap. ii; E. C. Bayley, loc. cit., p. 28 et seq.; A. C. Burnell, loc. cit., p. 3; J. E. Tennent, *Ceylon*, London, 1859, Vol. I, p. 159; Geo. Turnour, *Epitome of the History of Ceylon*, London, n.d., preface; "Philalethes," *History of Ceylon*, London, 1816, chap. i; H. C. Sirr, *Ceylon and the Cingalese*, London, 1850, Vol. I, chap. ix. On

the Hindu knowledge of the Nile see F. Wilford, *Asiatick Researches*, Vol. III, p. 295, Calcutta, 1792.

[291] G. Oppert, *On the Ancient Commerce of India*, Madras, 1879, p. 8.

[292] Gerhardt, *Études* etc., pp. 8, 11.

[293] See Smith's *Dictionary of Greek and Roman Biography and Mythology*.

[294] P. M. Sykes, *Ten Thousand Miles in Persia, or Eight Years in Irán*, London, 1902, p. 167. Sykes was the first European to follow the course of Alexander's army across eastern Persia.

[295] Bühler, *Indian Brāhma Alphabet*, note, p. 27; *Palaeographie*, p. 2; *Herodoti Halicarnassei historia*, Amsterdam, 1763, Bk. IV, p. 300; Isaac Vossius, *Periplus Scylacis Caryandensis*, 1639. It is doubtful whether the work attributed to Scylax was written by him, but in any case the work dates back to the fourth century B.C. See Smith's *Dictionary of Greek and Roman Biography*.

[296] Herodotus, Bk. III.

[297] Rameses II(?), the Sesoosis of Diodorus Siculus.

[298] *Indian Antiquary*, Vol. I, p. 229; F. B. Jevons, *Manual of Greek Antiquities*, London, 1895, p. 386. On the relations, political and commercial, between India and Egypt c. 72 B.C., under Ptolemy Auletes, see the *Journal Asiatique*, 1863, p. 297.

[299] Sikandar, as the name still remains in northern India.

[300] *Harper's Classical Dict.*, New York, 1897, Vol. I, p. 724; F. B. Jevons, loc. cit., p. 389; J. C. Marshman, *Abridgment of the History of India*, chaps. i and ii.

[301] Oppert, loc. cit., p. 11. It was at or near this place that the first great Indian mathematician, Āryabhaṭa, was born in 476 A.D.

[302] Bühler, *Palaeographie*, p. 2, speaks of Greek coins of a period anterior to Alexander, found in northern India. More complete information may be found in *Indian Coins*, by E. J. Rapson, Strassburg, 1898, pp. 3-7.

[303] Oppert, loc. cit., p. 14; and to him is due other similar information.

[304] J. Beloch, *Griechische Geschichte*, Vol. III, Strassburg, 1904, pp. 30-31.

[305] E.g., the denarius, the words for hour and minute (ὥρα, λεπτόν), and possibly the signs of the zodiac. [R. Caldwell, *Comparative Grammar of the Dravidian Languages*, London, 1856, p. 438.] On the probable Chinese origin of the zodiac see Schlegel, loc. cit.

[306] Marie, Vol. II, p. 73; R. Caldwell, loc. cit.

[307] A. Cunningham, loc. cit., p. 50.

[308] C. A. J. Skeel, *Travel*, loc. cit., p. 14.

[309] *Inchiver*, from *inchi*, "the green root." [*Indian Antiquary*, Vol. I, p. 352.]

[310] In China dating only from the second century A.D., however.

[311] The Italian *morra*.

[312] J. Bowring, *The Decimal System*, London, 1854, p. 2.

[313] H. A. Giles, lecture at Columbia University, March 12, 1902, on "China and Ancient Greece."

[314] Giles, loc. cit.

[315] E.g., the names for grape, radish (*la-po*, ῥάφη), water-lily (*si-kua*, "west gourds"; σικύα, "gourds"), are much alike. [Giles, loc. cit.]

[316] *Epistles*, I, 1, 45-46. On the Roman trade routes, see Beazley, loc. cit., Vol. I, p. 179.

[317] *Am. Journ. of Archeol.*, Vol. IV, p. 366.

[318] M. Perrot gives this conjectural restoration of his words: "Ad me ex India regum legationes saepe missi sunt numquam antea visae apud quemquam principem Romanorum." [M. Reinaud, "Relations politiques et commerciales de l'empire romain avec l'Asie orientale," *Journ. Asiat.*, Vol. I (6), p. 93.]

[319] Reinaud, loc. cit., p. 189. Florus, II, 34 (IV, 12), refers to it: "Seres etiam habitantesque sub ipso sole Indi, cum gemmis et margaritis elephantes quoque inter munera trahentes nihil magis quam longinquitatem viae imputabant." Horace shows his geographical knowledge by saying: "Not those who drink of the deep Danube shall now break the Julian edicts; not the Getae, not the Seres, nor the perfidious Persians, nor those born on the river Tanais." [*Odes*, Bk. IV, Ode 15, 21-24.]

[320] "Qua virtutis moderationisque fama Indos etiam ac Scythas auditu modo cognitos pellexit ad amicitiam suam populi Romani ultro per legatos petendam." [Reinaud, loc. cit., p. 180.]

[321] Reinaud, loc. cit., p. 180.

[322] *Georgics*, II, 170-172. So Propertius (*Elegies*, III, 4):

Arma deus Caesar dices meditatur ad Indos
Et freta gemmiferi findere classe maris.

"The divine Cæsar meditated carrying arms against opulent India, and with his ships to cut the gem-bearing seas."

[323] Heyd, loc. cit., Vol. I, p. 4.

[324] Reinaud, loc. cit., p. 393.

[325] The title page of Calandri (1491), for example, represents Pythagoras with these numerals before him. [Smith, *Rara*

Arithmetica, p. 46.] Isaacus Vossius, *Observationes ad Pomponium Melam de situ orbis*, 1658, maintained that the Arabs derived these numerals from the west. A learned dissertation to this effect, but deriving them from the Romans instead of the Greeks, was written by Ginanni in 1753 (*Dissertatio mathematica critica de numeralium notarum minuscularum origine*, Venice, 1753). See also Mannert, *De numerorum quos arabicos vocant vera origine Pythagorica*, Nürnberg, 1801. Even as late as 1827 Romagnosi (in his supplement to *Ricerche storiche sull' India* etc., by Robertson, Vol. II, p. 580, 1827) asserted that Pythagoras originated them. [R. Bombelli, *L'antica numerazione italica*, Rome, 1876, p. 59.] Gow (*Hist. of Greek Math.*, p. 98) thinks that Iamblichus must have known a similar system in order to have worked out certain of his theorems, but this is an unwarranted deduction from the passage given.

[326] A. Hillebrandt, *Alt-Indien*, p. 179.

[327] J. C. Marshman, loc. cit., chaps. i and ii.

[328] He reigned 631-579 A.D.; called Nuśīrwān, *the holy one*.

[329] J. Keane, *The Evolution of Geography*, London, 1899, p. 38.

[330] The Arabs who lived in and about Mecca.

[331] S. Guyard, in *Encyc. Brit.*, 9th ed., Vol. XVI, p. 597.

[332] Oppert, loc. cit., p. 29.

[333] "At non credendum est id in Autographis contigisse, aut vetustioribus Codd. MSS." [Wallis, *Opera omnia*, Vol. II, p. 11.]

[334] In *Observationes ad Pomponium Melam de situ orbis*. The question was next taken up in a large way by Weidler, loc. cit., *De characteribus* etc., 1727, and in *Spicilegium* etc., 1755.

[335] The best edition of these works is that of G. Friedlein, *Anicii Manlii Torquati Severini Boetii de institutione arithmetica*

libri duo, de institutione musica libri quinque. Accedit geometria quae fertur Boetii.... Leipzig.... MDCCCLXVII.

[336] See also P. Tannery, "Notes sur la pseudo-géométrie de Boèce," in *Bibliotheca Mathematica*, Vol. I (3), p. 39. This is not the geometry in two books in which are mentioned the numerals. There is a manuscript of this pseudo-geometry of the ninth century, but the earliest one of the other work is of the eleventh century (Tannery), unless the Vatican codex is of the tenth century as Friedlein (p. 372) asserts.

[337] Friedlein feels that it is partly spurious, but he says: "Eorum librorum, quos Boetius de geometria scripsisse dicitur, investigare veram inscriptionem nihil aliud esset nisi operam et tempus perdere." [Preface, p. v.] N. Bubnov in the *Russian Journal of the Ministry of Public Instruction*, 1907, in an article of which a synopsis is given in the *Jahrbuch über die Fortschritte der Mathematik* for 1907, asserts that the geometry was written in the eleventh century.

[338] The most noteworthy of these was for a long time Cantor (*Geschichte*, Vol. I., 3d ed., pp. 587-588), who in his earlier days even believed that Pythagoras had known them. Cantor says (*Die römischen Agrimensoren*, Leipzig, 1875, p. 130): "Uns also, wir wiederholen es, ist die Geometrie des Boetius echt, dieselbe Schrift, welche er nach Euklid bearbeitete, von welcher ein Codex bereits in Jahre 821 im Kloster Reichenau vorhanden war, von welcher ein anderes Exemplar im Jahre 982 zu Mantua in die Hände Gerbert's gelangte, von welcher mannigfache Handschriften noch heute vorhanden sind." But against this opinion of the antiquity of MSS. containing these numerals is the important statement of P. Tannery, perhaps the most critical of modern historians of mathematics, that none exists earlier than the eleventh century. See also J. L. Heiberg in *Philologus, Zeitschrift f. d. klass. Altertum*, Vol. XLIII, p. 508.

Of Cantor's predecessors, Th. H. Martin was one of the most prominent, his argument for authenticity appearing in the *Revue*

Archéologique for 1856-1857, and in his treatise *Les signes numéraux* etc. See also M. Chasles, "De la connaissance qu'ont eu les anciens d'une numération décimale écrite qui fait usage de neuf chiffres prenant les valeurs de position," *Comptes rendus*, Vol. VI, pp. 678-680; "Sur l'origine de notre système de numération," *Comptes rendus*, Vol. VIII, pp. 72-81; and note "Sur le passage du premier livre de la géométrie de Boèce, relatif à un nouveau système de numération," in his work *Aperçu historique sur l'origine et le développement des méthodes en géométrie*, of which the first edition appeared in 1837.

[339] J. L. Heiberg places the book in the eleventh century on philological grounds, *Philologus*, loc. cit.; Woepcke, in *Propagation*, p. 44; Blume, Lachmann, and Rudorff, *Die Schriften der römischen Feldmesser*, Berlin, 1848; Boeckh, *De abaco graecorum*, Berlin, 1841; Friedlein, in his Leipzig edition of 1867; Weissenborn, *Abhandlungen*, Vol. II, p. 185, his *Gerbert*, pp. 1, 247, and his *Geschichte der Einführung der jetzigen Ziffern in Europa durch Gerbert*, Berlin, 1892, p. 11; Bayley, loc. cit., p. 59; Gerhardt, *Études*, p. 17, *Entstehung und Ausbreitung*, p. 14; Nagl, *Gerbert*, p. 57; Bubnov, loc. cit. See also the discussion by Chasles, Halliwell, and Libri, in the *Comptes rendus*, 1839, Vol. IX, p. 447, and in Vols. VIII, XVI, XVII of the same journal.

[340] J. Marquardt, *La vie privée des Romains*, Vol. II (French trans.), p. 505, Paris, 1893.

[341] In a Plimpton manuscript of the arithmetic of Boethius of the thirteenth century, for example, the Roman numerals are all replaced by the Arabic, and the same is true in the first printed edition of the book. (See Smith's *Rara Arithmetica*, pp. 434, 25-27.) D. E. Smith also copied from a manuscript of the arithmetic in the Laurentian library at Florence, of 1370, the following forms, **1 2 3 4 5 6 7 8 9 0** which, of course, are interpolations. An interesting example of a forgery in ecclesiastical matters is in the charter said to have been given by St. Patrick, granting indulgences to the benefactors of Glastonbury, dated "In nomine domini nostri Jhesu Christi Ego

Patricius humilis servunculus Dei anno incarnationis ejusdem ccccxix." Now if the Benedictines are right in saying that Dionysius Exiguus, a Scythian monk, first arranged the Christian chronology c. 532 A.D., this can hardly be other than spurious. See Arbuthnot, loc. cit., p. 38.

[342] Halliwell, in his *Rara Mathematica*, p. 107, states that the disputed passage is not in a manuscript belonging to Mr. Ames, nor in one at Trinity College. See also Woepcke, in *Propagation*, pp. 37 and 42. It was the evident corruption of the texts in such editions of Boethius as those of Venice, 1499, Basel, 1546 and 1570, that led Woepcke to publish his work *Sur l'introduction de l'arithmétique indienne en Occident*.

[343] They are found in none of the very ancient manuscripts, as, for example, in the ninth-century (?) codex in the Laurentian library which one of the authors has examined. It should be said, however, that the disputed passage was written after the arithmetic, for it contains a reference to that work. See the Friedlein ed., p. 397.

[344] Smith, *Rara Arithmetica*, p. 66.

[345] J. L. Heiberg, *Philologus*, Vol. XLIII, p. 507.

[346] "Nosse autem huius artis dispicientem, quid sint digiti, quid articuli, quid compositi, quid incompositi numeri." [Friedlein ed., p. 395.]

[347] *De ratione abaci*. In this he describes "quandam formulam, quam ob honorem sui praeceptoris mensam Pythagoream nominabant ... a posterioribus appellabatur abacus." This, as pictured in the text, is the common Gerbert abacus. In the edition in Migne's *Patrologia Latina*, Vol. LXIII, an ordinary multiplication table (sometimes called Pythagorean abacus) is given in the illustration.

[348] "Habebant enim diverse formatos apices vel characteres." See the reference to Gerbert on p. 117.

[349] C. Henry, "Sur l'origine de quelques notations mathématiques," *Revue Archéologique*, 1879, derives these from the initial letters used as abbreviations for the names of the numerals, a theory that finds few supporters.

[350] E.g., it appears in Schonerus, *Algorithmus Demonstratus*, Nürnberg, 1534, f. A4. In England it appeared in the earliest English arithmetical manuscript known, *The Crafte of Nombrynge*: "¶ fforthermore ye most vndirstonde that in this craft ben vsid teen figurys, as here bene writen for ensampul, **⁊ 9 8 7 6 5 4 3 2 1** ... in the quych we vse teen figurys of Inde. Questio. ¶ why ten fyguris of Inde? Solucio. for as I have sayd afore thei were fonde fyrst in Inde of a kynge of that Cuntre, that was called Algor." See Smith, *An Early English Algorism*, loc. cit.

[351] Friedlein ed., p. 397.

[352] Carlsruhe codex of Gerlando.

[353] Munich codex of Gerlando.

[354] Carlsruhe codex of Bernelinus.

[355] Munich codex of Bernelinus.

[356] Turchill, c. 1200.

[357] Anon. MS., thirteenth century, Alexandrian Library, Rome.

[358] Twelfth-century Boethius, Friedlein, p. 396.

[359] Vatican codex, tenth century, Boethius.

[360] a, h, i, are from the Friedlein ed.; the original in the manuscript from which a is taken contains a zero symbol, as do all of the six plates given by Friedlein. b-e from the Boncompagni *Bulletino*, Vol. X, p. 596; f *ibid.*, Vol. XV, p. 186; g *Memorie della classe di sci., Reale Acc. dei Lincei*, An. CCLXXIV (1876-1877), April, 1877. A twelfth-century arithmetician, possibly John of Luna (Hispalensis, of Seville, c. 1150), speaks of the great diversity of these forms even in his day, saying: "Est autem in

aliquibus figuram istarum apud multos diuersitas. Quidam enim septimam hanc figuram representant .۹. alii autem sic .۷. uel sic ۱. Quidam vero quartam sic ۵." [Boncompagni, *Trattati*, Vol. II, p. 28.]

[361] Loc. cit., p. 59.

[362] Ibid., p. 101.

[363] Loc. cit., p. 396.

[364] Khosrū I, who began to reign in 531 A.D. See W. S. W Vaux, *Persia*, London, 1875, p. 169; Th. Nöldeke, *Aufsätze zur persischen Geschichte*, Leipzig, 1887, p. 113, and his article in the ninth edition of the *Encyclopædia Britannica*.

[365] Colebrooke, *Essays*, Vol. II, p. 504, on the authority of Ibn al-Adamī, astronomer, in a work published by his continuator Al-Qāsim in 920 A.D.; Al-Bīrūnī, *India*, Vol. II, p. 15.

[366] H. Suter, *Die Mathematiker* etc., pp. 4-5, states that Al-Fazārī died between 796 and 806.

[367] Suter, loc. cit., p. 63.

[368] Suter, loc. cit., p. 74.

[369] Suter, *Das Mathematiker-Verzeichniss im Fihrist*. The references to Suter, unless otherwise stated, are to his later work *Die Mathematiker und Astronomen der Araber* etc.

[370] Suter, *Fihrist*, p. 37, no date.

[371] Suter, *Fihrist*, p. 38, no date.

[372] Possibly late tenth, since he refers to one arithmetical work which is entitled *Book of the Cyphers* in his *Chronology*, English ed., p. 132. Suter, *Die Mathematiker* etc., pp. 98-100, does not mention this work; see the *Nachträge und Berichtigungen*, pp. 170-172.

- [373] Suter, pp. 96-97.
- [374] Suter, p. 111.
- [375] Suter, p. 124. As the name shows, he came from the West.
- [376] Suter, p. 138.
- [377] Hankel, *Zur Geschichte der Mathematik*, p. 256, refers to him as writing on the Hindu art of reckoning; Suter, p. 162.
- [378] Ψηφοφορία κατ' Ἰνδούς, Greek ed., C. I. Gerhardt, Halle, 1865; and German translation, *Das Rechenbuch des Maximus Planudes*, H. Wäschke, Halle, 1878.
- [379] "Sur une donnée historique relative à l'emploi des chiffres indiens par les Arabes," Tortolini's *Annali di scienze mat. e fis.*, 1855.
- [380] Suter, p. 80.
- [381] Suter, p. 68.
- [382] Sprenger also calls attention to this fact, in the *Zeitschrift d. deutschen morgenländ. Gesellschaft*, Vol. XLV, p. 367.
- [383] Libri, *Histoire des mathématiques*, Vol. I, p. 147.
- [384] "Dictant la paix à l'empereur de Constantinople, l'Arabe victorieux demandait des manuscrits et des savans." [Libri, loc. cit., p. 108.]
- [385] Persian *bagadata*, "God-given."
- [386] One of the Abbassides, the (at least pretended) descendants of 'Al-Abbās, uncle and adviser of Moḥammed.
- [387] E. Reclus, *Asia*, American ed., N. Y., 1891, Vol. IV, p. 227.
- [388] *Historical Sketches*, Vol. III, chap. iii.
- [389] On its prominence at that period see Villicus, p. 70.

[390] See pp. 4-5.

[391] Smith, D. E., in the *Cantor Festschrift*, 1909, note pp. 10-11. See also F. Woepcke, *Propagation*.

[392] Eneström, in *Bibliotheca Mathematica*, Vol. I (3), p. 499; Cantor, *Geschichte*, Vol. I (3), p. 671.

[393] Cited in Chapter I. It begins: "Dixit algoritmi: laudes deo rectori nostro atque defensori dicamus dignas." It is devoted entirely to the fundamental operations and contains no applications.

[394] M. Steinschneider, "Die Mathematik bei den Juden," *Bibliotheca Mathematica*, Vol. VIII (2), p. 99. See also the reference to this writer in Chapter I.

[395] Part of this work has been translated from a Leyden MS. by F. Woepcke, *Propagation*, and more recently by H. Suter, *Bibliotheca Mathematica*, Vol. VII (3), pp. 113-119.

[396] A. Neander, *General History of the Christian Religion and Church*, 5th American ed., Boston, 1855, Vol. III, p. 335.

[397] Beazley, loc. cit., Vol. I, p. 49.

[398] Beazley, loc. cit., Vol. I, pp. 50, 460.

[399] See pp. 7-8.

[400] The name also appears as Moḥammed Abū'l-Qāsim, and Ibn Hauqal. Beazley, loc. cit., Vol. I, p. 45.

[401] *Kitāb al-masālik wa'l-mamālik*.

[402] Reinaud, *Mém. sur l'Inde*; in Gerhardt, *Études*, p. 18.

[403] Born at Shiraz in 1193. He himself had traveled from India to Europe.

[404] *Gulistan (Rose Garden)*, Gateway the third, XXII. Sir Edwin Arnold's translation, N. Y., 1899, p. 177.

[405] Cunningham, loc. cit., p. 81.

[406] Putnam, *Books*, Vol. I, p. 227:

"Non semel externas peregrino tramite terras
Jam peragravit ovans, sophiae deductus amore,
Si quid forte novi librorum seu studiorum
Quod secum ferret, terris reperiret in illis.
Hic quoque Romuleum venit devotus ad urbem."

("More than once he has traveled joyfully through remote regions and by strange roads, led on by his zeal for knowledge and seeking to discover in foreign lands novelties in books or in studies which he could take back with him. And this zealous student journeyed to the city of Romulus.")

[407] A. Neander, *General History of the Christian Religion and Church*, 5th American ed., Boston, 1855, Vol. III, p. 89, note 4; Libri, *Histoire*, Vol. I, p. 143.

[408] Cunningham, loc. cit., p. 81.

[409] Heyd, loc. cit., Vol. I, p. 4.

[410] Ibid., p. 5.

[411] Ibid., p. 21.

[412] Ibid., p. 23.

[413] Libri, *Histoire*, Vol. I, p. 167.

[414] Picavet, *Gerbert, un pape philosophe, d'après l'histoire et d'après la légende*, Paris, 1897, p. 19.

[415] Beazley, loc. cit., Vol. I, chap, i, and p. 54 seq.

[416] Ibid., p. 57.

[417] Libri, *Histoire*, Vol. I, p. 110, n., citing authorities, and p. 152.

[418] Possibly the old tradition, "Prima dedit nautis usum magnetis Amalphis," is true so far as it means the modern form of compass card. See Beazley, loc. cit., Vol. II, p. 398.

[419] R. C. Dutt, loc. cit., Vol. II, p. 312.

[420] E. J. Payne, in *The Cambridge Modern History*, London, 1902, Vol. I, chap. i.

[421] Geo. Phillips, "The Identity of Marco Polo's Zaitun with Changchau, in T'oung pao," *Archives pour servir à l'étude de l'histoire de l'Asie orientale*, Leyden, 1890, Vol. I, p. 218. W. Heyd, *Geschichte des Levanthandels im Mittelalter*, Vol. II, p. 216.

The Palazzo dei Poli, where Marco was born and died, still stands in the Corte del Milione, in Venice. The best description of the Polo travels, and of other travels of the later Middle Ages, is found in C. R. Beazley's *Dawn of Modern Geography*, Vol. III, chap. ii, and Part II.

[422] Heyd, loc. cit., Vol. II, p. 220; H. Yule, in *Encyclopædia Britannica*, 9th (10th) or 11th ed., article "China." The handbook cited is Pegolotti's *Libro di divisamenti di paesi*, chapters i-ii, where it is implied that \$60,000 would be a likely amount for a merchant going to China to invest in his trip.

[423] Cunningham, loc. cit., p. 194.

[424] I.e. a commission house.

[425] Cunningham, loc. cit., p. 186.

[426] J. R. Green, *Short History of the English People*, New York, 1890, p. 66.

[427] W. Besant, *London*, New York, 1892, p. 43.

[428] *Baldakin, baldekin, baldachino*.

[429] Italian *Baldacco*.

[430] J. K. Mumford, *Oriental Rugs*, New York, 1901, p. 18.

[431] Or Girbert, the Latin forms *Gerbertus* and *Girbertus* appearing indifferently in the documents of his time.

[432] See, for example, J. C. Heilbronner, *Historia matheseos universæ*, p. 740.

[433] "Obscuro loco natum," as an old chronicle of Aurillac has it.

[434] N. Bubnov, *Gerberti postea Silvestri II papae opera mathematica*, Berlin, 1899, is the most complete and reliable source of information; Picavet, loc. cit., *Gerbert* etc.; Olleris, *Œuvres de Gerbert*, Paris, 1867; Havet, *Lettres de Gerbert*, Paris, 1889 ; H. Weissenborn, *Gerbert; Beiträge zur Kenntniss der Mathematik des Mittelalters*, Berlin, 1888, and *Zur Geschichte der Einführung der jetzigen Ziffern in Europa durch Gerbert*, Berlin, 1892; Büdinger, *Ueber Gerberts wissenschaftliche und politische Stellung*, Cassel, 1851; Richer, "Historiarum liber III," in Bubnov, loc. cit., pp. 376-381; Nagl, *Gerbert und die Rechenkunst des 10. Jahrhunderts*, Vienna, 1888.

[435] Richer tells of the visit to Aurillac by Borel, a Spanish nobleman, just as Gerbert was entering into young manhood. He relates how affectionately the abbot received him, asking if there were men in Spain well versed in the arts. Upon Borel's reply in the affirmative, the abbot asked that one of his young men might accompany him upon his return, that he might carry on his studies there.

[436] Vicus Ausona. Hatto also appears as Atton and Hatton.

[437] This is all that we know of his sojourn in Spain, and this comes from his pupil Richer. The stories told by Adhemar of Chabanois, an apparently ignorant and certainly untrustworthy contemporary, of his going to Cordova, are unsupported. (See e.g. Picavet, p. 34.) Nevertheless this testimony is still accepted: K. von Raumer, for example (*Geschichte der Pädagogik*, 6th ed., 1890, Vol. I, p. 6), says "Mathematik studierte man im Mittelalter

bei den Arabern in Spanien. Zu ihnen gieng Gerbert, nachmaliger Pabst Sylvester II."

[438] Thus in a letter to Aldaberon he says: "Quos post repperimus speretis, id est VIII volumina Boeti de astrologia, praeclarissima quoque figurarum geometriæ, aliaque non minus admiranda" (Epist. 8). Also in a letter to Rainard (Epist. 130), he says: "Ex tuis sumptibus fac ut michi scribantur M. Manlius (Manilius in one MS.) de astrologia."

[439] Picavet, loc. cit., p. 31.

[440] Picavet, loc. cit., p. 36.

[441] Havet, loc. cit., p. vii.

[442] Picavet, loc. cit., p. 37.

[443] "Con sinistre arti conseguri la dignita del Pontificato.... Lasciato poi l' abito, e 'l monasterio, e datosi tutto in potere del diavolo." [Quoted in Bombelli, *L'antica numerazione Italica*, Rome, 1876, p. 41 n.]

[444] He writes from Rheims in 984 to one Lupitus, in Barcelona, saying: "Itaque librum de astrologia translatum a te michi petenti dirige," presumably referring to some Arabic treatise. [Epist. no. 24 of the Havet collection, p. 19.]

[445] See Bubnov, loc. cit., p. x.

[446] Olleris, loc. cit., p. 361, l. 15, for Bernelinus; and Bubnov, loc. cit., p. 381, l. 4, for Richer.

[447] Woepcke found this in a Paris MS. of Radulph of Laon, c. 1100. [*Propagation*, p. 246.] "Et prima quidem trium spaciorum superductio unitatis caractere inscribitur, qui chaldeo nomine dicitur igin." See also Alfred Nagl, "Der arithmetische Tractat des Radulph von Laon" (*Abhandlungen zur Geschichte der Mathematik*, Vol. V, pp. 85-133), p. 97.

[448] Weissenborn, loc. cit., p. 239. When Olleris (*Œuvres de Gerbert*, Paris, 1867, p. cci) says, "C'est à lui et non point aux Arabes, que l'Europe doit son système et ses signes de numération," he exaggerates, since the evidence is all against his knowing the place value. Friedlein emphasizes this in the *Zeitschrift für Mathematik und Physik*, Vol. XII (1867), *Literaturzeitung*, p. 70: "Für das System unserer Numeration ist die Null das wesentlichste Merkmal, und diese kannte Gerbert nicht. Er selbst schrieb alle Zahlen mit den römischen Zahlzeichen und man kann ihm also nicht verdanken, was er selbst nicht kannte."

[449] E.g., Chasles, Büdinger, Gerhardt, and Richer. So Martin (*Recherches nouvelles* etc.) believes that Gerbert received them from Boethius or his followers. See Woepcke, *Propagation*, p. 41.

[450] Büdinger, loc. cit., p. 10. Nevertheless, in Gerbert's time one Al-Manṣūr, governing Spain under the name of Hishām (976-1002), called from the Orient Al-Begānī to teach his son, so that scholars were recognized. [Picavet, p. 36.]

[451] Weissenborn, loc. cit., p. 235.

[452] Ibid., p. 234.

[453] These letters, of the period 983-997, were edited by Havet, loc. cit., and, less completely, by Olleris, loc. cit. Those touching mathematical topics were edited by Bubnov, loc. cit., pp. 98-106.

[454] He published it in the *Monumenta Germaniae historica*, "Scriptores," Vol. III, and at least three other editions have since appeared, viz. those by Guadet in 1845, by Poinsignon in 1855, and by Waitz in 1877.

[455] Domino ac beatissimo Patri Gerberto, Remorum archiepiscopo, Richerus Monchus, Gallorum congressibus in volumine regerendis, imperii tui, pater sanctissime Gerberte, auctoritas seminarium dedit.

[456] In epistle 17 (Havet collection) he speaks of the "De multiplicatione et divisione numerorum libellum a Joseph Hispano editum abbas Warnerius" (a person otherwise unknown). In epistle 25 he says: "De multiplicatione et divisione numerorum, Joseph Sapiens sententias quasdam edidit."

[457] H. Suter, "Zur Frage über den Josephus Sapiens," *Bibliotheca Mathematica*, Vol. VIII (2), p. 84; Weissenborn, *Einführung*, p. 14; also his *Gerbert*; M. Steinschneider, in *Bibliotheca Mathematica*, 1893, p. 68. Wallis (*Algebra*, 1685, chap. 14) went over the list of Spanish Josefs very carefully, but could find nothing save that "Josephus Hispanus seu Josephus sapiens videtur aut Maurus fuisse aut alius quis in Hispania."

[458] P. Ewald, *Mittheilungen, Neues Archiv d. Gesellschaft für ältere deutsche Geschichtskunde*, Vol. VIII, 1883, pp. 354-364. One of the manuscripts is of 976 A.D. and the other of 992 A.D. See also Franz Steffens, *Lateinische Paläographie*, Freiburg (Schweiz), 1903, pp. xxxix-xl. The forms are reproduced in the plate on page 140.

[459] It is entitled *Constantino suo Gerbertus scolasticus*, because it was addressed to Constantine, a monk of the Abbey of Fleury. The text of the letter to Constantine, preceding the treatise on the Abacus, is given in the *Comptes rendus*, Vol. XVI (1843), p. 295. This book seems to have been written c. 980 A.D. [Bubnov, loc. cit., p. 6.]

[460] "Histoire de l'Arithmétique," *Comptes rendus*, Vol. XVI (1843), pp. 156, 281.

[461] Loc. cit., *Gerberti Opera* etc.

[462] Friedlein thought it spurious. See *Zeitschrift für Mathematik und Physik*, Vol. XII (1867), Hist.-lit. suppl., p. 74. It was discovered in the library of the Benedictine monastery of St. Peter, at Salzburg, and was published by Peter Bernhard Pez in 1721. Doubt was first cast upon it in the Olleris edition (*Œuvres de Gerbert*). See Weissenborn, *Gerbert*, pp. 2, 6, 168, and Picavet, p.

81. Hock, Cantor, and Th. Martin place the composition of the work at c. 996 when Gerbert was in Germany, while Olleris and Picavet refer it to the period when he was at Rheims.

[463] Picavet, loc. cit., p. 182.

[464] Who wrote after Gerbert became pope, for he uses, in his preface, the words, "a domino pape Gerberto." He was quite certainly not later than the eleventh century; we do not have exact information about the time in which he lived.

[465] Picavet, loc. cit., p. 182. Weissenborn, *Gerbert*, p. 227. In Olleris, *Liber Abaci* (of Bernelinus), p. 361.

[466] Richer, in Bubnov, loc. cit., p. 381.

[467] Weissenborn, *Gerbert*, p. 241.

[468] Writers on numismatics are quite uncertain as to their use. See F. Gnechi, *Monete Romane*, 2d ed., Milan, 1900, cap. XXXVII. For pictures of old Greek tesserae of Sarmatia, see S. Ambrosoli, *Monete Greche*, Milan, 1899, p. 202.

[469] Thus Tzwivel's arithmetic of 1507, fol. 2, v., speaks of the ten figures as "characteres sive numerorum apices a diuo Seuerino Boetio."

[470] Weissenborn uses *sipos* for 0. It is not given by Bernelinus, and appears in Radulph of Laon, in the twelfth century. See Günther's *Geschichte*, p. 98, n.; Weissenborn, p. 11; Pihan, *Exposé* etc., pp. xvi-xxii.

In Friedlein's *Boetius*, p. 396, the plate shows that all of the six important manuscripts from which the illustrations are taken contain the symbol, while four out of five which give the words use the word *sipos* for 0. The names appear in a twelfth-century anonymous manuscript in the Vatican, in a passage beginning

Ordine primigeno sibi nomen possidet igin.
Andras ecce locum mox uendicat ipse secundum

Ormis post numeros incompositus sibi primus.

[Boncompagni *Buttettino*, XV, p. 132.] Turchill (twelfth century) gives the names Igin, andras, hormis, arbas, quimas, caletis, zenis, temenias, celentis, saying: "Has autem figuras, ut donnus [dominus] Gvillielmus Rx testatur, a pytagoricis habemus, nomina uero ab arabibus." (Who the William R. was is not known. Boncompagni *Bulletino* XV, p. 136.) Radulph of Laon (d. 1131) asserted that they were Chaldean (*Propagation*, p. 48 n.). A discussion of the whole question is also given in E. C. Bayley, loc. cit. Huet, writing in 1679, asserted that they were of Semitic origin, as did Nesselmann in spite of his despair over ormis, calctis, and celentis; see Woepcke, *Propagation*, p. 48. The names were used as late as the fifteenth century, without the zero, but with the superscript dot for 10's, two dots for 100's, etc., as among the early Arabs. Gerhardt mentions having seen a fourteenth or fifteenth century manuscript in the Bibliotheca Amploniana with the names "Ingnin, andras, armis, arbas, quinas, calctis, zencis, zemenias, zcelentis," and the statement "Si unum punctum super ingnin ponitur, X significat.... Si duo puncta super ... figuras superponunter, fiet decuplim illius quod cum uno puncto significabatur," in *Monatsberichte der K. P. Akad. d. Wiss.*, Berlin, 1867, p. 40.

[471] *A chart of ten numerals in 200 tongues*, by Rev. R. Patrick, London, 1812.

[472] "Numeratio figuralis est cuiusuis numeri per notas, et figuras numerates descriptio." [Clichtoveus, edition of c. 1507, fol. C ii, v.] "Aristoteles enim uoces rerum σύμβολα uocat: id translatum, sonat notas." [Noviomagus, *De Numeris Libri II*, cap. vi.] "Alphabetum decem notarum." [Schonerus, notes to Ramus, 1586, p. 3 seq.] Richer says: "novem numero notas omnem numerum significantes." [Bubnov, loc. cit., p. 381.]

[473] "Il y a dix Caracteres, autrement Figures, Notes, ou Elements." [Peletier, edition of 1607, p. 13.] "Numerorum notas alij figuras, alij signa, alij characteres uocant." [Glareanus, 1545]

edition, f. 9, r.] "Per figuras (quas zyphras uocant) assignationem, quales sunt hæ notulæ, 1. 2. 3. 4...." [Noviomagus, *De Numeris Libri II*, cap. vi.] Gemma Frisius also uses *elementa* and Cardan uses *literae*. In the first arithmetic by an American (Greenwood, 1729) the author speaks of "a few Arabian *Charecters* or Numeral Figures, called *Digits*" (p. 1), and as late as 1790, in the third edition of J. J. Blassière's arithmetic (1st ed. 1769), the name *characters* is still in use, both for "de Latynsche en de Arabische" (p. 4), as is also the term "Cyfferletters" (p. 6, n.). *Ziffer*, the modern German form of cipher, was commonly used to designate any of the nine figures, as by Boeschenstein and Riese, although others, like Köbel, used it only for the zero. So *zifre* appears in the arithmetic by Borgo, 1550 ed. In a Munich codex of the twelfth century, attributed to Gerland, they are called *characters* only: "Usque ad VIII. enim porrigitur omnis numerus et qui supercrescit eisdem designator Karakteribus." [Boncompagni *Bulletino*, Vol. X. p. 607.]

[474] The title of his work is *Prologus N. Ocreati in Helceph* (Arabic *al-qeif*, investigation or memoir) *ad Adelardum Batensem magistrum suum*. The work was made known by C. Henry, in the *Zeitschrift für Mathematik und Physik*, Vol. XXV, p. 129, and in the *Abhandlungen zur Geschichte der Mathematik*, Vol. III; Weissenborn, Gerbert, p. 188.

[475] The zero is indicated by a vacant column.

[476] Leo Jordan, loc. cit., p. 170. "Chifre en augorisme" is the expression used, while a century later "giffre en argorisme" and "cyffres d'augorisme" are similarly used.

[477] *The Works of Geoffrey Chaucer*, edited by W. W. Skeat, Vol. IV, Oxford, 1894, p. 92.

[478] Loc. cit., Vol. III, pp. 179 and 180.

[479] In Book II, chap, vii, of *The Testament of Love*, printed with Chaucer's Works, loc. cit., Vol. VII, London, 1897.

[480] *Liber Abacci*, published in Olleris, *Œuvres de Gerbert*, pp. 357-400.

[481] G. R. Kaye, "The Use of the Abacus in Ancient India," *Journal and Proceedings of the Asiatic Society of Bengal*, 1908, pp. 293-297.

[482] *Liber Abbaci*, by Leonardo Pisano, loc. cit., p. 1.

[483] Friedlein, "Die Entwicklung des Rechnens mit Columnen," *Zeitschrift für Mathematik und Physik*, Vol. X, p. 247.

[484] The divisor 6 or 16 being increased by the difference 4, to 10 or 20 respectively.

[485] E.g. Cantor, Vol. I, p. 882.

[486] Friedlein, loc. cit.; Friedlein, "Gerbert's Regeln der Division" and "Das Rechnen mit Columnen vor dem 10. Jahrhundert," *Zeitschrift für Mathematik und Physik*, Vol. IX; Bubnov, loc. cit., pp. 197-245; M. Chasles, "Histoire de l'arithmétique. Recherches des traces du système de l'abacus, après que cette méthode a pris le nom d'Algorisme.—Preuves qu'à toutes les époques, jusqu'au ^{xvi}^e siècle, on a su que l'arithmétique vulgaire avait pour origine cette méthode ancienne," *Comptes rendus*, Vol. XVII, pp. 143-154, also "Règles de l'abacus," *Comptes rendus*, Vol. XVI, pp. 218-246, and "Analyse et explication du traité de Gerbert," *Comptes rendus*, Vol. XVI, pp. 281-299.

[487] Bubnov, loc. cit., pp. 203-204, "Abbonis abacus."

[488] "Regulae de numerorum abaci rationibus," in Bubnov, loc. cit., pp. 205-225.

[489] P. Treutlein, "Intorno ad alcuni scritti inediti relativi al calcolo dell' abaco," *Bulletino di bibliografia e di storia delle scienze matematiche e fisiche*, Vol. X, pp. 589-647.

[490] "Intorno ad uno scritto inedito di Adelhardo di Bath intitolato 'Regulae Abaci,'" B. Boncompagni, in his *Bulletino*, Vol. XIV, pp. 1-134.

[491] Treutlein, loc. cit.; Boncompagni, "Intorno al Tractatus de Abaco di Gerlando," *Bulletino*, Vol. X, pp. 648-656.

[492] E. Narducci, "Intorno a due trattati inediti d'abaco contenuti in due codici Vaticani del secolo XII," Boncompagni *Bulletino*, Vol. XV, pp. 111-162.

[493] See Molinier, *Les sources de l'histoire de France*, Vol. II, Paris, 1902, pp. 2, 3.

[494] Cantor, *Geschichte*, Vol. I, p. 762. A. Nagl in the *Abhandlungen zur Geschichte der Mathematik*, Vol. V, p. 85.

[495] 1030-1117.

[496] *Abhandlungen zur Geschichte der Mathematik*, Vol. V, pp. 85-133. The work begins "Incipit Liber Radulfi laudunensis de abaco."

[497] *Materialien zur Geschichte der arabischen Zahlzeichen in Frankreich*, loc. cit.

[498] Who died in 1202.

[499] Cantor, *Geschichte*, Vol. I (3), pp. 800-803; Boncompagni, *Trattati*, Part II. M. Steinschneider ("Die Mathematik bei den Juden," *Bibliotheca Mathematica*, Vol. X (2), p. 79) ingeniously derives another name by which he is called (Abendeuth) from Ibn Daūd (Son of David). See also *Abhandlungen*, Vol. III, p. 110.

[500] John is said to have died in 1157.

[501] For it says, "Incipit prologus in libro alghoarismi de practica arismetrice. Qui editus est a magistro Johanne yspalensi." It is published in full in the second part of Boncompagni's *Trattati d'aritmetica*.

[502] Possibly, indeed, the meaning of "libro alghoarismi" is not "to Al-Khowārazmī's book," but "to a book of algorism." John of Luna says of it: "Hoc idem est illud etiam quod ... alcorismus dicere videtur." [*Trattati*, p. 68.]

[503] For a résumé, see Cantor, Vol. I (3), pp. 800-803. As to the author, see Eneström in the *Bibliotheca Mathematica*, Vol. VI (3), p. 114, and Vol. IX (3), p. 2.

[504] Born at Cremona (although some have asserted at Carmona, in Andalusia) in 1114; died at Toledo in 1187. Cantor, loc. cit.; Boncompagni, *Atti d. R. Accad. d. n. Lincei*, 1851.

[505] See *Abhandlungen zur Geschichte der Mathematik*, Vol. XIV, p. 149; *Bibliotheca Mathematica*, Vol. IV (3), p. 206. Boncompagni had a fourteenth-century manuscript of his work, *Gerardi Cremonensis artis metrice practice*. See also T. L. Heath, *The Thirteen Books of Euclid's Elements*, 3 vols., Cambridge, 1908, Vol. I, pp. 92-94 ; A. A. Björnbo, "Gerhard von Cremonas Übersetzung von Alkwarizmis Algebra und von Euklids Elementen," *Bibliotheca Mathematica*, Vol. VI (3), pp. 239-248.

[506] Wallis, *Algebra*, 1685, p. 12 seq.

[507] Cantor, *Geschichte*, Vol. I (3), p. 906; A. A. Björnbo, "Al-Chwārizmī's trigonometriske Tavler," *Festskrift til H. G. Zeuthen*, Copenhagen, 1909, pp. 1-17.

[508] Heath, loc. cit., pp. 93-96.

[509] M. Steinschneider, *Zeitschrift der deutschen morgenländischen Gesellschaft*, Vol. XXV, 1871, p. 104, and *Zeitschrift für Mathematik und Physik*, Vol. XVI, 1871, pp. 392-393; M. Curtze, *Centralblatt für Bibliothekswesen*, 1899, p. 289; E. Wappler, *Zur Geschichte der deutschen Algebra im 15. Jahrhundert*, Programm, Zwickau, 1887; L. C. Karpinski, "Robert of Chester's Translation of the Algebra of Al-Khowārazmī," *Bibliotheca Mathematica*, Vol. XI (3), p. 125. He is also known as Robertus Retinensis, or Robert of Reading.

[510] Nagl, A., "Ueber eine Algorismus-Schrift des XII. Jahrhunderts und über die Verbreitung der indisch-arabischen Rechenkunst und Zahlzeichen im christl. Abendlande," in the *Zeitschrift für Mathematik und Physik, Hist.-lit. Abth.*, Vol. XXXIV, p. 129. Curtze, *Abhandlungen zur Geschichte der Mathematik*, Vol. VIII, pp. 1-27.

[511] See line *a* in the plate on p. 143.

[512] *Sefer ha-Mispar, Das Buch der Zahl, ein hebräisch-arithmetisches Werk des R. Abraham ibn Esra*, Moritz Silberberg, Frankfurt a. M., 1895.

[513] Browning's "Rabbi ben Ezra."

[514] "Darum haben auch die Weisen Indiens all ihre Zahlen durch neun bezeichnet und Formen für die 9 Ziffern gebildet." [*Sefer ha-Mispar*, loc. cit., p. 2.]

[515] F. Bonaini, "Memoria unica sincrona di Leonardo Fibonacci," Pisa, 1858, republished in 1867, and appearing in the *Giornale Arcadico*, Vol. CXCVII (N.S. LII); Gaetano Milanesi, *Documento inedito e sconosciuto a Lionardo Fibonacci*, Roma, 1867; Guglielmini, *Elogio di Lionardo Pisano*, Bologna, 1812, p. 35; Libri, *Histoire des sciences mathématiques*, Vol. II, p. 25; D. Martines, *Origine e progressi dell' aritmetica*, Messina, 1865, p. 47; Lucas, in Boncompagni *Bulletino*, Vol. X, pp. 129, 239; Besagne, *ibid.*, Vol. IX, p. 583; Boncompagni, three works as cited in Chap. I; G. Eneström, "Ueber zwei angebliche mathematische Schulen im christlichen Mittelalter," *Bibliotheca Mathematica*, Vol. VIII (3), pp. 252-262; Boncompagni, "Della vita e delle opere di Leonardo Pisano," loc. cit.

[516] The date is purely conjectural. See the *Bibliotheca Mathematica*, Vol. IV (3), p. 215.

[517] An old chronicle relates that in 1063 Pisa fought a great battle with the Saracens at Palermo, capturing six ships, one being "full of wondrous treasure," and this was devoted to building the cathedral.

[518] Heyd, loc. cit., Vol. I, p. 149.

[519] Ibid., p. 211.

[520] J. A. Symonds, *Renaissance in Italy. The Age of Despots*. New York, 1883, p. 62.

[521] Symonds, loc. cit., p. 79.

[522] J. A. Froude, *The Science of History*, London, 1864. "Un brevet d'apothicaire n'empêcha pas Dante d'être le plus grand poète de l'Italie, et ce fut un petit marchand de Pise qui donna l'algèbre aux Chrétiens." [Libri, *Histoire*, Vol. I, p. xvi.]

[523] A document of 1226, found and published in 1858, reads: "Leonardo bigollo quondam Guilielmi."

[524] "Bonaccingo germano suo."

[525] E.g. Libri, Guglielmini, Tiraboschi.

[526] Latin, *Bonaccius*.

[527] Boncompagni and Milanesi.

[528] Reprint, p. 5.

[529] Whence the French name for candle.

[530] Now part of Algiers.

[531] E. Reclus, *Africa*, New York, 1893, Vol. II, p. 253.

[532] "Sed hoc totum et algorismum atque arcus pictagore quasi errorem computavi respectu modi indorum." Woepcke, *Propagation* etc., regards this as referring to two different systems, but the expression may very well mean algorism as performed upon the Pythagorean arcs (or table).

[533] "Book of the Abacus," this term then being used, and long afterwards in Italy, to mean merely the arithmetic of computation.

[534] "Incipit liber Abaci a Leonardo filio Bonacci compositus anno 1202 et correctus ab eodem anno 1228." Three MSS. of the thirteenth century are known, viz. at Milan, at Siena, and in the Vatican library. The work was first printed by Boncompagni in 1857.

[535] I.e. in relation to the quadrivium. "Non legant in festivis diebus, nisi Philosophos et rhetoricas et quadrivalia et barbarismum et ethicam, si placet." Suter, *Die Mathematik auf den Universitäten des Mittelalters*, Zürich, 1887, p. 56. Roger Bacon gives a still more gloomy view of Oxford in his time in his *Opus minus*, in the *Rerum Britannicarum medii aevi scriptores*, London, 1859, Vol. I, p. 327. For a picture of Cambridge at this time consult F. W. Newman, *The English Universities, translated from the German of V. A. Huber*, London, 1843, Vol. I, p. 61; W. W. R. Ball, *History of Mathematics at Cambridge*, 1889; S. Günther, *Geschichte des mathematischen Unterrichts im deutschen Mittelalter bis zum Jahre 1525*, Berlin, 1887, being Vol. III of *Monumenta Germaniae paedagogica*.

[536] On the commercial activity of the period, it is known that bills of exchange passed between Messina and Constantinople in 1161, and that a bank was founded at Venice in 1170, the Bank of San Marco being established in the following year. The activity of Pisa was very manifest at this time. Heyd, loc. cit., Vol. II, p. 5; V. Casagrandi, *Storia e cronologia*, 3d ed., Milan, 1901, p. 56.

[537] J. A. Symonds, loc. cit., Vol. II, p. 127.

[538] I. Taylor, *The Alphabet*, London, 1883, Vol. II, p. 263.

[539] Cited by Unger's History, p. 15. The Arabic numerals appear in a Regensburg chronicle of 1167 and in Silesia in 1340. See Schmidt's *Encyclopädie der Erziehung*, Vol. VI, p. 726; A. Kuckuk, "Die Rechenkunst im sechzehnten Jahrhundert," *Festschrift zur dritten Säcularfeier des Berlinischen Gymnasiums zum grauen Kloster*, Berlin, 1874, p. 4.

[540] The text is given in Halliwell, *Rara Mathematica*, London, 1839.

[541] Seven are given in Ashmole's *Catalogue of Manuscripts in the Oxford Library*, 1845.

[542] Maximilian Curtze, *Petri Philomeni de Dacia in Algorismum Vulgarem Johannis de Sacrobosco commentarius, una cum Algorismo ipso*, Copenhagen, 1897; L. C. Karpinski, "Jordanus Nemorarius and John of Halifax," *American Mathematical Monthly*, Vol. XVII, pp. 108-113.

[543] J. Aschbach, *Geschichte der Wiener Universität im ersten Jahrhunderte ihres Bestehens*, Wien, 1865, p. 93.

[544] Curtze, loc. cit., gives the text.

[545] Curtze, loc. cit., found some forty-five copies of the *Algorismus* in three libraries of Munich, Venice, and Erfurt (Amploniana). Examination of two manuscripts from the Plimpton collection and the Columbia library shows such marked divergence from each other and from the text published by Curtze that the conclusion seems legitimate that these were students' lecture notes. The shorthand character of the writing further confirms this view, as it shows that they were written largely for the personal use of the writers.

[546] "Quidam philosophus edidit nomine Albus, unde et Algorismus nuncupatur." [Curtze, loc. cit., p. 1.]

[547] "Sinistrorsum autera scribimus in hac arte more arabico sive iudaico, huius scientiae inventorum." [Curtze, loc. cit., p. 7.] The Plimpton manuscript omits the words "sive iudaico."

[548] "Non enim omnis numerus per quascumque figuras Indorum repraesentatur, sed tantum determinatus per determinatam, ut 4 non per 5,..." [Curtze, loc. cit., p. 25.]

[549] C. Henry, "Sur les deux plus anciens traités français d'algorisme et de géométrie," Boncompagni *Bulletino*, Vol. XV, p.

49; Victor Mortet, "Le plus ancien traité français d'algorisme," loc. cit.

[550] *L'État des sciences en France, depute la mort du Roy Robert, arrivée en 1031, jusqu'à celle de Philippe le Bel, arrivée en 1314*, Paris, 1741.

[551] *Discours sur l'état des lettres en France au XIII^e siecle*, Paris, 1824.

[552] *Aperçu historique*, Paris, 1876 ed., p. 464.

[553] Ranulf Higden, a native of the west of England, entered St. Werburgh's monastery at Chester in 1299. He was a Benedictine monk and chronicler, and died in 1364. His *Polychronicon*, a history in seven books, was printed by Caxton in 1480.

[554] Trevisa's translation, Higden having written in Latin.

[555] An illustration of this feeling is seen in the writings of Prosdocimo de' Beldomandi (b. c. 1370-1380, d. 1428): "Inveni in quam pluribus libris algorismi nuncupatis mores circa numeros operandi satis varios atque diversos, qui licet boni existerent atque veri erant, tamen fastidiosi, tum propter ipsarum regularum multitudinem, tum propter earum deleationes, tum etiam propter ipsarum operationum probationes, utrum si bone fuerint vel ne. Erant et etiam isti modi interim fastidiosi, quod si in aliquo calculo astroloico error contigisset, calculatorem operationem suam a capite incipere oportebat, dato quod error suus adhuc satis propinquus existeret; et hoc propter figuras in sua operatione deletas. Indigebat etiam calculator semper aliquo lapide vel sibi conformi, super quo scribere atque faciliter delere posset figuras cum quibus operabatur in calculo suo. Et quia haec omnia satis fastidiosa atque laboriosa mihi visa sunt, disposui libellum edere in quo omnia ista abicerentur: qui etiam algorismus sive liber de numeris denominari poterit. Scias tamen quod in hoc libello ponere non intendo nisi ea quae ad calculum necessaria sunt, alia quae in aliis libris practice arismetrice tanguntur, ad calculum non necessaria, propter brevitatem dimitendo." [Quoted by A. Nagl,

Zeitschrift für Mathematik und Physik, Hist.-lit. Abth., Vol. XXXIV, p. 143; Smith, *Rara Arithmetica*, p. 14, in facsimile.]

[556] P. Ewald, loc. cit.; Franz Steffens, *Lateinische Paläographie*, pp. xxxix-xl. We are indebted to Professor J. M. Burnam for a photograph of this rare manuscript.

[557] See the plate of forms on p. 88.

[558] Karabacek, loc. cit., p. 56; Karpinski, "Hindu Numerals in the Fihrist," *Bibliotheca Mathematica*, Vol. XI (3), p. 121.

[559] Woepcke, "Sur une donnée historique," etc., loc. cit., and "Essai d'une restitution de travaux perdus d'Apollonius sur les quantités irrationnelles, d'après des indications tirées d'un manuscrit arabe," *Tome XIV des Mémoires présentés par divers savants à l'Académie des sciences*, Paris, 1856, note, pp. 6-14.

[560] *Archeological Report of the Egypt Exploration Fund for 1908-1909*, London, 1910, p. 18.

[561] There was a set of astronomical tables in Boncompagni's library bearing this date: "Nota quod anno dni nri ihu xpi. 1264. perfecto." See Narducci's *Catalogo*, p. 130.

[562] "On the Early use of Arabic Numerals in Europe," read before the Society of Antiquaries April 14, 1910, and published in *Archæologia* in the same year.

[563] *Ibid.*, p. 8, n. The date is part of an Arabic inscription.

[564] O. Codrington, *A Manual of Musalman Numismatics*, London, 1904.

[565] See Arbuthnot, *The Mysteries of Chronology*, London, 1900, pp. 75, 78, 98; F. Pichler, *Repertorium der steierischen Münzkunde*, Grätz, 1875, where the claim is made of an Austrian coin of 1458; *Bibliotheca Mathematica*, Vol. X (2), p. 120, and Vol. XII (2), p. 120. There is a Brabant piece of 1478 in the collection of D. E. Smith.

[566] A specimen is in the British Museum. [Arbuthnot, p. 79.]

[567] Ibid., p. 79.

[568] *Liber de Remediis utriusque fortunae Coloniae*.

[569] Fr. Walther et Hans Hurning, Nördlingen.

[570] *Ars Memorandi*, one of the oldest European block-books.

[571] Eusebius Caesariensis, *De praeparatione evangelica*, Venice, Jenson, 1470. The above statement holds for copies in the Astor Library and in the Harvard University Library.

[572] Francisco de Retza, *Comestorium vitiorum*, Nürnberg, 1470. The copy referred to is in the Astor Library.

[573] See Mauch, "Ueber den Gebrauch arabischer Ziffern und die Veränderungen derselben," *Anzeiger für Kunde der deutschen Vorzeit*, 1861, columns 46, 81, 116, 151, 189, 229, and 268; Calmet, *Recherches sur l'origine des chiffres d'arithmétique*, plate, loc. cit.

[574] Günther, *Geschichte*, p. 175, n.; Mauch, loc. cit.

[575] These are given by W. R. Lethaby, from drawings by J. T. Irvine, in the *Proceedings of the Society of Antiquaries*, 1906, p. 200.

[576] There are some ill-tabulated forms to be found in J. Bowring, *The Decimal System*, London, 1854, pp. 23, 25, and in L. A. Chassant, *Dictionnaire des abréviations latines et françaises ... du moyen âge*, Paris, MDCCCLXVI, p. 113. The best sources we have at present, aside from the Hill monograph, are P. Treutlein, *Geschichte unserer Zahlzeichen*, Karlsruhe, 1875; Cantor's *Geschichte*, Vol. I, table; M. Prou, *Manuel de paléographie latine et française*, 2d ed., Paris, 1892, p. 164; A. Cappelli, *Dizionario di abbreviature latine ed italiane*, Milan, 1899. An interesting early source is found in the rare Caxton work of 1480, *The Myrroure of the World*. In Chap. X is a cut with the various numerals, the chapter beginning "The fourth scyence is

called arismetrique." Two of the fifteen extant copies of this work are at present in the library of Mr. J. P. Morgan, in New York.

[577] From the twelfth-century manuscript on arithmetic, Curtze, loc. cit., *Abhandlungen*, and Nagl, loc. cit. The forms are copied from Plate VII in *Zeitschrift für Mathematik und Physik*, Vol. XXXIV.

[578] From the Regensburg chronicle. Plate containing some of these numerals in *Monumenta Germaniae historica*, "Scriptores" Vol. XVII, plate to p. 184; Wattenbach, *Anleitung zur lateinischen Palaeographie*, Leipzig, 1886, p. 102; Boehmer, *Fontes rerum Germanicarum*, Vol. III, Stuttgart, 1852, p. lxx.

[579] French Algorismus of 1275; from an unpublished photograph of the original, in the possession of D. E. Smith. See also p. 135.

[580] From a manuscript of Boethius c. 1294, in Mr. Plimpton's library. Smith, *Rara Arithmetica*, Plate I.

[581] Numerals in a 1303 manuscript in Sigmaringen, copied from Wattenbach, loc. cit., p. 102.

[582] From a manuscript, Add. Manuscript 27,589, British Museum, 1360 A.D. The work is a computus in which the date 1360 appears, assigned in the British Museum catalogue to the thirteenth century.

[583] From the copy of Sacrabosco's *Algorismus* in Mr. Plimpton's library. Date c. 1442. See Smith, *Rara Arithmetica*, p. 450.

[584] See *Rara Arithmetica*, pp. 446-447.

[585] Ibid., pp. 469-470.

[586] Ibid., pp. 477-478.

[587] The i is used for "one" in the Treviso arithmetic (1478), Clichtoveus (c. 1507 ed., where both i and j are so used), Chiarini

(1481), Sacrobosco (1488 ed.), and Tzwivel (1507 ed., where jj and jz are used for 11 and 12). This was not universal, however, for the *Algorithmus linealis* of c. 1488 has a special type for 1. In a student's notebook of lectures taken at the University of Würzburg in 1660, in Mr. Plimpton's library, the ones are all in the form of i.

[588] Thus the date *ſſ.ſſ.ſſ.*, for 1580, appears in a MS. in the Laurentian library at Florence. The second and the following five characters are taken from Cappelli's *Dizionario*, p. 380, and are from manuscripts of the twelfth, thirteenth, fourteenth, sixteenth, seventeenth, and eighteenth centuries, respectively.

[589] E.g. Chiarini's work of 1481; Clichtoveus (c. 1507).

[590] The first is from an algorismus of the thirteenth century, in the Hannover Library. [See Gerhardt, "Ueber die Entstehung und Ausbreitung des dekadischen Zahlensystems," loc. cit., p. 28.] The second character is from a French algorismus, c. 1275. [Boncompagni *Bulletino*, Vol. XV, p. 51.] The third and the following sixteen characters are given by Cappelli, loc. cit., and are from manuscripts of the twelfth (1), thirteenth (2), fourteenth (7), fifteenth (3), sixteenth (1), seventeenth (2), and eighteenth (1) centuries, respectively.

[591] Thus Chiarini (1481) has *z3* for 23.

[592] The first of these is from a French algorismus, c. 1275. The second and the following eight characters are given by Cappelli, loc. cit., and are from manuscripts of the twelfth (2), thirteenth, fourteenth, fifteenth (3), seventeenth, and eighteenth centuries, respectively.

[593] See Nagl, loc. cit.

[594] Hannover algorismus, thirteenth century.

[595] See the Dagomari manuscript, in *Rara Arithmetica*, pp. 435, 437-440.

[596] But in the woodcuts of the *Margarita Philosophica* (1503) the old forms are used, although the new ones appear in the text. In Caxton's *Myrrour of the World* (1480) the old form is used.

[597] Cappelli, loc. cit. They are partly from manuscripts of the tenth, twelfth, thirteenth (3), fourteenth (7), fifteenth (6), and eighteenth centuries, respectively. Those in the third line are from Chassant's *Dictionnaire*, p. 113, without mention of dates.

[598] The first is from the Hannover algorismus, thirteenth century. The second is taken from the Rollandus manuscript, 1424. The others in the first two lines are from Cappelli, twelfth (3), fourteenth (6), fifteenth (13) centuries, respectively. The third line is from Chassant, loc. cit., p. 113, no mention of dates.

[599] The first of these forms is from the Hannover algorismus, thirteenth century. The following are from Cappelli, fourteenth (3), fifteenth, sixteenth (2), and eighteenth centuries, respectively.

[600] The first of these is taken from the Hannover algorismus, thirteenth century. The following forms are from Cappelli, twelfth, thirteenth, fourteenth (5), fifteenth (2), seventeenth, and eighteenth centuries, respectively.

[601] All of these are given by Cappelli, thirteenth, fourteenth, fifteenth (2), and sixteenth centuries, respectively.

[602] Smith, *Rara Arithmetica*, p. 489. This is also seen in several of the Plimpton manuscripts, as in one written at Ancona in 1684. See also Cappelli, loc. cit.

[603] French algorismus, c. 1275, for the first of these forms. Cappelli, thirteenth, fourteenth, fifteenth (3), and seventeenth centuries, respectively. The last three are taken from *Byzantinische Analekten*, J. L. Heiberg, being forms of the fifteenth century, but not at all common. Ϡ was the old Greek symbol for 90.

[604] For the first of these the reader is referred to the forms ascribed to Boethius, in the illustration on p. 88; for the second, to

Radulph of Laon, see p. 60. The third is used occasionally in the Rollandus (1424) manuscript, in Mr. Plimpton's library. The remaining three are from Cappelli, fourteenth (2) and seventeenth centuries.

[605] Smith, *An Early English Algorism*.

[606] Kuckuck, p. 5.

[607] A. Cappelli, loc. cit., p. 372.

[608] Smith, *Rara Arithmetica*, p. 443.

[609] Curtze, *Petri Philomeni de Dacia* etc., p. IX.

[610] Cappelli, loc. cit., p. 376.

[611] Curtze, loc. cit., pp. VIII-IX, note.

[612] Edition of 1544-1545, f. 52.

[613] *De numeris libri II*, 1544 ed., cap. xv. Heilbronner, loc. cit., p. 736, also gives them, and compares this with other systems.

[614] Noviomagus says of them: "De quibusdam Astrologicis, sive Chaldaicis numerorum notis.... Sunt & aliæ quædam notæ, quibus Chaldaei & Astrologii quemlibet numerum artificiose & arguté describunt, scitu periucundæ, quas nobis communicavit Rodolphus Paludanus Nouiomagus."

*** END OF THE PROJECT GUTENBERG EBOOK THE HINDU-
ARABIC NUMERALS ***

Updated editions will replace the previous one—the old editions will be renamed.

Creating the works from print editions not protected by U.S. copyright law means that no one owns a United States copyright in these works, so the Foundation (and you!) can copy and distribute it in the United States without permission and without paying copyright royalties. Special rules, set forth in the General Terms of Use part of this license, apply to copying and distributing Project Gutenberg™ electronic works to protect the PROJECT GUTENBERG™ concept and trademark. Project Gutenberg is a registered trademark, and may not be used if you charge for an eBook, except by following the terms of the trademark license, including paying royalties for use of the Project Gutenberg trademark. If you do not charge anything for copies of this eBook, complying with the trademark license is very easy. You may use this eBook for nearly any purpose such as creation of derivative works, reports, performances and research. Project Gutenberg eBooks may be modified and printed and given away—you may do practically ANYTHING in the United States with eBooks not protected by U.S. copyright law. Redistribution is subject to the trademark license, especially commercial redistribution.

START: FULL LICENSE

THE FULL PROJECT GUTENBERG™ LICENSE

PLEASE READ THIS BEFORE YOU DISTRIBUTE OR USE THIS WORK

To protect the Project Gutenberg™ mission of promoting the free distribution of electronic works, by using or distributing this work (or any other work associated in any way with the phrase “Project Gutenberg”), you agree to comply with all the terms of the Full Project Gutenberg License available with this file or online at www.gutenberg.org/license.

Section 1. General Terms of Use and Redistributing Project Gutenberg electronic works

1.A. By reading or using any part of this Project Gutenberg electronic work, you indicate that you have read, understand, agree to and accept all the terms of this license and intellectual property (trademark/copyright) agreement. If you do not agree to abide by all the terms of this agreement, you must cease using and return or destroy all copies of Project Gutenberg electronic works in your possession. If you paid a fee for obtaining a copy of or access to a Project Gutenberg electronic work and you do not agree to be bound by the terms of this agreement, you may obtain a refund from the person or entity to whom you paid the fee as set forth in paragraph 1.E.8.

1.B. “Project Gutenberg” is a registered trademark. It may only be used on or associated in any way with an electronic work by people who agree to be bound by the terms of this agreement. There are a few things that you can do with most Project Gutenberg electronic works even without complying with the full terms of this agreement. See paragraph 1.C below. There are a lot of things you can do with Project Gutenberg electronic works if you follow the terms of this agreement and help preserve free future access to Project Gutenberg electronic works. See paragraph 1.E below.

1.C. The Project Gutenberg Literary Archive Foundation (“the Foundation” or PGLAF), owns a compilation copyright in the

collection of Project Gutenberg electronic works. Nearly all the individual works in the collection are in the public domain in the United States. If an individual work is unprotected by copyright law in the United States and you are located in the United States, we do not claim a right to prevent you from copying, distributing, performing, displaying or creating derivative works based on the work as long as all references to Project Gutenberg are removed. Of course, we hope that you will support the Project Gutenberg mission of promoting free access to electronic works by freely sharing Project Gutenberg works in compliance with the terms of this agreement for keeping the Project Gutenberg name associated with the work. You can easily comply with the terms of this agreement by keeping this work in the same format with its attached full Project Gutenberg License when you share it without charge with others.

1.D. The copyright laws of the place where you are located also govern what you can do with this work. Copyright laws in most countries are in a constant state of change. If you are outside the United States, check the laws of your country in addition to the terms of this agreement before downloading, copying, displaying, performing, distributing or creating derivative works based on this work or any other Project Gutenberg work. The Foundation makes no representations concerning the copyright status of any work in any country other than the United States.

1.E. Unless you have removed all references to Project Gutenberg:

1.E.1. The following sentence, with active links to, or other immediate access to, the full Project Gutenberg License must appear prominently whenever any copy of a Project Gutenberg work (any work on which the phrase “Project Gutenberg” appears, or with which the phrase “Project Gutenberg” is associated) is accessed, displayed, performed, viewed, copied or distributed:

This eBook is for the use of anyone anywhere in the United States and most other parts of the world at no cost and with almost no restrictions whatsoever. You may copy it, give it away or re-use it under the terms of the Project Gutenberg™

License included with this eBook or online at www.gutenberg.org. If you are not located in the United States, you will have to check the laws of the country where you are located before using this eBook.

1.E.2. If an individual Project Gutenberg electronic work is derived from texts not protected by U.S. copyright law (does not contain a notice indicating that it is posted with permission of the copyright holder), the work can be copied and distributed to anyone in the United States without paying any fees or charges. If you are redistributing or providing access to a work with the phrase “Project Gutenberg” associated with or appearing on the work, you must comply either with the requirements of paragraphs 1.E.1 through 1.E.7 or obtain permission for the use of the work and the Project Gutenberg trademark as set forth in paragraphs 1.E.8 or 1.E.9.

1.E.3. If an individual Project Gutenberg electronic work is posted with the permission of the copyright holder, your use and distribution must comply with both paragraphs 1.E.1 through 1.E.7 and any additional terms imposed by the copyright holder. Additional terms will be linked to the Project Gutenberg License for all works posted with the permission of the copyright holder found at the beginning of this work.

1.E.4. Do not unlink or detach or remove the full Project Gutenberg License terms from this work, or any files containing a part of this work or any other work associated with Project Gutenberg.

1.E.5. Do not copy, display, perform, distribute or redistribute this electronic work, or any part of this electronic work, without prominently displaying the sentence set forth in paragraph 1.E.1 with active links or immediate access to the full terms of the Project Gutenberg License.

1.E.6. You may convert to and distribute this work in any binary, compressed, marked up, nonproprietary or proprietary form, including any word processing or hypertext form. However, if you provide access to or distribute copies of a Project Gutenberg work in a format

other than “Plain Vanilla ASCII” or other format used in the official version posted on the official Project Gutenberg website (www.gutenberg.org), you must, at no additional cost, fee or expense to the user, provide a copy, a means of exporting a copy, or a means of obtaining a copy upon request, of the work in its original “Plain Vanilla ASCII” or other form. Any alternate format must include the full Project Gutenberg License as specified in paragraph 1.E.1.

1.E.7. Do not charge a fee for access to, viewing, displaying, performing, copying or distributing any Project Gutenberg works unless you comply with paragraph 1.E.8 or 1.E.9.

1.E.8. You may charge a reasonable fee for copies of or providing access to or distributing Project Gutenberg electronic works provided that:

- You pay a royalty fee of 20% of the gross profits you derive from the use of Project Gutenberg works calculated using the method you already use to calculate your applicable taxes. The fee is owed to the owner of the Project Gutenberg trademark, but he has agreed to donate royalties under this paragraph to the Project Gutenberg Literary Archive Foundation. Royalty payments must be paid within 60 days following each date on which you prepare (or are legally required to prepare) your periodic tax returns. Royalty payments should be clearly marked as such and sent to the Project Gutenberg Literary Archive Foundation at the address specified in Section 4, “Information about donations to the Project Gutenberg Literary Archive Foundation.”
- You provide a full refund of any money paid by a user who notifies you in writing (or by e-mail) within 30 days of receipt that s/he does not agree to the terms of the full Project Gutenberg™ License. You must require such a user to return or destroy all copies of the works possessed in a physical medium and discontinue all use of and all access to other copies of Project Gutenberg™ works.
- You provide, in accordance with paragraph 1.F.3, a full refund of any money paid for a work or a replacement copy, if a defect in the

electronic work is discovered and reported to you within 90 days of receipt of the work.

- You comply with all other terms of this agreement for free distribution of Project Gutenberg™ works.

1.E.9. If you wish to charge a fee or distribute a Project Gutenberg™ electronic work or group of works on different terms than are set forth in this agreement, you must obtain permission in writing from the Project Gutenberg Literary Archive Foundation, the manager of the Project Gutenberg™ trademark. Contact the Foundation as set forth in Section 3 below.

1.F.

1.F.1. Project Gutenberg volunteers and employees expend considerable effort to identify, do copyright research on, transcribe and proofread works not protected by U.S. copyright law in creating the Project Gutenberg™ collection. Despite these efforts, Project Gutenberg™ electronic works, and the medium on which they may be stored, may contain “Defects,” such as, but not limited to, incomplete, inaccurate or corrupt data, transcription errors, a copyright or other intellectual property infringement, a defective or damaged disk or other medium, a computer virus, or computer codes that damage or cannot be read by your equipment.

1.F.2. LIMITED WARRANTY, DISCLAIMER OF DAMAGES - Except for the “Right of Replacement or Refund” described in paragraph 1.F.3, the Project Gutenberg Literary Archive Foundation, the owner of the Project Gutenberg™ trademark, and any other party distributing a Project Gutenberg™ electronic work under this agreement, disclaim all liability to you for damages, costs and expenses, including legal fees. YOU AGREE THAT YOU HAVE NO REMEDIES FOR NEGLIGENCE, STRICT LIABILITY, BREACH OF WARRANTY OR BREACH OF CONTRACT EXCEPT THOSE PROVIDED IN PARAGRAPH 1.F.3. YOU AGREE THAT THE FOUNDATION, THE TRADEMARK OWNER, AND ANY DISTRIBUTOR UNDER THIS AGREEMENT WILL NOT BE

LIABLE TO YOU FOR ACTUAL, DIRECT, INDIRECT, CONSEQUENTIAL, PUNITIVE OR INCIDENTAL DAMAGES EVEN IF YOU GIVE NOTICE OF THE POSSIBILITY OF SUCH DAMAGE.

1.F.3. LIMITED RIGHT OF REPLACEMENT OR REFUND - If you discover a defect in this electronic work within 90 days of receiving it, you can receive a refund of the money (if any) you paid for it by sending a written explanation to the person you received the work from. If you received the work on a physical medium, you must return the medium with your written explanation. The person or entity that provided you with the defective work may elect to provide a replacement copy in lieu of a refund. If you received the work electronically, the person or entity providing it to you may choose to give you a second opportunity to receive the work electronically in lieu of a refund. If the second copy is also defective, you may demand a refund in writing without further opportunities to fix the problem.

1.F.4. Except for the limited right of replacement or refund set forth in paragraph 1.F.3, this work is provided to you 'AS-IS', WITH NO OTHER WARRANTIES OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO WARRANTIES OF MERCHANTABILITY OR FITNESS FOR ANY PURPOSE.

1.F.5. Some states do not allow disclaimers of certain implied warranties or the exclusion or limitation of certain types of damages. If any disclaimer or limitation set forth in this agreement violates the law of the state applicable to this agreement, the agreement shall be interpreted to make the maximum disclaimer or limitation permitted by the applicable state law. The invalidity or unenforceability of any provision of this agreement shall not void the remaining provisions.

1.F.6. INDEMNITY - You agree to indemnify and hold the Foundation, the trademark owner, any agent or employee of the Foundation, anyone providing copies of Project Gutenberg™ electronic works in accordance with this agreement, and any volunteers associated with the production, promotion and distribution of Project Gutenberg™ electronic works, harmless from all liability,

costs and expenses, including legal fees, that arise directly or indirectly from any of the following which you do or cause to occur: (a) distribution of this or any Project Gutenberg work, (b) alteration, modification, or additions or deletions to any Project Gutenberg work, and (c) any Defect you cause.

Section 2. Information about the Mission of Project Gutenberg

Project Gutenberg is synonymous with the free distribution of electronic works in formats readable by the widest variety of computers including obsolete, old, middle-aged and new computers. It exists because of the efforts of hundreds of volunteers and donations from people in all walks of life.

Volunteers and financial support to provide volunteers with the assistance they need are critical to reaching Project Gutenberg's goals and ensuring that the Project Gutenberg collection will remain freely available for generations to come. In 2001, the Project Gutenberg Literary Archive Foundation was created to provide a secure and permanent future for Project Gutenberg and future generations. To learn more about the Project Gutenberg Literary Archive Foundation and how your efforts and donations can help, see Sections 3 and 4 and the Foundation information page at www.gutenberg.org.

Section 3. Information about the Project Gutenberg Literary Archive Foundation

The Project Gutenberg Literary Archive Foundation is a non-profit 501(c)(3) educational corporation organized under the laws of the state of Mississippi and granted tax exempt status by the Internal Revenue Service. The Foundation's EIN or federal tax identification number is 64-6221541. Contributions to the Project Gutenberg Literary Archive Foundation are tax deductible to the full extent permitted by U.S. federal laws and your state's laws.

The Foundation's business office is located at 41 Watchung Plaza #516, Montclair NJ 07042, USA, +1 (862) 621-9288. Email contact links and up to date contact information can be found at the Foundation's website and official page at www.gutenberg.org/contact

Section 4. Information about Donations to the Project Gutenberg Literary Archive Foundation

Project Gutenberg™ depends upon and cannot survive without widespread public support and donations to carry out its mission of increasing the number of public domain and licensed works that can be freely distributed in machine-readable form accessible by the widest array of equipment including outdated equipment. Many small donations (\$1 to \$5,000) are particularly important to maintaining tax exempt status with the IRS.

The Foundation is committed to complying with the laws regulating charities and charitable donations in all 50 states of the United States. Compliance requirements are not uniform and it takes a considerable effort, much paperwork and many fees to meet and keep up with these requirements. We do not solicit donations in locations where we have not received written confirmation of compliance. To SEND DONATIONS or determine the status of compliance for any particular state visit www.gutenberg.org/donate.

While we cannot and do not solicit contributions from states where we have not met the solicitation requirements, we know of no prohibition against accepting unsolicited donations from donors in such states who approach us with offers to donate.

International donations are gratefully accepted, but we cannot make any statements concerning tax treatment of donations received from outside the United States. U.S. laws alone swamp our small staff.

Please check the Project Gutenberg web pages for current donation methods and addresses. Donations are accepted in a number of other

ways including checks, online payments and credit card donations. To donate, please visit: www.gutenberg.org/donate.

Section 5. General Information About Project Gutenberg electronic works

Professor Michael S. Hart was the originator of the Project Gutenberg concept of a library of electronic works that could be freely shared with anyone. For forty years, he produced and distributed Project Gutenberg eBooks with only a loose network of volunteer support.

Project Gutenberg eBooks are often created from several printed editions, all of which are confirmed as not protected by copyright in the U.S. unless a copyright notice is included. Thus, we do not necessarily keep eBooks in compliance with any particular paper edition.

Most people start at our website which has the main PG search facility: www.gutenberg.org.

This website includes information about Project Gutenberg, including how to make donations to the Project Gutenberg Literary Archive Foundation, how to help produce our new eBooks, and how to subscribe to our email newsletter to hear about new eBooks.

24

[back](#)

I

II

III

IV

[back](#)

| | | | | | | | |
|----|-----|-----|------|-----|------|----|----|
| 1 | 2 | 3 | 4 | 5 | 6 | 8 | 10 |
| I | II | III | X | IX | IIIX | XX | ? |
| 3 | 233 | 333 | 2333 | 人I | 2II | | |
| 20 | 50 | 60 | 70 | 100 | 200 | | |

[back](#)

1 11 + 6 6 6 6 6 6 6 6 6 6

1 2 4 6 50 50 200 200 200

[back](#)


| | | | | | | | | | |
|---|---|---|---|---|---|---|----|----|----|
| — | = | ⊥ | ⊥ | 4 | 7 | ρ | α | α | α |
| 1 | 2 | 4 | | 6 | 7 | 9 | 10 | 10 | 10 |

| | | | | | | | | |
|----|----|----|-----|-----|-----|-----|-----|-----|
| o | + | ∞ | 2 | π | 3 | 4 | 5 | 6 |
| 20 | 60 | 80 | 100 | 100 | 100 | 200 | 200 | 400 |

| | | | | | | |
|-----|------|------|------|------|--------|--------|
| 24 | 7 | 8 | 9 | 10 | 11 | 12 |
| 700 | 1000 | 1000 | 4000 | 6000 | 10,000 | 20,000 |

[back](#)

Nānāghāt Inscriptions.



[back](#)

| | | | | | | | | | |
|------|------|------|------|------|--------|-----|-----|----|---|
| — | = | ≡ | 𐤀 | 𐤁 | 𐤂𐤃 | 𐤄 | 𐤅 | 𐤆𐤇 | 𐤈 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | |
| 𐤉 | 𐤊𐤋 | 𐤌 | 𐤍 | 𐤎 | 𐤏 | 𐤐 | 𐤑𐤒 | 𐤓 | |
| 10 | 10 | 20 | 40 | 70 | 100 | 200 | 500 | | |
| 𐤔 | 𐤕 | 𐤖 | 𐤗 | 𐤘𐤙 | 𐤚𐤛 | 𐤜 | | | |
| 1000 | 2000 | 3000 | 4000 | 8000 | 70,000 | | | | |

[back](#)

1 2 3 4 5 6 7 8 9 10 20 30 40 50 60 70 80 90 100 200 1000

[back](#)

7 11 10 111

[back](#)

I II III X IX II X XX 2 3 233333 41 711

[back](#)

I II + 6

6

4

[back](#)

-- 7 47 2α0

[back](#)

1 0 HHT

—=≡¥ ¢ ¤ 7 4 } α θ ×

7 7 9

[back](#)

—=≡ƒŀƶǁǂǃǄǅǆǇǈǉǊǋǌǍǎǏǐǑǒǓǔǕǖǗǙǚǛǜǝǞǟǠǡǢǣǤǥǦǧǨǩǪǫǬǭǮǯǰǱǲǳǴǵǶǷǸǹǺǻǼǽǿǾǠǡǢǣǤǥǦǧǨǩǪǫǬǭǮǯǰǱǲǳǴǵǶǷǸǹǺǻǼǽǿǾ

[back](#)

_ = ≡ 7 F 6 7 8 P ∞ θ ʌ ʒ 6 x ∞ ⊕

[back](#)

~ = ୫୪୫୩୫୩୦୩

தேவ அருள்

[back](#)

[illegible]

[back](#)

~ = 2 16B 7 4 8 5 4 0 2

[back](#)

ဒါနု နှစ် ၁၀၀ နှစ်

[back](#)

ከ ዓገዳ

[back](#)

494

[back](#)

21 (X) -

[back](#)

431

[back](#)

77=

[back](#)



[back](#)

225

[back](#)



[back](#)

2

[back](#)

i

[back](#)

back



[back](#)

~~_____~~
~~_____~~
[back](#)



[back](#)

—

—

—

[back](#)



[back](#)



[back](#)

4

[back](#)

44

[back](#)



[back](#)

~~_____~~

~~_____~~

[back](#)

Z

[back](#)

—

—

—

[back](#)



[back](#)



[back](#)



[back](#)



[back](#)



[back](#)



[back](#)

7

[back](#)

7

[back](#)



[back](#)

0 1 2 3 4 5 6 7 8 9 10

[back](#)

o ၅ ဩ၇၄၆ ခုနှစ်၇၀

[back](#)

୦ ୨ ୩ ୪ ୫ ୬ ୭ ୮ ୯ ୧୦

[back](#)

உருகிறது என்பது

[back](#)

° 7' 2' 3' 4' 5' 6' 7'

[back](#)

ମେଲେ ମେଣ୍ଟିଲେ ଚାଲୁଛି ମେ

[back](#)

പ രു ര ഖ ഉ യ ഹ ണ ധ

[back](#)

୧ ୨ ୩ ୪ ୫ ୬ ୭ ୮ ୯ ୧୦

[back](#)

۱ ۲ ۳ ۴ ۵ ۶ ۷ ۸ ۹ .

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

- ३३ २५ १८ ४७.

[back](#)

— # 4 9 e 3

[back](#)

2

21

27

[back](#)

84

7 2 3 0

[back](#)

3 851

2 7 0

[back](#)

၇ ၃ ၃ ၄ ၅ ၆ ၇ ၈ ၉ ၀

[back](#)

~ 7 3 8 4 4 2 7 ~ 0

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

1 2 3 4 5 6 7 8 9

[back](#)

1 2 3 4 5 6

0

[back](#)

7 3 3 0 4 5 2 4 1 0

[back](#)

9 2 3 4 5 6 7 8 9 0

[back](#)

0 9 3 4 5 1 3 9 .

[back](#)



[back](#)



[back](#)

YYY

[back](#)

Y Y Y Y

[back](#)

εφ

[back](#)

270

[back](#)



[back](#)

④

[back](#)



[back](#)

9 1Vξ Δ γ* μρ10.

[back](#)



[back](#)



[back](#)



[back](#)



[back](#)

5

[back](#)

5

[back](#)

٩ ٨ ٧ ٦ ٥ ٤ ٣ ٢ ١

[back](#)

9 8 7 6 4 f t z s

[back](#)

0 9 1 v 4 8 5 3 2 1

[back](#)

١ ٢ ٣ ٤ ٥ ٦ ٧ ٨ ٩ .

[back](#)

1 2 3 4 5 6 7 8

[back](#)

1 8 9 6 5 3 2 1

[back](#)

1
2
3
1, 4
22
32
31
11, 44
✓
✓

1
2
3, 3
2, 2
22
32
32
22
✓
✓

[back](#)

p

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

1 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000 1001 1002 1003 1004 1005 1006 1007 1008 1009 1010 1011 1012 1013 1014 1015 1016 1017 1018 1019 1020 1021 1022 1023 1024 1025 1026 1027 1028 1029 1030 1031 1032 1033 1034 1035 1036 1037 1038 1039 1040 1041 1042

[back](#)

1 6 3 9 4 6 1 8 2

[back](#)

1 2 3 4 5 6 7 8 9

[back](#)

1 6 3 4 5 7 8 9

[back](#)

1 7

4 6 1 8 2

[back](#)

z m p h L V 8 b

[back](#)

1 ਵ ਮ ਬ ਯ ਗ ਲ ੜ ੳ

[back](#)

I t \$ e y f ^ 8 9 @

[back](#)

I 7 H B h L V 8 6 @

[back](#)



[back](#)



[back](#)

| | | | | | | | | | | | |
|----|---|---|---|---|---|---|---|---|---|------------------|-----------|
| 1 | I | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 976 |
| 2 | T | W | V | P | Y | O | V | 3 | S | NS ¹⁴ | X |
| 3 | / | 6 | 7 | 8 | 9 | 4 | ^ | 8 | 2 | | 077 |
| 4 | I | 6 | N | 9 | 4 | L | ^ | 8 | 9 | 0 | XI |
| 5 | I | 6 | S | B | 4 | L | ^ | 8 | 9 | 0 | XI |
| 6 | I | 6 | H | B | 4 | L | ^ | 8 | 9 | 0 | XI |
| 7 | I | 6 | S | B | 4 | L | ^ | 8 | 9 | 0 | XI |
| 8 | / | 6 | X | 1 | 4 | L | ^ | 8 | 9 | | XI-XII |
| 9 | 1 | 6 | N | 8 | 4 | L | ^ | 8 | 9 | | XI-XII |
| 10 | 1 | | 3 | 8 | 4 | L | ^ | 8 | 9 | | XI? |
| 11 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | | XII |
| 12 | / | 6 | 4 | 8 | 4 | L | ^ | 8 | 9 | | XII |
| 13 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | X ¹⁴ | XII 2 1/2 |
| 14 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | | c. 1200 |
| 15 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | | c. 1200 |
| 16 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | | ? |
| 17 | | 6 | S | 1 | 4 | L | ^ | 8 | 9 | | ? |
| 18 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | | ? |
| 19 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | 0 | XV |
| 20 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | | XV |
| 21 | 1 | 6 | H | 8 | 4 | L | ^ | 8 | 9 | 0 | XVI and |

[back](#)

5'2'2'1'0

[back](#)

1 2 3 4 5 6 7 8 9 0
Y

[back](#)

Z

[back](#)

3

[back](#)

Cz7

[back](#)

Cyo

[back](#)

CSA

[back](#)

cc2

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

1 2,2 1 24,4 6 7 8 9 0

[back](#)

1 2,3 4,5 6 7,8 9 0

[back](#)

1. 7. 3 2 4 6 1. 8 9 0

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

1 2,73.3 24.96 1.2 8 9 0.0

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

v — 1028416.
 t — 422288
 b — 262122.
 bi — 131011.
 q — 64436.
 p — 32168.
 o — 16382.
 n — 8192.
 m — 2096
 l — 2028.
 k — 1022.
 i — 412.
 h — 216.
 g — 128.
 f — 62.
 e — 32.
 d — 16.
 c — 8.
 b — 2.
 a — 2

[back](#)

1. 2. 3. 4. 5. 6. 7. 8. 9. 10:~

[back](#)

| | | | | | | | | | | |
|---|-----|------|------|------|------|------|------|------|------|------|
| 1 | .2. | .3. | .4. | .6. | .0. | .1. | .8. | .9. | .10. | 11 |
| 4 | .8. | .12. | .16. | .20. | .24. | .28. | .32. | .36. | .40. | .44. |
| 3 | .0. | .9. | .12. | .15. | .18. | .21. | .24. | .27. | .30. | .33. |

[back](#)

S, J, I, X, t, L, 2.

[back](#)

2, 7, 0, 7, 6, 3, 3, 2, 7, 3, 7, 2
3, 0, 2, 2, 1, 0, 1

[back](#)

~~_____~~

~~_____~~

[back](#)

—

—

—

[back](#)

3

[back](#)

3, 3, 7, 6, 3, 3, 3, 3, 3, 3

[back](#)



[back](#)

4c

[back](#)



[back](#)



[back](#)

9

[back](#)

4

[back](#)

4

[back](#)

À, Á, Â, Ã, Ä, Å, Æ, Ç, È, É, Ê, Ë

Ì, Í, Î, Ï, Ñ, Ò, Ó, Ô, Õ, Ö, Ø

Ù, Ú, Û, Ü, Ý, Þ, ß, à, á, â, ã

[back](#)

q, q, g, 2, 9, 4, 4, 7, 9, 7
7, 2, 7, 9, 5, 9, 4, 8, 9, 6, 7, 5
8, 9, 4, 2, 5, 2, 7

[back](#)

6, 2, 4, 5, 6, 6, 6, 8

[back](#)

1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1

[back](#)

8, 8, 8, 8, 8

[back](#)




[back](#)

9. 7. 2; 2. 2. 7. 9. 9. 2. 2.

[back](#)

$\odot$, $\odot$, ϕ , θ , θ , θ

[back](#)



[back](#)



[back](#)

α β γ δ ε ζ η θ

ι κ λ μ ν ξ ο π ρ

σ τ υ φ χ ψ ω

[back](#)



[back](#)



[back](#)



[back](#)

क

1

क१

10^2

क२

10^4

क३

10^6

क४

10^8 , etc.,

[back](#)



[back](#)

9

[back](#)



[back](#)

1 μ.

[back](#)



[back](#)

9

[back](#)



[back](#)



[back](#)

.O.
[back](#)

⊙HKH

[back](#)



[back](#)



[back](#)

g ^ v y o s μ p i

[back](#)



[back](#)

ṽ

[back](#)



[back](#)

1 2 3 4 5 6 7 8 9 0

[back](#)

ø 9 8 7 6 5 4 3 2 1

[back](#)

.4.

[back](#)



[back](#)



[back](#)



[back](#)

J.S.O.

[back](#)

z3

[back](#)



[back](#)