

BULLETIN No. 3
UTAH ENGINEERING EXPERIMENT STATION
JANUARY, 1910

The Construction and Maintenance
OF
EARTH ROADS

BY

RICHARD R. LYMAN
PROFESSOR OF CIVIL
ENGINEERING



STATE SCHOOL OF MINES
UNIVERSITY OF UTAH

SALT LAKE CITY, UTAH

BULLETIN No. 3
UTAH ENGINEERING EXPERIMENT STATION
JANUARY, 1910

The Construction and Maintenance
OF
EARTH ROADS

BY

RICHARD R. LYMAN
PROFESSOR OF CIVIL
ENGINEERING



STATE SCHOOL OF MINES
UNIVERSITY OF UTAH

SALT LAKE CITY, UTAH

The Project Gutenberg eBook of The construction and maintenance of earth roads

This eBook is for the use of anyone anywhere in the United States and most other parts of the world at no cost and with almost no restrictions whatsoever. You may copy it, give it away or re-use it under the terms of the Project Gutenberg License included with this eBook or online at www.gutenberg.org. If you are not located in the United States, you will have to check the laws of the country where you are located before using this eBook.

Title: The construction and maintenance of earth roads

Author: Richard Roswell Lyman

Release date: September 20, 2022 [eBook #69016]

Most recently updated: October 19, 2024

Language: English

Original publication: United States: State School of Mines, University of Utah, 1910

Other information and formats: www.gutenberg.org/ebooks/69016

Credits: Charlene Taylor and the Online Distributed Proofreading Team at <https://www.pgdp.net> (This file was produced from images generously made available by The Internet Archive/American Libraries.)

*** START OF THE PROJECT GUTENBERG EBOOK THE
CONSTRUCTION AND MAINTENANCE OF EARTH ROADS ***

UNIVERSITY OF UTAH

“The Head of the Public School System of the State.”

The University of Utah includes the School of Arts and Sciences, the State Normal School, the State School of Mines, and a School of Medicine.

School of Arts and Sciences.

The School of Arts and Sciences offers courses in:

1. General Science.
2. Liberal Arts.
3. Commerce and Industry.
4. Government and Administration.
5. Journalism.
6. Law (first two years).
7. Graduate Courses.

State Normal School.

The Normal School offers:

1. Science—Normal Course.
2. Arts—Normal Course.

State School of Mines.

The State School of Mines offers Courses in:

1. Mining Engineering.

2. Electrical Engineering.
3. Civil Engineering.
4. Mechanical Engineering.
5. Chemical Engineering.
6. General Engineering.
7. Irrigation Engineering (in connection with
the Agricultural College of Utah).
8. Graduate Courses.

“STUDY MINING IN A MINING COUNTRY.”

School of Medicine.

The School of Medicine offers:

1. Arts—Medical Course (four years).

The proximity of great mines, reduction works of various kinds, and power houses for the generation of electricity afford excellent advantages for thorough and practical work in all the engineering courses. The shops and the various laboratories are thoroughly equipped.

The library is the largest and best in the state.

The faculty includes graduates from the best universities in America and Europe.

The Catalogue, which gives full information concerning courses, etc., will be sent free upon request.

UNIVERSITY OF UTAH.

Salt Lake City, Utah.

BULLETIN No. 3

UTAH ENGINEERING EXPERIMENT STATION

JANUARY, 1910

**The Construction and Maintenance
OF
*EARTH ROADS***

BY
RICHARD R. LYMAN
PROFESSOR OF CIVIL
ENGINEERING



STATE SCHOOL OF MINES
UNIVERSITY OF UTAH
SALT LAKE CITY, UTAH

Introduction

The Utah Engineering Experiment Station was established by an Act of the State Legislature in March 1909, as a department of the State School of Mines, the engineering college of the University of Utah. The station is authorized "to carry on experiments and investigation, pertaining to any and all questions and problems that admit of laboratory methods of study, and a solution of which would tend to benefit the industrial interests of the State, or would be for the public good."

Just now in the State of Utah the problem of good roads—how to construct and maintain them—is prominent in the public mind. As a contribution to the discussion of this problem Professor Richard R. Lyman of the Engineering Experiment Station staff offers the subject matter of this bulletin. The publication and distribution of such an article is clearly within the province of the privileges of the station. It is hoped that this contribution will help solve the problem of good roads in Utah.

Bulletin No. 1, now out of print, was on "Tests on Utah Brick," and No. 2 was on "Tests of Macadam Rock." The next bulletin to be published will be tests on the cements on the Utah Market. So long as they last bulletins of this Station will be sent free, upon application.

JOSEPH F. MERRILL, DIRECTOR.

UTAH ENGINEERING EXPERIMENT STATION
State School of Mines, University of Utah

The Construction and Maintenance of Earth Roads

By Richard R. Lyman

*Prof. of Civil Engineering, University of Utah,
and Vice-Chairman State Road Commission*

Great institutions, great movements, and great advances in science grow, they do not spring into existence instantly. So it will be with the installation of good roads—the system must grow. No legislation can be enacted that will bring into existence suddenly a fine system of well made and well maintained highways. The beginning must be at the bottom where even the best legislation can give no more than a good beginning and then, by the vigorous application of work and wisdom, a system of roads may be constructed that will be not only the pride of the citizens of the state, but a source of education, prosperity, and pleasure. Education, because good roads will make it easy for boys and girls to get to the grade schools, and young men and young women to the high schools at all seasons of the year; prosperity, because farm products can be put in the market when the price is highest, and teams can be used profitably at other work when they cannot be used on the farm; pleasure, because of the comfort with which, at all times, those in the country can travel, thus making it possible to have and enjoy the many social advantages offered in the club, the church, and the neighbor's home.

When, by enacting into law the best road legislation it can, the legislature has made a beginning, it is then the duty of the people to begin to learn more concerning roads and their maintenance. It may be well, in the imagination, to picture hard roads leading everywhere, but, advocating their construction at once and working ever so vigorously to this end, will probably delay rather than advance this work, for the reason that the cost of their maintenance is such that, if these roads were already constructed, it would be impossible in this state at present to keep them in good condition.

It will take years of education to teach the people to place that value upon good roads that will induce them to spend, both in the construction and maintenance of highways, even a small fraction of the sum it would require to keep in repair an extensive system of hard roads in Utah. Farmers see at once when their actual cost is presented, that to make such outlays is, for them, utterly and absolutely impossible.

First in the natural development of a system of highways comes the earth road, and since a good road of this character is the very best foundation for all kinds of better highways, it may be considered, not only as a road complete in and of itself, but also as an important part of every good road. When the people throughout the state have been so taught and trained in road construction that they can and do actually construct and maintain earth roads in good condition, the foundation will then be laid for some, or in fact for any better road, and the time will have arrived in which the construction of roads with hard surfaces of some sort can be taken up appropriately and perhaps effectively.

The discussion on roads, road construction, and road maintenance of the past few years has pretty well demonstrated that people generally are of the opinion that the roads should be improved and that with the general improvement of the roads will come a corresponding improvement in the prosperity and general uplifting of the people in the country districts; yet, while the opinion is general that roads should be improved, there is a vast difference of opinion as to what is the best method to follow to reach the desired end.

Hard Roads.

Men with money and automobiles are vigorously urging that road-building materials everywhere be tested, that road graders, stone crushers, and other expensive road-building machinery be purchased, and that the preparation for commencing road construction be begun at once. In short, they are conducting a vigorous campaign in the interest of hard roads—and in so doing, they may defeat their own cause now as they have done in the past. “When the hard road enthusiast began to tell the farmer how much it cost him to haul his produce to market,” says Professor Baker, “and how much he could save by the construction of hard roads, he knew instinctively

that the conclusions were ridiculous, and the continual harping upon these false statistics and absurd estimates led him to believe that an attempt was being made to force hard roads upon him, whether or no, and his attitude changed from one of indifference to one of open hostility to all road improvement.”^[1]

What, then, should be the line of procedure? “Unless a community is willing and able to maintain the earth roads in a reasonably good condition,” says Professor Baker again, “it is useless to expect that it will be willing or able to support a high class wagon road; and therefore, the dissemination of correct information concerning the construction and care of earth roads is politically, economically, and physically the first step towards a better form of construction.”^[2]

An earth road to be a good road must be “dry, smooth, and hard.” These three conditions could be maintained with comparative ease if the earth road could be protected from water, which is its greatest destroyer and one of the most important factors in the destruction or deterioration of all roads.

Since in Utah the rainfall is very small, compared with that in the Eastern states and in the states of the Mississippi valley, the road problem is a much simpler one here than there.

Drainage.

If not actually the most important, certainly the drainage of a road is one of the most important factors to be considered in the construction or in the maintenance of that road.


A system of underdrainage is a necessity, where the surface water comes near the top of the ground on which a road is to be built, and drain tile laid longitudinally on boards to a carefully and properly made grade will carry such water away. Fortunately however, for the builders of roads in Utah there are comparatively few such places where roads need to be maintained in this state. Drain tile, however, laid in soft material, without the use of a board or plank to keep the ends of the individual pieces of pipe in line, is practically valueless.

Standard Cross-Sections.

It is a small amount of precipitation or rainfall only that the road builder here must take care of. Very wisely the last legislature passed a law establishing standard cross-sections for the roads in this state. Figures [1](#), [2](#), [3](#), [4](#), [5](#) and [6](#) show in a clearer way what these cross-sections are, than these can be shown in the law by the use of words only.


The elevation of the crown of the road above the fence line varies from four inches to eighteen inches, the amount depending on the width of the street, and the depth of the drain ditches on the sides of the roadway is as shown some two feet below the grade of the fence line.

The roadways and sidewalks as the figures giving the cross-sections show, all have such slopes, that water falling upon these surfaces will flow quickly into the drain ditches.




Two Rod Lane

Fig. 1




Four Rod Street

Fig. 2



Five Rod Street

Fig. 3



Six Rod Street

Fig. 4


Road Grades.

Some of our country roads in Utah have been very well constructed as far as the cross section is concerned, but no particular attention has been paid to the grade of the road in the direction of its length except when work has been done to reduce the grade on steep pitches.

Roads should have a grade or slope of about 1 to 80, or $1\frac{1}{4}$ per cent, in the direction of their length, so that water will not remain in any small ruts that may be formed, but will flow along them to a point where it will flow from the rut into the drain ditch.

Drain Ditches.


The slope of the drain ditches should be the same as the slope of the road and their cross-sections should be practically the same at all points, so that all the water flowing into them will flow promptly to a nearby cross drain that will carry it entirely away from the road.



Seven Rod Street

Fig. 5

In many cases unsightly, uneven holes are dug on either side of the roadway in order to secure material for making the crown of the road and the water, which gathers in these, keeps the foundation under the road always soft.



Eight Rod Street

Fig. 6

Cross-drains should be provided at all “low places.” Culverts should be constructed under the roadway at these points to carry the water from the upper to the lower side of the road.

If storm water is carried quickly well away from a road, the condition of that road for traveling will be greatly improved. But rain and other storms do not generally put roads into their worst condition. This comes in the spring time, when the frost “comes out of the ground.” Observation shows, however, that not much frost gets into dry ground, so that if a road is properly maintained during the fall, and the fall and winter storm water is promptly drained well away from the road, frost can do the road very little damage. It cannot loosen up the earth, rendering it soft and mushy, as it does earth that is filled with moisture. To make good earth roads in the spring, therefore, requires good drainage and careful maintenance during the fall and winter.

The average country road in Utah can be constructed with its center raised six inches for from \$40.00 to \$50.00 per mile. To raise the crown of the road six inches more above the sides will cost about the same amount.

Maintenance.


Even more important than a proper construction of a road is the proper maintenance of that road. There is a difference, too, between maintenance

and repair. The one keeps the road in good condition always, the other puts it in good condition occasionally. “What a minute and a shovelful of earth will do as maintenance may require loads of earth and hours of time as repairs.”

The road grader with its inclined blade, its four wheels, and its comparatively complex machinery, when used for maintaining or repairing an earth road merely cuts off the high places and deposits in the low places, the earth thus cut away.

Devices for Maintenance.

The leveler, a frame-work of planks held on edge and drawn in the direction of the length of the road with three or four of the timbers at right angles to this direction, renders good service by taking off the high places and filling up the low ones. The weight of this device and the greater width of its timbers, make it pack the earth into low places better than the road grader does. But since the blade of the grader can be set at such an angle with the direction of the road that it will constantly carry the earth from the outer edge toward the crown of the road, it makes the center of the road high, as it should, while the leveler makes it flat.




Plan of Split-Log Road Drag

Fig. 7

The triangular shaped drag has, to a certain degree, the good qualities of both the devices just named, but what is generally regarded as the best device for repairing and maintaining earth roads is the King road drag or the split-log drag.

Split-Log Drag.

A split-log drag actually constructed of a log split in two is shown in [Fig. 8](#); while this same device, constructed of planks, is shown in [Fig. 9](#).




Split-Log Road Drag

Fig. 8

Practically all the good qualities of all the other devices used up to this time for maintaining earth roads are found in the split-log drag.

[Fig. 7](#) shows the drag with the doubletree attached, and therefore it shows the position of the team drawing the drag with respect to the drag itself. The diagonal brace between the two heavy timbers near the forward end is used to keep the end of the timber which travels ahead from vibrating. The chain by which this device is drawn may be attached directly to the front timber or it may be extended through holes in this timber and be attached to the timber in the rear. If, instead of passing through the hole A

([Fig. 9.](#)) the chain is carried over this timber and attached to the timber B, more room will thus be made for earth in front of the drag to slide under the chain.



Plank Road Drag

Fig. 9

The angle the sides of the drag make with the direction of the road can be varied at pleasure by attaching the doubletree to different links of the chain.

The teamster will soon learn by experience that changing his position as he rides on the drag will affect the work of the drag very materially, and he will soon learn also how and when to change his position in order to obtain the best results.

Importance of Using Drag.

The proper and best use of this drag or the careful maintenance of the ordinary earth road is perhaps the most important lesson in “roads” Utah people have to learn at this time. It is more important than the actual grading or construction of these roads.

When to Use Drag.

This drag should be used upon the road after every heavy rain and after every big thaw as faithfully as the successful dry-farmer harrows his crop at these same times.

Fortunately, too, the road dries faster than the farming land, so that the work on the roads can be completed before teams can, to advantage, be taken upon the farms to work.

Professor Ira. O. Baker of the University of Illinois, in an excellent article on the maintenance of roads in the Transactions of the American Society of Civil Engineers, Vol. LXI., gives a description and also drawings of the split-log drag. His drawings are reproduced in Figs. [7](#), [8](#), and [9](#). He describes the drag as follows:

“Farmers in different parts of the country for many years, have used various devices occasionally in smoothing the surface of the earth roads; but of all these, none seems to have devised a better form of machine or been more persistent and intelligent in its use than Mr. D. Ward King, of Maitland, Mo. Mr. King devised what he calls the split-log drag. A plan of the split-log drag as shown in [Fig. 7](#), and [Fig. 8](#) is a perspective view. The drag may be made from a log ten or twelve inches in diameter and from seven to nine feet long. A light wood, like elm, is preferable to a heavy one, like oak. The cross braces may be round or square sticks from three to four inches in diameter, the ends fitting into two-inch auger holes. A board, not shown in the cut, is laid upon the cross-pieces for the driver to stand upon. The drag may also be made of two pieces of plank, ten or twelve inches wide and from seven to nine feet long. The plank drag is shown in [Fig. 9](#). It is wise to reinforce the wide planks with either a 1 by 6-in. or a 2 by 6-in. strip as shown in [Fig. 9](#).

The drag is drawn by two horses, and its length should be proportional to the weight of the horses. A drag seven feet long is about right for a team

of 1200-lb. horses, and one nine feet long for two 1600-lb. horses. The driver rides upon the drag, and varies its effect by his position upon it. The drag does the best work when the soil is moist, but not sticky. If the roadway is badly rutted and full of holes, it is well to drag it when the surface is slushy.”

Common Mistakes With Drag.

Mr. King, the government expert on the split-log drag, says:^[3] “Two mistakes are commonly made in constructing a drag. The first lies in making it too heavy. It should be so light that one man can easily lift it. Besides, a light drag responds more readily to various methods of hitching and to the shifting of the position and weight of the operator. *** A drag can be made heavier at any time by proper weighting.

The other mistake is in the use of square timbers, instead of those with sharp edges, whereby the cutting effect of sharp edges is lost and the drag is permitted to glide over instead of to equalize the irregularities in the surface of the road. ***”

Iron on Drag.

“A strip of iron about 3½ feet long, three or four inches wide and one-quarter of an inch thick may be used for the blade. This should be attached to the front slab so that it will be one-half inch below the lower edge of the slab at the ditch end, while the end of the iron toward the middle of the road should be flush with the edge of the slab. The bolts holding the blade in place should have flat heads and the holes to receive them should be counter-sunk.

If the face of the log stands plumb, it is well to wedge out the lower edge of the blade with a three-cornered strip of wood to give it a set like the bit of a plane.”

Mr. Chas. H. Hoyt of the U. S. Office of Public Roads, says,^[4] “The split-log drag is a very simple affair, costs \$2.00 to build, is economical to use, and every farmer or teamster living along a country road, who is

interested in having the road past his place kept in good condition and is also interested to keep highway taxes down, should have a split-log drag.”

To maintain in this way all the important rural roads will make it necessary to put to work many of the teams that are idle when this work should be done. Perhaps some system can be devised that will require each farmer to maintain that portion of road in his neighborhood, and for so doing he may be exempt from paying a cash road tax. Those who prefer to do so can pay the tax in money, and the funds thus derived can be used to pay for the general supervision of this maintenance-work, and for the actual work of maintenance on the roads where farmers do not care to do the work themselves.

Earth or Macadam Road.

Since the hard, dry, smooth earth road is an excellent road, and since it is possible with reasonable effort to induce the people to construct and maintain such a road from one end of this state to the other, with a good many side roads of the same sort on the way, why not strive for this possible end, instead of attempting to get a few miles of hard road constructed? Such a road could be pointed to with pride by every citizen of the state in the presence of any citizen of any other state. Would it not be better to have a well constructed and carefully maintained earth road from Logan to St. George, a distance of 350 miles, than to have the best tar macadam road for a distance of 37 miles between Ogden and Salt Lake City? The longer road would cost \$25,000 with many interested and willing people to pay for it, while the other would cost thirty-seven times as much with fewer people personally interested in it. Every farmer between Logan and St. George drives upon the public highway, while many persons in the larger cities rarely, if ever, do.

Cost of Roads.

An ordinary macadam road two rods wide costs about \$20,000 per mile; a tar macadam road about \$25,000 per mile; an asphaltum pavement some \$44,000 per mile; a gravel road, covered with gravel one foot deep, costs

from \$1,600 to \$5,000 per mile, and the cost of constructing an earth road the same width varies from \$40 to \$100 per mile.

While the figures given are the costs of constructing various roads two rods wide, this occasion is taken to emphasize the fact that a road sixteen feet wide is broad enough in most country districts, while in sparsely settled parts even narrower roads will answer all actual needs very well.

Ordinary Macadam.

Ordinary macadam pavement is composed of carefully selected stone and gravel thoroughly rolled into a compact mass, with the material so graded that the coarsest stones are on the bottom and the finer binding material is on the top. Such a roadway proved very satisfactory until the general advent of the automobile. In order to resist the digging or scratching effect of the driving wheels of high speed motor cars, which is technically called the shear, it is necessary to use tar or some other binding material for holding the particles of stone more firmly together.

Tar Macadam.

Tar macadam roads are constructed the same as other macadam roads, except that the top layers of broken stone are covered with hot tar before they are rolled into place.

Costs Compared.

If \$70 per mile be taken as the cost of constructing an earth road two rods wide, the cost of building one mile of gravel road will build some fifty miles of earth road; one mile of ordinary macadam will build 300 miles of earth road; one mile of tar macadam will build 360 miles of earth road; and one mile of asphalt pavement will construct 600 miles of earth road.

The Earth Road a Portion of Better Roads.

An important argument in favor of the earth road is the fact that when it is laid out and constructed, it is the beginning of a first-class gravel road, a first-class macadam road, or a first-class tar macadam road, so that by getting the earth road made, the individual interested primarily in the construction of hard roads has succeeded in getting the hard road well begun.

Roads in Sand and Soft Clay.

While nearly everywhere in Utah the soil is such that it will make a good earth road, there are parts in which the soft clay is filled with alkali, and there are other parts where there are extensive stretches of sand. Neither of these alone can be made into an earth road that will be a good, passable road all the year round. The sand road is best in wet weather, while the alkali road is best in dry weather. If, however, the soft clay and the sand are so mixed on the road that the clay just fills the openings or interstices between the grains of sand, and yet this quantity is not so large as to keep the grains of sand from touching or coming in contact with one another, the road, if properly and constantly maintained, will be a good one.

Cost of Maintenance.

Since proper maintenance is an important part of the work on ordinary roads, its cost will be considered briefly.

The repairs and maintenance on an asphalt pavement cost from 9 to 60 cents per square yard annually, or for a two rod road the cost is from \$1,750 to \$11,600 per mile per year; on a tar macadam road the cost is from \$2,000 to \$4,000 per mile per year; on a gravel road it is about \$40 per mile per annum, while for \$5 per mile per year an earth road can be kept in a condition of repair that will surprise those who have not used the split-log drag on such a road.

As already stated, narrower roads will answer all necessary demands in many parts, and maintaining such will reduce the cost proportionately. A well kept narrow road is infinitely better than a broad one in bad condition.

Earth Roads Poorly Kept.

Concerning the maintenance and the construction of roads, Mr. Charles H. Hoyt of the United States Office of Public Roads, writes:^[5] “It is sad when we have to say that because of neglect the roads that have already been built have been allowed to go to pieces and have not been properly maintained. Even our ordinary dirt roads are horrible examples of this statement.”

On the value to a community of good roads, Mr. Hoyt says, in the same article: “Any country which longer continues to insist upon remaining stagnant concerning highways, will soon be classed behind the times and avoided by progressive citizens.”

Mr. D. Howard King, Expert on Split-log Drag, Office of Public Roads, has prepared a bulletin called Farmers’ Bulletin, No. 321, on “The Use of the Split-Log Drag on Earth Roads.” All who are interested in this subject should secure a copy of this excellent paper from the United States Department of Agriculture, Washington, D. C., and make a careful study of the same.

Drag Reduces Dust.

On the use of this drag the bulletin says, in part: “Clay, when mixed with water and thoroughly worked, becomes remarkably tough and impervious to water. If compacted in this condition it becomes extremely hard. Another valuable result of dragging is the reduction of dust, for the particles of clay adhere so tenaciously that there is but little wear when the surface is smooth. Dust on an earth road is due to the breaking up under traffic of the frayed and upturned edges of ruts and hoof prints. If the surface is smoothed after each rain and the road dries hard and even, no edges are exposed to crushing, and the only dust which forms is that due to actual wear of the road surface.”

Examples and Their Cost.

The bulletin quotes Mr. F. P. Sanborne^[6] as follows: “The least expense per mile (for dragging) was about \$1.50; the greatest, a little over \$6; the average expense per mile for five and one-half miles, a little less than \$3.” Continuing, Mr. Sanborne says: “The writer has lived by this piece of road all his life, and although we have had the extremes of weather this season, both wet and dry, not for forty years has the road in question been so free from mud and dust. Parties who have known the road all their lives are agreed that it never was in so good a condition a season through.”

“The total expense for twelve months on twenty-eight miles of road in Iowa,” continues Mr. Hoyt, “averaged \$2.40 per mile, and the roads were reported to have been ‘like a race track’ the larger portion of the year.

A number of farmers in Ray county, Missouri, employed one of their number to drag a five-mile stretch. He received compensation at the rate of \$3 per day. When the end of the year came and a settlement was made, the cost for the year was found to be \$1.66 per mile. The road is a tough clay, and my informant declares it was always much better than the other roads in the neighborhood.

Prof. William Robertson of the Minnesota Agricultural station, after a year’s experience in dragging a ‘main road made entirely of gumbo, without any sand or gravel, and which during the past year has shown no defects either by rutting or development of soft places,’ fixes the cost of the work at not to exceed \$5 per mile.”

Since in Maine, Iowa, Missouri and Minnesota, the four states just referred to, there is a comparatively great annual rainfall, while in Utah the rainfall is comparatively small, the cost of maintaining the earth road in Utah will be correspondingly less and the results will be proportionately greater.

If the state legislature, the Automobile Club of Utah, some other organization or some philanthropic individual, will offer an annual prize of \$1000 to the county actually constructing and maintaining during the year the best five miles of earth road, the number of excellent roads that will be built in the next few years will be a most pleasant surprise to all who are anxious to see good roads constructed.

The better, and, in fact, the best roads will come along naturally after we have a first-class system of earth roads built and well maintained generally throughout the state. When once the efforts of all our good-roads enthusiasts are united on constructing and maintaining first-class earth roads everywhere, the road problem in Utah will be solved, and our road systems will be the pride of the whole state.

What is the State School of Mines?

The State School of Mines is the college of engineering of the University of Utah. It is an organic part of the University and enjoys all the advantages that spring from an intimate connection between a technical college and a modern university.

COURSES.

The school offers seven four-year courses leading to bachelor's degrees, also graduate courses leading to the degree of master of science in several lines of engineering. The seven four-year courses are in MINING ENGINEERING, ELECTRICAL ENGINEERING, CIVIL ENGINEERING, MECHANICAL ENGINEERING, CHEMICAL ENGINEERING, GENERAL ENGINEERING, and IRRIGATION ENGINEERING, the first part of the course in irrigation engineering being given, however, by the Agricultural College at Logan. Graduate courses are offered in each of these lines of engineering.

FACILITIES AND EQUIPMENT.

The school is provided with a first-class equipment to do its work. The laboratories are all well furnished, in this respect ranking with the foremost colleges of the country. The teachers are all specialists and the methods of instruction modern. For mining work the location of the school is unexcelled, Salt Lake City being the center of a great mining region, which makes it easy to provide abundant and inexpensive field work.

EXPENSES.

The expenses at the school are very low, the cost of registration and tuition being from ten to twenty-five dollars per year. The school is certainly among the most inexpensive good engineering colleges in the country for a student to attend.

Catalogues and illustrated circulars are sent free upon request.

**SKELTON PUBLISHING CO.
SALT LAKE CITY**

Footnotes:

[1] Trans. Am. Soc., C. E., Vol. LXI., p. 475.

[2] Trans. Am. Soc., C. E., Vol. LXI., p. 480.

[3] The Use of the Split-Log Drag on Earth Roads, Farmers' Bulletin, 321, U. S. Department of Agriculture, by D. Ward King, pp. 1, 6 and 7.

[4] The Cornell Civil Engineer, December, 1909, p. 81.

[5] The Cornell Civil Engineer, Dec., 1909.

[6] Report of Highway Commission of Maine, 1906, p. 112.

Transcriber's Notes:

The illustrations have been moved so that they do not break up paragraphs and so that they are next to the text they illustrate.

Typographical and punctuation errors have been silently corrected.

*** END OF THE PROJECT GUTENBERG EBOOK THE
CONSTRUCTION AND MAINTENANCE OF EARTH ROADS ***

Updated editions will replace the previous one—the old editions will be renamed.

Creating the works from print editions not protected by U.S. copyright law means that no one owns a United States copyright in these works, so the Foundation (and you!) can copy and distribute it in the United States without permission and without paying copyright royalties. Special rules, set forth in the General Terms of Use part of this license, apply to copying and distributing Project Gutenberg™ electronic works to protect the PROJECT GUTENBERG™ concept and trademark. Project Gutenberg is a registered trademark, and may not be used if you charge for an eBook, except by following the terms of the trademark license, including paying royalties for use of the Project Gutenberg trademark. If you do not charge anything for copies of this eBook, complying with the trademark license is very easy. You may use this eBook for nearly any purpose such as creation of derivative works, reports, performances and research. Project Gutenberg eBooks may be modified and printed and given away—you may do practically ANYTHING in the United States with eBooks not protected by U.S. copyright law. Redistribution is subject to the trademark license, especially commercial redistribution.

START: FULL LICENSE

THE FULL PROJECT GUTENBERG™ LICENSE

PLEASE READ THIS BEFORE YOU DISTRIBUTE OR USE THIS WORK

To protect the Project Gutenberg™ mission of promoting the free distribution of electronic works, by using or distributing this work (or any other work associated in any way with the phrase “Project Gutenberg”), you agree to comply with all the terms of the Full Project Gutenberg License available with this file or online at www.gutenberg.org/license.

Section 1. General Terms of Use and Redistributing Project Gutenberg electronic works

1.A. By reading or using any part of this Project Gutenberg electronic work, you indicate that you have read, understand, agree to and accept all the terms of this license and intellectual property (trademark/copyright) agreement. If you do not agree to abide by all the terms of this agreement, you must cease using and return or destroy all copies of Project Gutenberg electronic works in your possession. If you paid a fee for obtaining a copy of or access to a Project Gutenberg electronic work and you do not agree to be bound by the terms of this agreement, you may obtain a refund from the person or entity to whom you paid the fee as set forth in paragraph 1.E.8.

1.B. “Project Gutenberg” is a registered trademark. It may only be used on or associated in any way with an electronic work by people who agree to be bound by the terms of this agreement. There are a few things that you can do with most Project Gutenberg electronic works even without complying with the full terms of this agreement. See paragraph 1.C below. There are a lot of things you can do with Project Gutenberg electronic works if you follow the terms of this agreement and help preserve free future access to Project Gutenberg electronic works. See paragraph 1.E below.

1.C. The Project Gutenberg Literary Archive Foundation (“the Foundation” or PGLAF), owns a compilation copyright in the

collection of Project Gutenberg electronic works. Nearly all the individual works in the collection are in the public domain in the United States. If an individual work is unprotected by copyright law in the United States and you are located in the United States, we do not claim a right to prevent you from copying, distributing, performing, displaying or creating derivative works based on the work as long as all references to Project Gutenberg are removed. Of course, we hope that you will support the Project Gutenberg mission of promoting free access to electronic works by freely sharing Project Gutenberg works in compliance with the terms of this agreement for keeping the Project Gutenberg name associated with the work. You can easily comply with the terms of this agreement by keeping this work in the same format with its attached full Project Gutenberg License when you share it without charge with others.

1.D. The copyright laws of the place where you are located also govern what you can do with this work. Copyright laws in most countries are in a constant state of change. If you are outside the United States, check the laws of your country in addition to the terms of this agreement before downloading, copying, displaying, performing, distributing or creating derivative works based on this work or any other Project Gutenberg work. The Foundation makes no representations concerning the copyright status of any work in any country other than the United States.

1.E. Unless you have removed all references to Project Gutenberg:

1.E.1. The following sentence, with active links to, or other immediate access to, the full Project Gutenberg License must appear prominently whenever any copy of a Project Gutenberg work (any work on which the phrase “Project Gutenberg” appears, or with which the phrase “Project Gutenberg” is associated) is accessed, displayed, performed, viewed, copied or distributed:

This eBook is for the use of anyone anywhere in the United States and most other parts of the world at no cost and with almost no restrictions whatsoever. You may copy it, give it away or re-use it under the terms of the Project Gutenberg™ License included with

this eBook or online at www.gutenberg.org. If you are not located in the United States, you will have to check the laws of the country where you are located before using this eBook.

1.E.2. If an individual Project Gutenberg electronic work is derived from texts not protected by U.S. copyright law (does not contain a notice indicating that it is posted with permission of the copyright holder), the work can be copied and distributed to anyone in the United States without paying any fees or charges. If you are redistributing or providing access to a work with the phrase “Project Gutenberg” associated with or appearing on the work, you must comply either with the requirements of paragraphs 1.E.1 through 1.E.7 or obtain permission for the use of the work and the Project Gutenberg trademark as set forth in paragraphs 1.E.8 or 1.E.9.

1.E.3. If an individual Project Gutenberg electronic work is posted with the permission of the copyright holder, your use and distribution must comply with both paragraphs 1.E.1 through 1.E.7 and any additional terms imposed by the copyright holder. Additional terms will be linked to the Project Gutenberg License for all works posted with the permission of the copyright holder found at the beginning of this work.

1.E.4. Do not unlink or detach or remove the full Project Gutenberg License terms from this work, or any files containing a part of this work or any other work associated with Project Gutenberg.

1.E.5. Do not copy, display, perform, distribute or redistribute this electronic work, or any part of this electronic work, without prominently displaying the sentence set forth in paragraph 1.E.1 with active links or immediate access to the full terms of the Project Gutenberg License.

1.E.6. You may convert to and distribute this work in any binary, compressed, marked up, nonproprietary or proprietary form, including any word processing or hypertext form. However, if you provide access to or distribute copies of a Project Gutenberg work in a format other than “Plain Vanilla ASCII” or other format used in the official

version posted on the official Project Gutenberg website (www.gutenberg.org), you must, at no additional cost, fee or expense to the user, provide a copy, a means of exporting a copy, or a means of obtaining a copy upon request, of the work in its original “Plain Vanilla ASCII” or other form. Any alternate format must include the full Project Gutenberg License as specified in paragraph 1.E.1.

1.E.7. Do not charge a fee for access to, viewing, displaying, performing, copying or distributing any Project Gutenberg works unless you comply with paragraph 1.E.8 or 1.E.9.

1.E.8. You may charge a reasonable fee for copies of or providing access to or distributing Project Gutenberg electronic works provided that:

- You pay a royalty fee of 20% of the gross profits you derive from the use of Project Gutenberg works calculated using the method you already use to calculate your applicable taxes. The fee is owed to the owner of the Project Gutenberg trademark, but he has agreed to donate royalties under this paragraph to the Project Gutenberg Literary Archive Foundation. Royalty payments must be paid within 60 days following each date on which you prepare (or are legally required to prepare) your periodic tax returns. Royalty payments should be clearly marked as such and sent to the Project Gutenberg Literary Archive Foundation at the address specified in Section 4, “Information about donations to the Project Gutenberg Literary Archive Foundation.”
- You provide a full refund of any money paid by a user who notifies you in writing (or by e-mail) within 30 days of receipt that s/he does not agree to the terms of the full Project Gutenberg™ License. You must require such a user to return or destroy all copies of the works possessed in a physical medium and discontinue all use of and all access to other copies of Project Gutenberg™ works.
- You provide, in accordance with paragraph 1.F.3, a full refund of any money paid for a work or a replacement copy, if a defect in the electronic work is discovered and reported to you within 90 days of receipt of the work.

- You comply with all other terms of this agreement for free distribution of Project Gutenberg™ works.

1.E.9. If you wish to charge a fee or distribute a Project Gutenberg™ electronic work or group of works on different terms than are set forth in this agreement, you must obtain permission in writing from the Project Gutenberg Literary Archive Foundation, the manager of the Project Gutenberg™ trademark. Contact the Foundation as set forth in Section 3 below.

1.F.

1.F.1. Project Gutenberg volunteers and employees expend considerable effort to identify, do copyright research on, transcribe and proofread works not protected by U.S. copyright law in creating the Project Gutenberg™ collection. Despite these efforts, Project Gutenberg™ electronic works, and the medium on which they may be stored, may contain “Defects,” such as, but not limited to, incomplete, inaccurate or corrupt data, transcription errors, a copyright or other intellectual property infringement, a defective or damaged disk or other medium, a computer virus, or computer codes that damage or cannot be read by your equipment.

1.F.2. LIMITED WARRANTY, DISCLAIMER OF DAMAGES - Except for the “Right of Replacement or Refund” described in paragraph 1.F.3, the Project Gutenberg Literary Archive Foundation, the owner of the Project Gutenberg™ trademark, and any other party distributing a Project Gutenberg™ electronic work under this agreement, disclaim all liability to you for damages, costs and expenses, including legal fees. YOU AGREE THAT YOU HAVE NO REMEDIES FOR NEGLIGENCE, STRICT LIABILITY, BREACH OF WARRANTY OR BREACH OF CONTRACT EXCEPT THOSE PROVIDED IN PARAGRAPH 1.F.3. YOU AGREE THAT THE FOUNDATION, THE TRADEMARK OWNER, AND ANY DISTRIBUTOR UNDER THIS AGREEMENT WILL NOT BE LIABLE TO YOU FOR ACTUAL, DIRECT, INDIRECT, CONSEQUENTIAL, PUNITIVE OR INCIDENTAL DAMAGES

EVEN IF YOU GIVE NOTICE OF THE POSSIBILITY OF SUCH DAMAGE.

1.F.3. LIMITED RIGHT OF REPLACEMENT OR REFUND - If you discover a defect in this electronic work within 90 days of receiving it, you can receive a refund of the money (if any) you paid for it by sending a written explanation to the person you received the work from. If you received the work on a physical medium, you must return the medium with your written explanation. The person or entity that provided you with the defective work may elect to provide a replacement copy in lieu of a refund. If you received the work electronically, the person or entity providing it to you may choose to give you a second opportunity to receive the work electronically in lieu of a refund. If the second copy is also defective, you may demand a refund in writing without further opportunities to fix the problem.

1.F.4. Except for the limited right of replacement or refund set forth in paragraph 1.F.3, this work is provided to you 'AS-IS', WITH NO OTHER WARRANTIES OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO WARRANTIES OF MERCHANTABILITY OR FITNESS FOR ANY PURPOSE.

1.F.5. Some states do not allow disclaimers of certain implied warranties or the exclusion or limitation of certain types of damages. If any disclaimer or limitation set forth in this agreement violates the law of the state applicable to this agreement, the agreement shall be interpreted to make the maximum disclaimer or limitation permitted by the applicable state law. The invalidity or unenforceability of any provision of this agreement shall not void the remaining provisions.

1.F.6. INDEMNITY - You agree to indemnify and hold the Foundation, the trademark owner, any agent or employee of the Foundation, anyone providing copies of Project Gutenberg™ electronic works in accordance with this agreement, and any volunteers associated with the production, promotion and distribution of Project Gutenberg™ electronic works, harmless from all liability, costs and expenses, including legal fees, that arise directly or indirectly from any of the following which you do or cause to occur: (a)

distribution of this or any Project Gutenberg work, (b) alteration, modification, or additions or deletions to any Project Gutenberg work, and (c) any Defect you cause.

Section 2. Information about the Mission of Project Gutenberg

Project Gutenberg is synonymous with the free distribution of electronic works in formats readable by the widest variety of computers including obsolete, old, middle-aged and new computers. It exists because of the efforts of hundreds of volunteers and donations from people in all walks of life.

Volunteers and financial support to provide volunteers with the assistance they need are critical to reaching Project Gutenberg's goals and ensuring that the Project Gutenberg collection will remain freely available for generations to come. In 2001, the Project Gutenberg Literary Archive Foundation was created to provide a secure and permanent future for Project Gutenberg and future generations. To learn more about the Project Gutenberg Literary Archive Foundation and how your efforts and donations can help, see Sections 3 and 4 and the Foundation information page at www.gutenberg.org.

Section 3. Information about the Project Gutenberg Literary Archive Foundation

The Project Gutenberg Literary Archive Foundation is a non-profit 501(c)(3) educational corporation organized under the laws of the state of Mississippi and granted tax exempt status by the Internal Revenue Service. The Foundation's EIN or federal tax identification number is 64-6221541. Contributions to the Project Gutenberg Literary Archive Foundation are tax deductible to the full extent permitted by U.S. federal laws and your state's laws.

The Foundation's business office is located at 41 Watchung Plaza #516, Montclair NJ 07042, USA, +1 (862) 621-9288. Email contact

links and up to date contact information can be found at the Foundation's website and official page at www.gutenberg.org/contact

Section 4. Information about Donations to the Project Gutenberg Literary Archive Foundation

Project Gutenberg™ depends upon and cannot survive without widespread public support and donations to carry out its mission of increasing the number of public domain and licensed works that can be freely distributed in machine-readable form accessible by the widest array of equipment including outdated equipment. Many small donations (\$1 to \$5,000) are particularly important to maintaining tax exempt status with the IRS.

The Foundation is committed to complying with the laws regulating charities and charitable donations in all 50 states of the United States. Compliance requirements are not uniform and it takes a considerable effort, much paperwork and many fees to meet and keep up with these requirements. We do not solicit donations in locations where we have not received written confirmation of compliance. To SEND DONATIONS or determine the status of compliance for any particular state visit www.gutenberg.org/donate.

While we cannot and do not solicit contributions from states where we have not met the solicitation requirements, we know of no prohibition against accepting unsolicited donations from donors in such states who approach us with offers to donate.

International donations are gratefully accepted, but we cannot make any statements concerning tax treatment of donations received from outside the United States. U.S. laws alone swamp our small staff.

Please check the Project Gutenberg web pages for current donation methods and addresses. Donations are accepted in a number of other ways including checks, online payments and credit card donations. To donate, please visit: www.gutenberg.org/donate.

Section 5. General Information About Project Gutenberg electronic works

Professor Michael S. Hart was the originator of the Project Gutenberg concept of a library of electronic works that could be freely shared with anyone. For forty years, he produced and distributed Project Gutenberg eBooks with only a loose network of volunteer support.

Project Gutenberg eBooks are often created from several printed editions, all of which are confirmed as not protected by copyright in the U.S. unless a copyright notice is included. Thus, we do not necessarily keep eBooks in compliance with any particular paper edition.

Most people start at our website which has the main PG search facility: www.gutenberg.org.

This website includes information about Project Gutenberg, including how to make donations to the Project Gutenberg Literary Archive Foundation, how to help produce our new eBooks, and how to subscribe to our email newsletter to hear about new eBooks.